

STATE OF UTAH



OFFICE OF THE LIEUTENANT GOVERNOR

CERTIFICATION OF PETITION FOR INCORPORATION

I, Deidre M. Henderson, Lieutenant Governor of the State of Utah, hereby certify that the petition for incorporation filed by petition sponsors of the Echo Canyon Preliminary Municipality Incorporation on May 20, 2025, meets the requirements outlined in §10-2a-507, Utah Code Annotated, 1953, as amended.

In accordance with §10-2a-508, Utah Code Annotated, 1953, as amended, the Office of the Lieutenant Governor hereby incorporates Echo Canyon as a Preliminary Municipality and appoints Craig Weston, Thomas Gottlieb, Trent Arnold, and Jonathan Hoffman as four of the five board members who will serve as a five member council form of government.



IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed the Great Seal of the State of Utah on June 9th, 2025, in Salt Lake City, Utah.

DEIDRE M. HENDERSON
Lieutenant Governor

***CORRECTED* PETITION FOR INCORPORATION
OF ECHO CANYON, A PRELIMINARY MUNICIPALITY**

Hon. Deidre Henderson
Lieutenant Governor of Utah
350 State St. #220
Salt Lake City, UT 84103

May 20, 2025

Via Hand Delivery

On May 5, 2025, the Echo Canyon Petition for Incorporation was rejected due to its failure to comply with Utah Code §10-2a-507(1)(b). Specifically, the descriptions contained in the plat map included in the Petition were different from those described in the initial feasibility request filed on May 1, 2024. In accordance with Utah Code § 10-2a-508(2), the Applicants modified the Petition to correct this deficiency and hereby submit this Corrected Petition for Incorporation of Echo Canyon. In accordance with Utah Code Ann. § 10-2a-508(2)(b), this Corrected Petition is timely as it is submitted within 30 days of the Determination Notice issued by the Office of the Lieutenant Governor on May 5, 2025.

The undersigned (the “**Applicants**” or “**Initial Landowners**”) hereby submit this Petition for Incorporation of Echo Canyon, a Preliminary Municipality (the “**Petition**”) pursuant to the Utah Code Section 10-2a-507(1).

I. Applicants; Contact Sponsor

Applicants / Initial Landowners:

Kane Creek Preservation and Development LLC, a Delaware limited liability company
10446 N. Iverson Ln.
Highland, UT 84003
Phone: 801-318-7100
Email: cnweston@icloud.com

G&H Miller Family Holdings LLC, a Utah limited liability company
405 S. Main St. Suite 800
Salt Lake City, UT 84111
Phone: 801-530-7359

Primary Contact / Sponsor:

Craig Weston
General Partner
Kane Creek Preservation and Development, LLC

Corrected Petition for Incorporation of Echo Canyon, a Preliminary Municipality
Page 2 of 7

10446 N. Iverson Ln.
Highland, UT 84003
Phone: 801-318-7100
Email: cnweston@icloud.com

With a copy to:

Snell & Wilmer LLP
Attn: Wade Budge
Salt Lake City, UT 84101
Phone: 801-257-1906
Email: wbudge@swlaw.com

The above and undersigned Applicants and Initial Landowners represent 100% of the surface property owners within the proposed boundaries of the Echo Canyon Preliminary Municipality (“**Preliminary Municipality**”) and are the same owners who filed the Feasibility Request for the Creation of a Preliminary Municipality on May 1, 2024, pursuant to Utah Code § 10-2a-502 (a copy of the “**Feasibility Request**” is attached hereto as **Exhibit A**). (Utah Code §§ 10-2a-507(1) and 10-2a-507(1)(a) and (e)).

II. Timeliness of Petition

This Petition is timely under Utah Code Section 10-2a-507(a). The hearing required by Utah Code § 10-2a-506 was completed on March 5, 2025.

III. Proposed Preliminary Municipal Boundaries

Pursuant to Utah Code § 10-2a-507(b), the Applicants provide the following description in Exhibit B of the Preliminary Municipality area which is consistent with the description provided in their Feasibility Request, pursuant to Utah Code Section 10-2a-502(5)(d). The Applicants request the initial boundaries of the proposed Preliminary Municipality include all of the real property described in **Exhibit B** which is unaltered from the Feasibility Request (Utah Code § 10-2a-502(5)(e)(i)). (Utah Code § 10-2a-507(1)(b)).

The Preliminary Municipality will be located approximately 1 mile west of Moab, in unincorporated Grand County, Utah and is comprised of approximately 176.4 acres. The Preliminary Municipality will include a mix of residential unit types, including affordable housing, and commercial/mixed-use area, including a hotel, along with the necessary public and private infrastructure to facilitate the Preliminary Municipality’s development. A portion of the Preliminary Municipality will also be reserved for municipal buildings and facilities. A depiction of the planned development and phasing thereof was previously provided as part of the Feasibility Request. (*See* Feasibility Request at p. 2 and Exhibit A to Feasibility Request)

Corrected Petition for Incorporation of Echo Canyon, a Preliminary Municipality
Page 3 of 7

Phase 1 of the Preliminary Municipality will include approximately 50 single family homes, 104 twin homes, 116 condo units, 102 transient overnight accommodations, 48 affordable housing units, and approximately 67,000 square feet of commercial space spread over acreage as depicted in Exhibit A of the Feasibility Request. Phase 2 will include approximately 69 single family homes and 73 townhouse units over acreage as depicted in Exhibit A of the Feasibility Request. Phase 3 will include approximately 18 single family homes over acreage depicted in Exhibit A of the Feasibility Request.

IV. Feasibility Study Compliance

This Petition complies with the requirements of Utah Code §§ 10-2a-504(4) and 10-2a-507(c) as demonstrated by the final published Preliminary Feasibility Study for the Proposed Incorporation of Kane Creek prepared by LRB Public Finance Advisors on January 10, 2025. (A copy of the “**Feasibility Study**” is attached hereto as **Exhibit C.**) Utah Code Section 10-2a-504(4) states that:

If the five-year projected revenues calculated under Subsection (3)(a)(ii)(C) exceed the five-year projected costs calculated under Subsection (3)(a)(ii)(B) by more than 5%, the feasibility consultant shall project and report the expected annual revenue surplus to the primary sponsor contact and the lieutenant governor.

The Feasibility Study found the Preliminary Municipality would meet a five-year average revenue margin of 22.7%, far exceeding the 5% threshold. Accordingly, the incorporation may proceed. (UCA § 10-2a-507(c)). (See Feasibility Study at p. 3. An update to the Feasibility Study made before March 5, 2025, showing a revenue margin of 15.4% is also attached with Exhibit C.)

V. Name of the Preliminary Municipality

The Initial Landowners propose the Preliminary Municipality be named:

Echo Canyon¹

(Utah Code § 10-2a-507(1)(d))

VI. Preliminary Municipality Board Appointments, Chair and Three Members

Pursuant to Utah Code Section 10-2a-507(f), the following shall serve as the Chair and three of the four members of the “**Board**” who, along with the Board member appointed by Grand County, will serve as a five-member council form of government for the Preliminary Municipality:

¹ Note that the Feasibility Study included the placeholder name of “Kane Creek” (*see, e.g.*, Feasibility Study Section 1, Executive Summary). The Feasibility Study’s choice to use the name was for convenience, and this Petition is the document that determines the name of the Preliminary Municipality. (*See generally*, UCA 10-2a-501 et seq.)

Corrected Petition for Incorporation of Echo Canyon, a Preliminary Municipality
Page 4 of 7

Board Chair: Craig Weston
Board Member 1: Thomas Gottlieb
Board Member 2: Trent Arnold
Board Member 3: Jonathan Hoffman

Grand County is required to appoint the fourth and last member of the Board within thirty days following the creation of the Preliminary Municipality pursuant to Utah Code Section 10-2a-509(1)(a).

VII. Map of Preliminary Municipality

An accurate map prepared by a licensed surveyor of the Preliminary Municipality and other supporting documents are attached hereto as **Exhibit D** and show:

- A depiction of the legal description of the boundaries of the Preliminary Municipality area and each phase of the proposed Preliminary Municipality area (Utah Code §§ 10-2a-502(5)(e)(i) and 10-2a-507(1)(g)(i)); and
- All development planned for the proposed Preliminary Municipality area in a single development plan, depicting each phase of the development (Utah Code §§ 10-2a-502(5)(e)(ii) and 10-2a-507(1)(g)(ii)).

VIII. Cash Deposit

Pursuant to Utah Code Section 10-2a-507(1)(h), the Applicants and Initial Landowners submit proof of a “**Cash Deposit**” in the amount of three million six hundred twenty two thousand six hundred fifty-two dollars (\$3,622,652.00) by and among the Initial Landowners and a separate entity Echo Canyon Bond Guarantee Co. LLC, a Utah limited liability company, attached as **Exhibit E**.² The Cash Deposit is:

- (i) posted by the Initial Landowners;
- (ii) in favor of the Preliminary Municipality;

² Exhibit E includes three components: **Exhibit E-1** is the Cash Deposit and Restricted Use Agreement to Guarantee Completion of the System Infrastructure for Echo Canyon, a Proposed Preliminary Municipality, including its own exhibits (the “**Cash Deposit Agreement**”); **Exhibit E-2** is the Engineer’s Certification of the amount needed to complete the System Infrastructure; and **Exhibit E-3** is proof of the funds deposited and available under the Cash Deposit Agreement.

Corrected Petition for Incorporation of Echo Canyon, a Preliminary Municipality

Page 5 of 7

- (iii) guarantees that the Initial Landowners will complete the “system infrastructure,” as defined in Utah Code Section 10-2a-501(13) for the Preliminary Municipality no later than six years after the date of this Petition; and
- (iv) provides for periodic refund and reduction of the Cash Deposit in percentages that reflect the progress toward completing the system infrastructure.

The Cash Deposit procedures described in Exhibit E closely follow the completion assurance provisions applicable for infrastructure improvements within existing municipalities under Utah Municipal Code, specifically Utah Code Section 10-9a-604.5, which provides for cash deposits to guarantee completion of required infrastructure. Because the Preliminary Municipality will not exist until after the Cash Deposit is processed by the Office of the Lieutenant Governor, the Cash Deposit Agreement (Exhibit E-1) also provides for the Cash Deposit to be transferred to and accepted and assumed by the Preliminary Municipality promptly after its creation. Thereafter, the Cash Deposit will be handled in accordance with existing standards under Utah Code applicable to all municipalities.

IX. Costs of the Office of the Lieutenant Governor

Pursuant to Utah Code Section 10-2a-507(1)(i), the Applicants concurrently remit payment of the costs incurred by the Office of the Lieutenant Governor for the Feasibility Study and other expenses. In consultation with Jordan Schwanke, Local Entity Specialist, in the Office of the Lieutenant Governor, the only qualifying cost is the consulting fee for the Feasibility Study submitted by LRB Public Finance Advisors, Inc. on December 31, 2024, in the total amount of \$24,240. A copy of the cost detail and invoice is attached as **Exhibit F**. A check in the amount of \$24,240 to the Lieutenant Governor is submitted herewith, and a copy of the check included as **Exhibit G**.

X. Applicants'/Initial Landowners' Statements

The Applicants hereby state:

- (a) Those individuals signing on behalf of the entity Applicant/Initial Landowners are authorized to do so;
- (b) The Applicants are the owners of all the real property included within the Preliminary Municipality (Utah Code § 10-2a-502(5)(a));
- (c) This Petition is signed by 100% of the property owners of real property within the Preliminary Municipality (Utah Code § 10-2a-502(2)(d)(i));
- (d) The land comprising the Preliminary Municipality is contiguous (Utah Code § 10-2a-502(2)(a));

Corrected Petition for Incorporation of Echo Canyon, a Preliminary Municipality

Page 6 of 7

- (e) None of the land comprising the Preliminary Municipality is located within a county of the first or second class (Utah Code § 10-2a-502(2)(b));
- (f) None of the land comprising the Preliminary Municipality is located within 0.25 miles of an existing municipality. The Preliminary Municipality is at least 0.91 miles from the closest municipality, the City of Moab (Utah Code § 10-2a-502(2)(c));
- (g) The area comprising the Preliminary Municipality is not owned by more than three persons and at least 50% of the area is undeveloped (Utah Code § 10-2a-502(2)(d));
- (h) The Applicants intend to develop the Preliminary Municipality to the point that at least 100 individuals will reside in the area, the area will have an average population density of no less than seven individuals per square mile, and at least 10% of the housing within the Preliminary Municipality will be affordable housing, as defined by Utah Code § 10-2a-501(1) (Utah Code § 10-2a-502(2)(e));
- (i) The area comprising the Preliminary Municipality does not include any land owned by the United States government (Utah Code § 10-2a-502(2)(f));
- (j) The area comprising the Preliminary Municipality is located entirely within Grand County (Utah Code § 10-2a-502(2)(g)); and
- (k) The area comprising the Preliminary Municipality is not included in a pending annexation area (Utah Code § 10-2a-502(3)(a)).

XI. Applicants'/Initial Landowners' Consent

The Applicants/Initial Landowners, as the owners of 100% of the land comprising the Preliminary Municipality, hereby consent to the creation of a Preliminary Municipality. (Utah Code §§ 10-2a-502(2)(d)(i) and 10-2a-502(5)(a))

XII. Petition for Incorporation of Echo Canyon, a Preliminary Municipality

Pursuant to Utah Code § 10-2a-507(1), the Applicants hereby petition the Hon. Deidre Henderson, Lieutenant Governor of Utah, to incorporate Echo Canyon as a Preliminary Municipality as identified in this Petition. The Applicants stand ready and willing to provide any further information necessary for Lieutenant Governor Henderson to cause the incorporation of Echo Canyon as a Preliminary Municipality as Petitioned herein.

XIII. Electronic Means; Counterparts

This Petition may be circulated by electronic means and executed in several counterparts, including by electronic signature, all or any of which may be treated for all purposes as an original and shall constitute and be one and the same document.

Corrected Petition for Incorporation of Echo Canyon, a Preliminary Municipality
Page 7 of 7

IN WITNESS WHEREOF, the Applicants have each executed this Petition for Incorporation of a Preliminary Municipality as of the date indicated above.

KANE CREEK PRESERVATION AND DEVELOPMENT LLC,
a Delaware limited liability company

DocuSigned by:
[Redacted Signature]
By: _____
Name: Craig Weston
Its: General Partner

G&H MILLER FAMILY HOLDINGS LLC,
a Utah limited liability company

DocuSigned by:
[Redacted Signature]
By: _____
Name: Greg Miller
Its: Manager

THE UNDERSIGNED, as General Partner of Kane Creek Preservation and Development LLC, a Delaware limited liability company, consents to be the “primary sponsor contact” as defined in Utah Code Section 10-2a-501(10) for this Petition for Incorporation.

DocuSigned by:
[Redacted Signature]
By: _____
Craig Weston, individually and as General Partner

Exhibit A
to Petition for Incorporation of Echo Canyon,
a Preliminary Municipality
Feasibility Request

Received

MAY 01 2024

Deidre M. Henderson
Lieutenant Governor

**FEASIBILITY REQUEST FOR THE CREATION OF
A PRELIMINARY MUNICIPALITY**

Lieutenant Governor's Office
350 State St. #220,
Salt Lake City, UT, 84103

The undersigned (the "Applicants") hereby apply for the creation of a new Preliminary Municipality ("Preliminary Municipality") pursuant to the Utah Code, Title 10, Chapter 2a, Utah Code annotated 1953 (Utah Code § 10-2a-502(1)).

I. Applicants; Contact Sponsor

Applicants / Owners:

Kane Creek Preservation and Development LLC, a Delaware limited liability company
10446 N. Iverson Ln.
Highland, UT 84003
Phone No. 801-318-7100
Email: cnweston@icloud.com

G&H Miller Family Holdings LLC, a Utah limited liability company
405 S. Main St. Suite 800
Salt Lake City, UT 84111
Phone No. 801-530-7359

Primary Contact / Sponsor:

Craig Weston
10446 N. Iverson Ln.
Highland, UT 84003
Phone No. 801-318-7100
Email: cnweston@icloud.com

With a copy to:

Snell & Wilmer LLP
Attn: Wade Budge
15 West South Temple Suite 1200
Salt Lake City, UT 84101
Phone No. 801-257-1906
Email: wbudge@swlaw.com

The above and undersigned Applicants represent 100% of the surface property owners within the proposed boundaries of the Preliminary Municipality (Utah Code § 10-2a-502(5)(a)).

II. Proposed Preliminary Municipal Boundaries

The Applicants request that the initial boundaries of the proposed Preliminary Municipality include all of the real property described in Exhibit A, Page 1 (Utah Code § 10-2a-502(5)(e)(i)).

III. Description of the Preliminary Municipality

Pursuant to Utah Code § 10-2a-502(5)(d), the Applicants provide the following description of the Preliminary Municipality area. The Preliminary Municipality will be located approximately 1 mile outside of Moab, Utah and is comprised of approximately 176.4 acres. The preliminary municipality will include a mix of residential unit types, including affordable housing, and commercial/mixed-use area, including a hotel, along with the necessary public and private infrastructure to facilitate the Preliminary Municipality's development. A portion of the Preliminary Municipality will also be used for municipal building space. A depiction of the planned development and phasing thereof is attached hereto as Exhibit A.

Phase 1 will include approximately 50 single family homes, 104 twin homes, 116 condo units, 102 overnight accommodations, 48 affordable housing units, and approximately 67,000 square feet of commercial space spread over 79.9 acres as depicted on Exhibit A, Page 3. Phase 2 will include 69 single family homes and 73 townhouse units within 67.5 acres as depicted on Exhibit A, Page 4. Phase 3 will include 18 single family homes on 17.8 acres as depicted on Exhibit A, Page 5.

IV. Map of Preliminary Municipality

An accurate map and other supporting documents, prepared by a licensed surveyor are attached hereto as Exhibit A and show:

- A depiction of the legal description of the boundaries of the Preliminary Municipality area and each phase of the proposed Preliminary Municipality area (Utah Code § 10-2a-502(5)(e)(i));
- All development planned for the proposed Preliminary Municipality area (Utah Code § 10-2a-502(5)(e)(ii)); and
- That the first phase of the proposed Preliminary Municipality area is projected to have at least 100 residents when completed, as depicted on Exhibit A, Page 3 and on the attached Exhibit B (Utah Code § 10-2a-502(5)(e)(iii)).

V. Applicants' Statements

The Applicants hereby states that:

- (a) Those signing on behalf of the entity owners are authorized to do so;
- (b) The Applicants are the owners of all the real property included within the Preliminary Municipality (Utah Code § 10-2a-502(5)(a));
- (c) This Feasibility Request is signed by 100% of the property owners of real property within the Preliminary Municipality (Utah Code § 10-2a-502(2)(d)(i));

- (d) The land comprising the Preliminary Municipality is contiguous (Utah Code § 10-2a-502(2)(a));
- (e) None of the land comprising the Preliminary Municipality is located within a county of the first or second class (Utah Code § 10-2a-502(2)(b));
- (f) None of the land comprising the Preliminary Municipality is located within .25 miles of an existing municipality. The Preliminary Municipality is at least .91 miles away from the closest municipality, the City of Moab, as depicted on the attached Exhibit C (Utah Code § 10-2a-502(2)(c));
- (g) The area comprising the Preliminary Municipality is not owned by more than three persons and at least 50% of the area is undeveloped (Utah Code § 10-2a-502(2)(d));
- (h) The Applicants intend to develop the Preliminary Municipality to the point that at least 100 individuals will reside in the area, the area will have an average population density of no less than seven individuals per square mile, and at least 10% of the housing within the Preliminary Municipality will be affordable housing, as defined by Utah Code § 10-2a-501(1) (Utah Code § 10-2a-502(2)(e));
- (i) The area comprising the Preliminary Municipality does not include any land owned by the United States government (Utah Code § 10-2a-502(2)(f));
- (j) The area comprising the Preliminary Municipality is located entirely within Grand County (Utah Code § 10-2a-502(2)(g));
- (k) The area comprising the Preliminary Municipality is not included in a pending annexation area (Utah Code § 10-2a-502(3)(a)); and
- (l) The area comprising the Preliminary Municipality is not the subject of a completed feasibility study or supplemental feasibility study (Utah Code § 10-2a-502(3)(b)).
- (m) The area comprising the Preliminary Municipality does not include all or part of an area that is the subject of a completed feasibility study or supplemental feasibility study whose results comply with Utah Code § 10-2a-507(1) (Utah Code § 10-2a-502(3)(c)).

VI. Applicants' Consent

The Applicants, as the owners of 100% of the land comprising the Preliminary Municipality, hereby consent to the creation of a Preliminary Municipality (Utah Code §§ 10-2a-502(2)(d)(i) and 10-2a-502(5)(a).

VII. Feasibility Study Request


Pursuant to Utah Code § 10-2a-502(5)(f), the Applicants hereby request that the Lieutenant Governor commission a study to determine the feasibility of incorporating the Preliminary Municipality. The Applicants stand ready and willing to provide any further information necessary to perform the feasibility study.

VIII. Electronic Means; Counterparts


This Feasibility Request may be circulated by electronic means and executed in several counterparts, including by electronic signature, all or any of which may be treated for all purposes as an original and shall constitute and be one and the same document.

IN WITNESS WHEREOF, the Applicants have each executed this Feasibility Request as of the date indicated above.

KANE CREEK PRESERVATION AND
DEVELOPMENT LLC,
a Delaware limited liability company

DocuSigned by:
By: 
Name: Craig Weston
Its: General Partner

G&H MILLER FAMILY HOLDINGS LLC,
a Utah limited liability company

DocuSigned by:
By: 
Name: GREG MILLER
Its: Manager

THE UNDERSIGNED, as General Partner of Kane Creek Preservation and Development LLC, a Delaware limited liability company consents to be the primary sponsor contact for this Feasibility Request.

DocuSigned by:

Name: Craig Weston
Its: Craig Weston, an individual

EXHIBIT A

Legal Description and Maps

EXHIBIT B

Unit Tables

EXHIBIT C

Municipality Proximity Map



88 E Center Street
Moab, UT 84532
435.259.8171

	R-1P RESIDENTIAL, SINGLE-FAMILY DETACHED HOMES
	R-2P RESIDENTIAL, MULTIFAMILY DETACHED HOMES
	R-3P RESIDENTIAL, MULTIFAMILY ATTACHED HOMES
	R-4P RESIDENTIAL, CONDO
	R-5P RESIDENTIAL, COMMERCIAL LIGHTLY DENSITY
	R-6P RESIDENTIAL, COMMERCIAL HEAVY DENSITY
	R-7P RESIDENTIAL, SPECIALTY
	R-8P RESIDENTIAL, TRANSITIONAL
	R-9P RESIDENTIAL, TRANSITIONAL
	R-10P RESIDENTIAL, TRANSITIONAL
	R-11P RESIDENTIAL, TRANSITIONAL
	R-12P RESIDENTIAL, TRANSITIONAL
	R-13P RESIDENTIAL, TRANSITIONAL
	R-14P RESIDENTIAL, TRANSITIONAL
	R-15P RESIDENTIAL, TRANSITIONAL
	R-16P RESIDENTIAL, TRANSITIONAL
	R-17P RESIDENTIAL, TRANSITIONAL
	R-18P RESIDENTIAL, TRANSITIONAL
	R-19P RESIDENTIAL, TRANSITIONAL
	R-20P RESIDENTIAL, TRANSITIONAL
	R-21P RESIDENTIAL, TRANSITIONAL
	R-22P RESIDENTIAL, TRANSITIONAL
	R-23P RESIDENTIAL, TRANSITIONAL
	R-24P RESIDENTIAL, TRANSITIONAL
	R-25P RESIDENTIAL, TRANSITIONAL
	R-26P RESIDENTIAL, TRANSITIONAL
	R-27P RESIDENTIAL, TRANSITIONAL
	R-28P RESIDENTIAL, TRANSITIONAL
	R-29P RESIDENTIAL, TRANSITIONAL
	R-30P RESIDENTIAL, TRANSITIONAL
	R-31P RESIDENTIAL, TRANSITIONAL
	R-32P RESIDENTIAL, TRANSITIONAL
	R-33P RESIDENTIAL, TRANSITIONAL
	R-34P RESIDENTIAL, TRANSITIONAL
	R-35P RESIDENTIAL, TRANSITIONAL
	R-36P RESIDENTIAL, TRANSITIONAL
	R-37P RESIDENTIAL, TRANSITIONAL
	R-38P RESIDENTIAL, TRANSITIONAL
	R-39P RESIDENTIAL, TRANSITIONAL
	R-40P RESIDENTIAL, TRANSITIONAL
	R-41P RESIDENTIAL, TRANSITIONAL
	R-42P RESIDENTIAL, TRANSITIONAL
	R-43P RESIDENTIAL, TRANSITIONAL
	R-44P RESIDENTIAL, TRANSITIONAL
	R-45P RESIDENTIAL, TRANSITIONAL
	R-46P RESIDENTIAL, TRANSITIONAL
	R-47P RESIDENTIAL, TRANSITIONAL
	R-48P RESIDENTIAL, TRANSITIONAL
	R-49P RESIDENTIAL, TRANSITIONAL
	R-50P RESIDENTIAL, TRANSITIONAL



PROJECT TYPE:
PROPOSED SITE PLAN
SURVEY

PROJECT ADDRESS:
88 E CENTER STREET, MOAB, UT 84532

PROJECT LOCATION:
BLM TRAILER TRAIL, MOAB, UT 84532

PREPARED FOR:
PRESERVATION AND
DEVELOPMENT

DATE:
JOB NUMBER:
SHEET 3 OF 5





ARCHITECT
LANDSCAPE ARCHITECTURE
PLANNING
3101 W. Adams Blvd. 3B
Tulsa, Oklahoma 74107
P: 918.438.9891
F: 918.438.9892
www.dty.com

KANE CREEK PRESERVATION & DEVELOPMENT
MASTER PLAN
KANE CREEK PRESERVATION & DEVELOPMENT LLC
GRAND COUNTY, UT

DATE: 11/11/2014
SCALE: AS SHOWN
SHEET NO. 2
PROJECT NO. 14-001

MASTER PLAN
TABULATIONS

PHASE #	KEY	LAND USE	LAND AREA	COMM. SF*	OVERNIGHT ACCOMMODATION UNITST	SINGLE FAMILY DETACHED UNITS	TWIN HOME UNITS	TOWNHOUSE UNITS	CONDO UNITS	TOTAL FOR-SALE DWELLING UNITS	AFFORDABLE HOUSING UNITS	TOTAL ALL DWELLING UNITS	Density (Dwelling Units per Acre)
1	R-MU	Mixed Use, Commercial/Amenity/Condo \$	11.8 acres	57,000 sf					60 Units	60 Units		60 Units	5.1 DU/AC
	DA	Overnight Accommodations	17.8 acres	10,000 sf	107 OA Units								
	R-SF	Residential, Single-Family Detached Homes	17.1 acres			50 Units				50 Units		50 Units	2.9 DU/AC
	R-TW	Residential, Twin Homes	15.7 acres				104 Units			104 Units		104 Units	6.6 DU/AC
	R-MF	Residential, Condo	3.5 acres						56 Units	56 Units	48 Units	48 Units	13.7 DU/AC
	R-AFH	Residential, Affordable Housing	3.1 acres										
	HOA	HOA Property	6.0 acres										
	ROW	Rights of Way	9.9 acres										
	sub-totals		79.9 acres	67,000 sf	107 OA Units	50 Units	104 Units		116 Units	370 Units	48 Units	48 Units	4.0 DU/AC
	2	R-SF	Residential, Single-Family Detached Homes	52.9 acres			69 Units				69 Units		69 Units
R-TH		Residential, Townhouse	8.7 acres				73 Units			73 Units		73 Units	8.4 DU/AC
HOA		HOA Property	0.0 acres										
ROW		Rights of Way	5.9 acres										
sub-totals			67.5 acres			69 Units	73 Units			142 Units		142 Units	2.1 DU/AC
3	R-SF	Residential, Single-Family Detached Homes	14.2 acres			18 Units				18 Units		18 Units	1.3 DU/AC
	HOA	HOA Property	3.9 acres										
	ROW	Rights of Way	1.7 acres										
	sub-totals		17.8 acres			18 Units				18 Units		18 Units	1.0 DU/AC
	Kane Creek Blvd	ROW	Rights of Way	11.2 acres									
sub-totals		11.2 acres											
TOTALS		136.4 acres	67,000 sf	310 OA Units	117 Units	104 Units	73 Units	116 Units	430 Units	48 Units	48 Units	478 Units	2.7 DU/AC

* Commercial lot layouts subject to site plan approval. Includes future amenity site.
 † Overnight accommodation unit counts incorporated for purposes of calculating utility and infrastructure requirements
 § MIXED USE refers to a commercial building with upper story residential

AREA-SUBTOTAL - UNIT TYPE	KEY	LAND USE	LAND AREA	TOTAL DWELLING UNITS
R-MU		Mixed Use, Commercial/Amenity/Condo \$	11.8 acres	60
R-SF		Residential, Single-Family Detached Homes	84.2 acres	133
R-TW		Residential, Twin Homes	15.7 acres	104
R-TH		Residential, townhouse	8.7 acres	73
R-MF		Residential, Condo	3.5 acres	56
R-AFH		Residential, Affordable Housing	3.1 acres	48
TOTALS			127.0 acres	478 DU




Exhibit B
to Petition for Incorporation of Echo Canyon,
a Preliminary Municipality
Map of Initial Boundaries



88 E Center Street
Moab, UT 84532
435.259.8171

STANDARD LEGEND



PROJECT TYPE:
LOCAL ENTITY BOUNDARY
SURVEY

PROJECT ADDRESS:
KANE CREEK BLVD, MOAB, UTAH

PROJECT LOCATION:
GRAND COUNTY, STATE OF UTAH

PREPARED FOR:
KANE CREEK
PRESERVATION AND
DEVELOPMENT LLC

DATE
5/12/25

SHEET 1 OF 1

JOB NUMBER:
191-22

SURVEYOR NOTES



THE BASIS OF BEARING IS NORTH 00°03'18" EAST BETWEEN THE SOUTHWEST CORNER AND THE WEST QUARTER CORNER OF SECTION 15, TOWNSHIP 26 SOUTH, RANGE 21 EAST, SALT LAKE BASE AND MERIDIAN.

THE INTENT OF THE SURVEY IS CREATE A BOUNDARY OF THE TOWN OF ECHO CANYON.

REFERENCED AND LOCATED MONUMENTS OF BLM SURVEY PLAT DATED FEBRUARY 7, 2012.

TOWN OF ECHO CANYON

GRAND COUNTY, UTAH
LOCATED IN SECTIONS 10, 15, & 16, T26S, R21E, SLB&M




VICINITY MAP

NOT TO SCALE

SURVEYOR'S CERTIFICATION

I, Lucas Blake, do hereby certify that I am a Professional Land Surveyor, and that I hold License No. 7540504, in accordance with Title 58, Chapter 22, of the Professional Engineers and Land Surveyors Act; I further certify that by authority of the owners I have completed a survey of the property described on this Local Entity Plat as **TOWN OF ECHO CANYON** in accordance with Section 17-23-20, have verified all measurements and monumented corners as shown on plat.

Lucas Blake
License No. 7540504



5/12/25
DATE

BOUNDARY LEGAL DESCRIPTION

Beginning at the Southeast corner of Section 16, Township 26 South, Range 21 East, Salt Lake Base and Meridian, and running thence South 89°55'57" West 900.24 Feet, more or less, along the South Section line to the easterly Meander Line of the Colorado River; thence, more or less, along the Meander Line of the Colorado the following seventeen courses: thence North 29°10'14" East 455.98 feet; thence North 18°13'02" East 507.07 feet; thence North 10°28'53" East 319.21 feet; thence North 08°22'50" East 639.1 feet; thence North 10°24'57" East 395.02 feet; thence North 11°11'15" East 497.69 feet; thence North 16°36'17" East 711.07 feet; thence North 16°36'17" East 105.60 feet; thence North 15°49'52" East 601.74 feet; thence North 28°26'24" East 793.82 feet; thence North 31°37'04" East 610.29 feet; thence North 31°37'04" East 147.57 feet; thence North 40°00'29" East 596.83 feet; thence North 40°36'00" East 718.96 feet; thence North 39°33'54" East 464.01 feet; thence North 43°59'37" East 392.77 feet; thence North 56°42'42" East 294.90 feet to a point on the center section line of Section 10, T26S, R21E, SLBM; thence with said line South 00°01'48" East 1935.64 feet to the South Quarter corner of said Section 10; thence North 89°50'30" West 1317.78 feet to the Northwest corner of the NE1/4NW1/4 of section 15, T26S, R21E, SLBM; thence South 00°03'18" West 2643.43 feet to the Northeast corner of the NW1/4SW1/4 of said Section 15; thence South 00°04'22" West 1321.74 feet to the Southeast corner of the NW1/4SW1/4 of said Section 15; thence North 89°46'18" West 1316.83 feet to the Southwest corner of the NW1/4SW1/4 of said Section 15; thence South 00°03'18" West 1319.80 feet to the point of beginning, having an area of 176.37 acres, more or less.

TOGETHER WITH a 25' Access easement filed as BLM serial N. UTU-57320




Exhibit C
to Petition for Incorporation of Echo Canyon, a
Preliminary Municipality
Feasibility Study



PUBLIC
FINANCE
ADVISORS

LEWIS | ROBERTSON | BURNINGHAM



GRAND
COUNTY,
UTAH

PRELIMINARY FEASIBILITY STUDY FOR
THE PROPOSED INCORPORATION
OF KANE CREEK

PREPARED BY:

LRB PUBLIC FINANCE ADVISORS

FORMERLY LEWIS YOUNG ROBERTSON & BURNINGHAM INC.

JANUARY 2025

TABLE OF CONTENTS

SECTION 1: EXECUTIVE SUMMARY	3
SECTION 2: POPULATION & POPULATION DENSITY	3
SECTION 3: INITIAL & FIVE-YEAR PROJECTIONS OF DEMOGRAPHICS & TAX BASE	6
SECTION 4: INITIAL & FIVE-YEAR COST PROJECTIONS	12
SECTION 5: INITIAL & FIVE-YEAR PROJECTED REVENUE	17
SECTION 6: RISKS & OPPORTUNITIES	22
SECTION 7: ANALYSIS OF NEW REVENUE SOURCES	24
SECTION 8: FISCAL IMPACTS & PROJECTED TAX BURDEN	26
SECTION 9: WATER AVAILABILITY	29
APPENDIX A: PHASE DEVELOPMENT MAPS	30
APPENDIX B: UPC DETERMINATION	33
APPENDIX C: BUILDOUT PROFORMA	35
APPENDIX D: STAKEHOLDER FEEDBACK	36



SECTION 1: EXECUTIVE SUMMARY

LRB Public Finance Advisors was retained by the Office of the Lieutenant Governor (OLG) to complete a preliminary feasibility study related to incorporation of an unincorporated area within Grand County (County) as outlined in Section §10-2a-504. The purpose of the Executive Summary is to fulfill the requirements established in Section §10-2a-504(2)(c)(iii) which requires the feasibility consultant to submit a completed feasibility study, including a one-page summary of the results.

The purpose of this study is to compare the fiscal impact to the residents of Kane Creek (Town or Study Area) if the County continues to provide services through the General Fund (GF) or if a newly incorporated Town provides services at a similar quality and level of service. Assuming the incorporated Town assesses a proportionate County tax rate necessary to maintain municipal services, the results shown below include the applicable incorporation costs as outlined in Section §10-2a-510 and assumes the cost for a general government office and public works facility will be paid by the developers during Phase I. **The five-year average revenue margin is at 22.7 percent, allowing the incorporation process to proceed.**

TABLE 1.1: FISCAL IMPACT TO STUDY AREA SUMMARY

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5	AVERAGE
Total Revenue	\$102,984	\$343,930	\$650,781	\$945,890	\$1,306,250	\$669,967
Total Expense	\$145,427	\$340,080	\$581,362	\$725,964	\$797,140	\$517,995
NET REVENUE (EXPENSE)	(\$45,846)	\$434	\$65,991	\$206,088	\$481,218	\$141,577
					Revenue Margin	22.7%

Matching the County's proportionate tax rate is sufficient to meet the expenditures within the Town in years two through five, and an additional Kane Creek rate is necessary to provide sufficient funding for the Study Area in year one.

TABLE 1.2: TAX IMPACT TO STUDY AREA SUMMARY

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
PROPORTIONATE COUNTY RATE	0.001416	0.001416	0.001416	0.001416	0.001416
Additional Levy to Balance Budget	0.012746	0.000000	0.000000	0.000000	0.000000
TOTAL TOWN RATE (COUNTY & TOWN LEVY)	0.014162	0.001416	0.001416	0.001416	0.001416
NET IMPACT ON MEDIAN HOME (\$750K)	\$5,679	\$0	\$0	\$0	\$0

Table 1.3 shows that in the event of incorporation, the tax impact for a median home (valued at \$750,000) in the remaining Grand County in year five is \$694, representing an increase of \$110 above the baseline tax impact of \$584. This assumes that the proposed development occurs but remains within the County. However, it is probable the County's GF would experience a decrease in expenses following the incorporation of the town.

TABLE 1.3: COUNTY PROVIDED SERVICES TAX IMPACT SUMMARY

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
COUNTY RATE	0.001416	0.001416	0.001416	0.001416	0.001416
Tax Impact	0.000024	0.000078	0.000141	0.000199	0.000266
TOTAL COUNTY LEVY (IF KANE CREEK INCORPORATES)	0.001441	0.001494	0.001558	0.001615	0.001683
TAX INCREASE FROM BASELINE ON MEDIAN HOME (\$750K)	\$10	\$32	\$58	\$82	\$110




SECTION 2: POPULATION & POPULATION DENSITY

Utah Code §10-2a-504(3) requires the preliminary feasibility study to include:

an analysis of the likely population and population density within the proposed preliminary municipality area when all phases of the map or plat for the proposed preliminary municipality area are completed; and the population and population density of the area surrounding the proposed preliminary municipality area on the day on which the feasibility request was submitted.

The preliminary incorporation boundary for the Study Area is illustrated in **Figure 2.1** and includes unincorporated areas of Grand County known as Kane Creek.

FIGURE 2.1: STUDY AREA BOUNDARY



POPULATION

Appendix A includes map illustrations detailing the three phases of development within the Study Area. Section §10-2a-504(3)(a)(i) requires the preliminary feasibility study to include an analysis of the likely population within

the preliminary municipality area when all phases of the map are completed. The total estimated population of Kane Creek upon phase completion is calculated at 1,105 persons. This calculation was determined by the Utah Population Committee (UPC) as detailed in **Appendix B**. Using the buildout proforma given by the Sponsors (see **Appendix C**), the UPC assumed that single family homes units are owner-occupied and other residential structures are considered renter occupied. The UPC's methodology then assumes 99% occupancy for owner-occupied units and 97% occupancy for renter-occupied units. The projected occupied units are then multiplied by Grand County's persons per occupied housing unit (HU) at 2.37. **Table 2.1** displays the calculated population and households in the Study Area using the UPC's methodology and buildout proforma. The likely population within the Study Area is calculated at 1,105 people.

TABLE 2.1: KANE CREEK LIKELY POPULATION BY PHASE COMPLETION

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5	TOTAL
Phase 1						
Population¹	180	281	217	55	-	733
Owner Occupied Units ²	10	20	20	-	-	50
Renter Occupied Units ³	68	102	74	24	-	268
Total Residential Units	78	122	94	24	-	318
Phase 2						
Population	-	42	111	111	65	330
Owner Occupied Units	-	6	24	24	15	69
Renter Occupied Units	-	12	24	24	13	73
Total Residential Units	-	18	48	48	28	142
Phase 3						
Population	-	14	14	14	-	42
Owner Occupied Units	-	6	6	6	-	18
Renter Occupied Units	-	-	-	-	-	-
Total Residential Units	-	6	6	6	-	18
Total Projected Population						1,105
Total Projected Residential Units						478

Note 1: Assumes persons per occupied housing unit at 2.37

Note 2: Assumes 99 percent occupancy

Note 3: Assumes 97 percent occupancy

POPULATION DENSITY

The UPC determined Kane Creek's population density upon plan competition is 4,009 persons per square mile, thus complying with Utah statute that requires the proposed area has an average population density of more than seven people per square mile.¹ The estimated 2024 populations and population density of surrounding communities within the County are shown below.

TABLE 2.2: POPULATION AND POPULATION DENSITY FOR SURROUNDING AREAS

	ESTIMATED POPULATION	LAND AREA (SQUARE MILES)	POPULATION PER SQUARE MILE
Castle Valley ¹	415	8.8	47.2
Moab ¹	5,395	4.8	1,123.7
Kane Creek²	1,105	0.3	4,009.0

Note 1: Estimated population on the day on which the feasibility request was submitted.

Note 2: Estimated population upon plan completion.

¹ Utah Code 10-2a-502(2)(e)(ii)



SECTION 3: INITIAL & FIVE-YEAR PROJECTIONS OF DEMOGRAPHICS & TAX BASE

Utah Code §10-2a-504(3) requires the preliminary feasibility study to include:

an analysis of the following, determined as if, at the time of the analysis, the proposed preliminary municipality area is incorporated as a town with a population of 100 people; and, the initial and projected five-year demographics and tax base within the boundaries of the proposed preliminary municipality area and the surrounding area, including household size and income, commercial and industrial development, and public facilities.

DEMOGRAPHICS

LRB assumed Kane Creek's year one population is 180 people. The projected demographics are calculated using the UPC's methodology and buildout proforma found in **Table 2.1**.

POPULATION PROJECTIONS

For purposes of calculating the surrounding area's initial and five-year projected population and HUs, the average annual growth rate (AAGR) of historic redistricting Census data from 2010 and 2020 was calculated for each community. The AAGR was then applied to the most recent Census data (2022) and onward. The initial and five-year demographic projections are illustrated in **Table 3.3**.

TABLE 3.1: GROWTH RATE DETERMINATION

	2010		2020		AAGR 2010-2020	
	POPULATION	HU	POPULATION	HU	POPULATION	HU
Grand County	9,225	4,816	9,669	5,192	0.5%	0.8%
Castle Valley	319	291	347	289	0.8%	-0.1%
Moab	5,046	2,366	5,366	2,622	0.6%	1.0%
Unincorporated Grand County	3,860	2,159	3,956	2,281	0.2%	0.6%

Source: U.S. Census Bureau, 2010 and 2020 Census Redistricting Data (PL 94-171)

TABLE 3.2: GRAND COUNTY HISTORIC POPULATION FIGURES

	2019	2020	2021	2022	2023	2024 ¹
Grand County	9,640	9,669	9,630	9,680	9,726	9,780
Castle Valley	365	347	398	409	412	415
Moab	5,268	5,366	5,329	5,329	5,362	5,395
Unincorporated Grand County	4,007	3,956	3,903	3,942	3,952	3,970

Note 1: Estimated 2024 population using growth rates calculated in Table 3.1.

Source: U.S. Census Bureau, American Community Survey 5-Year Estimates (DP05) (SUB-IP-EST2023-POP-49)

TABLE 3.3: GRAND COUNTY INITIAL AND 5-YEAR POPULATION FIGURES

	2025	2026	2027	2028	2029	2030
Grand County	9,936	10,172	10,566	10,965	11,203	11,225
Castle Valley	419	423	427	431	435	439
Moab	5,428	5,461	5,495	5,529	5,563	5,597
Unincorporated Grand County	3,989	4,008	4,027	4,046	4,065	4,084

The population projected in year one aligns with §10-2a-504(3)(a)(ii), which requires this analysis assumes the proposed preliminary municipality area is incorporated as a town with a population of 100 people. Five-year



population projections for the Study Area are based on the UPC’s methodology and buildout proforma found in **Table 2.1**.

TABLE 3.4: KANE CREEK INITIAL AND 5-YEAR POPULATION FIGURES

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Kane Creek Population	180	517	860	1,040	1,105
Households	78	224	372	450	478
Projected New Homes (See Table 2.1)	78	146	148	78	28
Persons per Household	2.30	2.31	2.31	2.31	2.31

HOUSEHOLD SIZE

The number of households was estimated starting with 2022 occupied households as the base units. The AAGR calculated in **Table 3.1** was then applied to the base to estimate current units and the persons per household (PPH) for this analysis.

TABLE 3.5: INITIAL AND PROJECTED CALCULATED PERSONS PER HOUSEHOLD (PPH)

	2025		2026		2027		2028		2029		2030	
	HU	PPH	HU	PPH	HU	PPH	HU	PPH	HU	PPH	HU	PPH
Grand County	4,434	2.22	4,467	2.25	4,501	2.33	4,535	2.40	4,569	2.43	4,603	2.44
Castle Valley	209	2.00	209	2.02	209	2.04	209	2.06	209	2.08	209	2.10
Moab	2,356	2.30	2,380	2.29	2,405	2.28	2,430	2.28	2,455	2.27	2,480	2.26
Unincorporated Grand County	1,872	2.13	1,882	2.13	1,892	2.13	1,902	2.13	1,912	2.13	1,923	2.12
Kane Creek	NA	NA	78	2.30	224	2.31	372	2.31	450	2.31	478	2.31

Note: PPH figures are calculated based on total population and **occupied** housing units which differ from Census reported average household size based on household population.

Source: U.S. Census Bureau, American Community Survey 5-Year Estimates

INCOME

Utilizing Census tract-level data ², the Study Area’s median household income is estimated at \$54,385 as of 2022.

TABLE 3.6: HISTORIC MEDIAN INCOME

	2019	2020	2021	2022	2023 ¹	2024 ¹	2010 – 2020 AAGR
Grand County	\$51,557	\$56,639	\$51,433	\$59,171	\$61,055	\$63,000	3.0%
Castle Valley	\$53,125	\$53,542	\$46,667	\$43,438	\$44,535	\$45,659	4.1%
Moab	\$51,168	\$46,875	\$42,083	\$52,385	\$53,265	\$54,160	3.5%
Kane Creek	NA	\$51,750	\$53,319	\$54,385	\$55,473	\$56,583	2.0%²

Note 1: Applied growth 2010 – 2020 growth rate to determine estimates.

Note 2: 10-year AAGR not available. Two percent growth is applied instead.

Source: U.S. Census Bureau, American Community Survey 5-Year Estimates (B19019)

TABLE 3.7: INITIAL & PROJECTED MEDIAN INCOME

	2025	2026	2027	2028	2029	2030
Grand County	\$65,006	\$67,077	\$69,213	\$71,417	\$73,692	\$76,039
Castle Valley	\$46,812	\$47,994	\$49,206	\$50,448	\$51,722	\$53,027
Moab	\$55,070	\$55,995	\$56,936	\$57,892	\$58,865	\$59,854
Kane Creek	\$57,714	\$58,868	\$60,046	\$61,247	\$62,472	\$63,721

² Applicable Census tracts include: 3.02




TAX BASE

The tax base of the region is important to consider in this incorporation study as growth in property values, taxable sales, and employment are valuable components when determining feasibility. The following paragraphs discuss the County's regional economy.

REGIONAL ECONOMY

Grand County is located in southeast Utah. The unemployment rate for the County averaged 4.5 percent in October 2024. Unemployment peaked in 2010 at an average of 10.6 percent (see **Figure 3.1**) according to seasonally adjusted data provided by the Utah Department of Workforce Services. Notable shifts in employment occurred between April 2020 and April 2021 as Grand County experienced a 55.7 percent increase in non-farm jobs. More generally, from 2021 to 2022, the County experienced large increases in professional and business services, financial activities, and education and health services, with a total employment change of 7.9 percent. Over the same period, information jobs declined by 16.6 percent and construction jobs decreased by 6.1 percent.


FIGURE 3.1: HISTORIC GRAND COUNTY SEASONALLY ADJUSTED UNEMPLOYMENT RATES



A comparison of quarterly taxable sales trends for the County and State illustrates the percent change from 2018 to 2022 as shown in **Figure 3.2**. Between 2020 and 2021, Q2 experienced an increase of 123.2 percent in taxable sales in the County.



FIGURE 3.2: COMPARISON OF QUARTERLY TAXABLE SALES TRENDS FOR GRAND COUNTY



Historic taxable value figures for Grand County show an AAGR of 13.4 percent from 2019 through 2023. It is important to note that the values below include redevelopment agency values, which will be excluded in the projection of future taxable values.

TABLE 3.8: GRAND COUNTY HISTORIC TAXABLE VALUE

	2019	2020	2021	2022	2023	5 Yr. AAGR
Real: Land	\$540,307,662	\$549,418,430	\$582,216,743	\$597,424,760	\$918,455,520	14.2%
Real: Buildings	\$949,834,446	\$1,032,580,981	\$1,215,890,742	\$1,482,058,500	\$1,823,731,780	17.7%
Personal	\$59,068,599	\$60,530,248	\$63,068,182	\$79,797,432	\$100,706,311	14.3%
Centrally Assessed	\$446,623,367	\$443,408,536	\$488,032,700	\$537,994,602	\$460,142,417	0.7%
TOTAL	\$1,995,834,074	\$2,085,938,195	\$2,349,208,367	\$2,697,275,294	\$3,303,036,028	13.4%
Motor Vehicle	\$12,473,299	\$11,496,469	\$16,579,539	\$15,220,486	\$15,117,179	4.9%

Source: Utah State Tax Commission

STUDY AREA ECONOMY

Study Area is comprised of eight (8) parcels³ with a taxable value of \$3,330,000. The Study Area represents 0.1 percent of the total County taxable value. Based on a review of current property information within the Study Area, the property type of three of the eight parcels is commercial improved. The remaining parcels are vacant land.

TABLE 3.9: ESTIMATE OF STUDY AREA TAXABLE VALUE

CURRENT KANE CREEK TAXABLE VALUE	\$3,330,000
Study Area Taxable Value as % of County Taxable Value	0.10%

Appendix A includes map illustrations detailing the future development within the Study Area. Phase 1, located along the river, includes 67,000 square footage of commercial space, 48 affordable housing units, and 270 residential units. Phase 2, centrally located along the east side of the Study Area border, proposes 142 residential units. The final phase proposes the development of 18 residential units.

³ Parcels considered for this analysis are all those within the Study Area boundary except for roadways.



PROJECTIONS OF COUNTY TAX BASE

Grand County does not have a separate Municipal Service Fund accounting for the cost of services provided to unincorporated county. As a result, this study analyzes the County’s General Fund. Using Utah State Tax Commission data for Grand County, projected taxable value estimates are shown below. **Table 3.11** details the current and projected values based on a five percent growth rate.

TABLE 3.10: HISTORIC GRAND COUNTY TAXABLE VALUE

	2019	2020	2021	2022	2023	2024
Certified Tax Rate Value	\$1,845,296,400	\$1,933,334,163	\$2,179,315,399	\$2,461,104,261	\$3,093,282,013	\$3,414,404,774

Source: Utah State Tax Commission

TABLE 3.11: INITIAL AND 5-YEAR PROJECTED GRAND COUNTY TAXABLE VALUE

	2025	2026	2027	2028	2029	2030
Certified Tax Rate Value	\$3,585,125,013	\$3,764,381,263	\$3,952,600,327	\$4,150,230,343	\$4,357,741,860	\$4,575,628,953

Future sales tax growth projections are based on a general growth estimate of five percent. Historic data from financial reports showed an AAGR of 8.9 percent from 2019 – 2024.

TABLE 3.12: HISTORIC GRAND COUNTY SALES TAX REVENUE

	2019	2020	2021	2022	2023	2024
GF Sales Tax Revenue	\$1,070,752	\$1,085,126	\$1,525,926	\$1,573,919	\$1,678,984	\$1,678,984

TABLE 3.13: INITIAL AND PROJECTED GRAND COUNTY SALES TAX REVENUE

	2025	2026	2027	2028	2029	2030
GF Sales Tax Revenue	\$1,762,933	\$1,851,080	\$1,943,634	\$2,040,816	\$2,142,856	\$2,249,999

PROJECTIONS OF STUDY AREA TAX BASE

Significant factors that will influence revenues within the Study Area include taxable assessed value and taxable sales. Growth in taxable value will influence future property tax revenues and fund general government services. In addition, future sales tax revenues will supplement the General Fund to support the community’s needs. Taxable value growth projections are shown below for the Study Area.

TABLE 3.14: STUDY AREA TAXABLE VALUE

	PROJECTED				
	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Assessed Value	\$3,330,000	\$3,330,000	\$93,360,000	\$238,000,000	\$411,900,000
Prior Year New Growth	\$0	\$90,030,000	\$144,640,000	\$173,900,000	\$90,000,000
TOTAL TAXABLE VALUE	\$3,330,000	\$93,360,000	\$238,000,000	\$411,900,000	\$501,900,000

New growth calculations in the table above are based on the future construction provided in **Appendix C**. Assumptions regarding home values and price per square foot are provided in the **Table 3.15**.



TABLE 3.15: STUDY AREA TAXABLE VALUE NEW GROWTH

	PROJECTED				
	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
RESIDENTIAL DEVELOPMENT					
New Workforce Units ¹	24	24	-	-	-
New Condos/Twin Homes ²	44	90	98	48	13
New Single-Family Detached ³	10	32	50	30	15
Total Residential New Growth	\$61,800,000	\$139,140,000	\$168,900,000	\$90,000,000	\$33,450,000
COMMERCIAL DEVELOPMENT					
New Commercial SF ⁴	15,000	22,000	20,000	-	-
New Overnight Accommodation SF ⁵	10,000	-	-	-	-
Total Commercial New Growth	\$28,230,000	\$5,500,000	\$5,000,000	\$0	\$0
TOTAL NEW GROWTH	\$90,030,000	\$144,640,000	\$173,900,000	\$90,000,000	\$33,450,000

Note 1: Assumes \$100,000 per unit.
 Note 2: Assumes \$1.5M per unit.
 Note 3: Assumes \$2.4M per unit.
 Note 4: Assumes \$250 per commercial SF.
 Note 5: Assumes \$2,448 per room SF.

Sales tax revenues are distributed based on two methodologies: 1) the ratio of population; and 2) point of sale, or the location of the sale. Total sales tax collections are distributed equally between these allocation strategies, with 50 percent assigned to point of sale and 50 percent to population. LRB assumed an AAGR of five percent for the population and point of sales projections. Population revenues are distributed to local entities based on the ratio of their population to the State’s population. Retail point of sale revenues was calculated using estimated commercial square footage, while online point of sale revenues was calculated using sales tax data from Grand County and E-Commerce figures from the US Census Bureau. The table below summarizes the total estimated sales tax revenue attributed to the Study Area. **Section 5** of this study discusses the population and point of sales methodologies further and **Section 7** outlines the challenges presented by the data utilized to calculate sales tax revenues.

TABLE 3.16: STUDY AREA ESTIMATED SALES TAX REVENUE

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Population Distribution	\$28,003	\$83,128	\$142,705	\$178,314	\$195,616
Point of Sale Distribution	\$55,042	\$114,711	\$175,472	\$194,490	\$207,446
TOTAL ESTIMATED SALES TAX	\$83,044	\$197,839	\$318,177	\$372,805	\$403,062

PUBLIC FACILITIES

There are presently no public facilities within the Study Area boundaries, except for utility-related infrastructure. There are various networks surrounding the proposed municipality including Moonflower Canyon and Moab Rim Trail.



SECTION 4: INITIAL & FIVE-YEAR COST PROJECTIONS

Utah Code §10-2a-504(3) requires the preliminary feasibility study to include:

an analysis of the following, determined as if, at the time of the analysis, the proposed preliminary municipality area is incorporated as a town with a population of 100 people; and, subject to Subsection (3)(b), the initial and five-year projected cost of providing municipal services to the proposed preliminary municipality area, including administrative costs.

GENERAL METHODOLOGY

This section compares the costs to the residents of the Study Area if the County continues to provide services or if a newly incorporated Town provides services. Utah Code requires that the level and quality of governmental services be fairly and reasonably approximate between the two options.⁴ This analysis assumes that several municipal services provided by the County, Special Districts, and private companies will continue to be provided regardless of the incorporation. However, actual service provision will be governed by the newly incorporated municipal governing body.

LRB assumes the following services will be provided by the various entities without any impact from incorporation or non-incorporation:

- Culinary and Secondary Water: Kane Springs Water Company, Grand County Water Conservancy District, Grand County Special Service Water District
- Sewer: Kane Springs Improvement District
- Fire: Moab Valley Fire Protection District
- Parks and Recreation: Grand County Cemetery Maintenance District, Grand County Recreation Service District, Grand County General Fund (there are currently no park facilities within the Study Area)
- Solid Waste: Solid Waste Special Service District #1

The following services were assumed to be provided by the County through the General Fund or through the Town if incorporated:

- General Government Services (including administrative overhead and planning and zoning)
- Law Enforcement and Animal Control
- Roads

COUNTY COST ESTIMATES

Expenditures related to County services were calculated using calendar year (CY) financial reports detailing General Fund actuals from CY 2019 – 2023, updated based on proposed CY 2024 budget information and recommendations from the County Clerk/Auditor. For the purposes of this analysis, the tables below combine the County's projected expenditures into the general categories specified in the financial report.

⁴ Utah Code 10-2a-205(4)(b)(i)



TABLE 4.1: COUNTY SCENARIO: HISTORIC AND PRESENT EXPENDITURES

	2019	2020	2021	2022	2023	2024
General Government	\$3,963,843	\$3,755,185	\$3,616,673	\$4,783,217	\$5,839,944	\$5,851,384
Public Safety	\$6,101,488	\$6,052,999	\$7,360,218	\$8,768,057	\$10,899,656	\$11,443,361
Public Works	\$627,040	\$687,573	\$685,216	\$806,141	\$1,015,386	\$951,864
Public Health	\$186,392	\$185,281	\$184,508	\$190,261	\$191,414	\$194,098
Community	\$1,171,635	\$1,054,926	\$1,287,305	\$1,462,157	\$1,788,957	\$1,771,406
Intergovernmental	\$505,561	\$677,206	\$167,217	\$298,909	\$367,565	\$332,621
Transfers Out	\$786,712	\$637,315	\$5,676,874	\$3,323,558	\$7,333,223	\$601,421
TOTAL	\$13,342,671	\$13,050,485	\$18,978,011	\$19,632,300	\$27,436,145	\$21,146,155

Between 2019 and 2024, the County’s GF expenditures grew at an AAGR of 9.6 percent. The five-year projections are based on an analysis of the historic AAGR for each budget line item, which are then applied to account for inflation and anticipated growth.⁵ **Table 4.2** illustrates the County’s estimated expenditures if they are fixed, meaning the General Fund expenditures will not be reduced and the County tax rate will remain the same if there is an incorporation.

TABLE 4.2: COUNTY SCENARIO: INITIAL AND 5-YEAR PROJECTED EXPENDITURES

	2025	2026	2027	2028	2029	2030
General Government	\$7,053,662	\$7,403,026	\$7,777,097	\$8,177,918	\$8,607,712	\$9,068,907
Public Safety	\$11,051,304	\$11,563,122	\$12,104,921	\$12,678,697	\$13,286,600	\$13,930,940
Public Works	\$997,229	\$1,045,143	\$1,095,761	\$1,149,254	\$1,205,802	\$1,265,598
Public Health	\$196,143	\$198,229	\$200,357	\$202,527	\$204,741	\$206,999
Community	\$1,845,277	\$1,923,489	\$2,006,353	\$2,094,208	\$2,187,419	\$2,286,383
Intergovernmental	\$342,600	\$352,878	\$363,464	\$374,368	\$385,599	\$397,167
Transfers Out	\$619,286	\$638,937	\$660,553	\$684,331	\$710,486	\$739,257
TOTAL	\$22,105,500	\$23,124,822	\$24,208,506	\$25,361,303	\$26,588,358	\$27,895,250

STUDY AREA COST ESTIMATES (ASSUMING TOWN INCORPORATION)

Expenditures for the Study Area were calculated using the following methodologies in order to determine an acceptable level of service (LOS):

- Per capita expenditures within the General Fund applicable to unincorporated areas
- Per capita expenditures of comparable cities
- Expenditures per center lane mile of comparable cities
- Average total expenditures per mile based on County estimates

INCORPORATION COST

A one-time cost due to incorporation is included in the analysis for when the population of the Study Area is expected to reach over 99 people.⁶ **Table 2.1** shows the Town’s population exceeding 99 people in 2026. These expenses include the estimated election cost, assuming the incorporation goes to a vote, and the LRB contract cost. According to a discussion with the County Clerk/Auditor, the County administers Castle Valley’s elections in addition to unincorporated areas. To determine the estimated election cost for the Study Area, LRB calculated the per capita cost based on Castle Valley’s FY 2024 election expense. After applying an inflationary increase of

⁵ §10-2a-504(3)(b)(ii)

⁶ §10-2a-510(1)



three percent, the election cost per capita for Castle Valley is \$30. Applying this cost to the Kane Creek 2026 population of 180 results in an election cost of \$5,411.

GENERAL GOVERNMENT SERVICES

Grand County does not have a separate Municipal Service Fund accounting for the cost of services provided to unincorporated county. As a result, this study analyzes the County's General Fund. Based on discussions with the County, expenditures related to assessor, surveyor, and county maintenance are County-level provided services and will remain regardless of incorporation. Assessor, surveyor, and county maintenance expenditures account for approximately 25 percent of total general government expenditures in 2024. A per capita rate removing assessor, surveyor, and county maintenance was calculated to determine Kane Creek's estimated general government expenditures. This figure was extended to 2030 at a three percent annual growth rate and applied to the projected Study Area population.

TABLE 4.3: KANE CREEK GENERAL GOVERNMENT SERVICES 5-YEAR PROJECTED COSTS

	INITIAL	PROJECTED				
		YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
GF Government Services Cost per Capita ¹	\$541	\$557	\$574	\$591	\$608	\$627
Kane Creek Population	-	180	517	860	1,040	1,105
TOTAL GENERAL GOVERNMENT COSTS	\$0	\$100,106	\$296,469	\$507,744	\$632,942	\$692,715

Note 1: Does not include costs related to assessor, surveyor, and county maintenance.

As the Kane Creek population increases to 1,105 people at the end of the five-year period, general government costs also increase. LRB gathered FY 2024 budget information for Green River and Monticello cities to determine the average expense for general government services for municipalities with near or over 1,000 people. After removing budgetary line items determined to be one-time expenses or irrelevant to maintaining the present LOS, the FY 2024 general government expense for Green River was \$1.3M and \$562,700 for Monticello. The projected 2030 cost determined in **Table 4.3** of \$692,715 falls between the Green River and Monticello's average cost. LRB also gathered FY 2024 budget data for communities with under 1,000 people including Bluff, Boulder, Castle Valley, Clawson, Hanksville and Leeds. The average general government expense for municipalities under 1,000 people is roughly \$126,800 and the average per capita rate is \$433. Kane Creek's initial per capita rate exceeds the per capita rate of \$433.

LAW ENFORCEMENT AND ANIMAL CONTROL

LRB gathered budget data from nine comparable Cities in Utah based upon population and geography. Of these nine comparable cities, four communities (Green River, Hanksville, Leeds, and Monticello) provide services related to law enforcement. A per capita rate using these four communities was calculated to determine the proposed Town's law enforcement expense. This figure was extended to 2030 at a three percent annual growth rate and applied to the projected Study Area population.

TABLE 4.4: LAW ENFORCEMENT PER CAPITA COST ALLOCATION

	INITIAL	PROJECTED				
		YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Comp. Public Safety Cost per Capita	\$68	\$70	\$72	\$74	\$76	\$79
Kane Creek Population	-	180	517	860	1,040	1,105
TOTAL LAW ENFORCEMENT COSTS	\$0	\$12,567	\$37,217	\$63,740	\$79,457	\$86,960

Budgetary line items determined to be one-time expenses or irrelevant to maintaining the present level of service were removed from the estimation of this expense. Comparative communities include Green River, Hanksville, Leeds, and Monticello.



ROADS

Of the eight total miles of Kane Creek Road 114, the County currently maintains the 1.34 miles that are in the Study Area. According to the County (see **Appendix D**), this road would remain a County Class B road, and the Town would not incur any cost nor gain any Class C revenue from Kane Creek Road 114. The remaining roads, as well as future roads in Kane Creek are, or will be, privately owned and maintained. According to the Sponsor, an estimate of two miles of private roads will be constructed. To quantify the financial impacts to the taxpayers of the proposed town, this analysis includes potential roads costs, assuming the Town constructs 0.4 miles of roads per year, totaling 2 road miles at the end of the five-year horizon.

TABLE 4.5: KANE CREEK PROJECTED WEIGHTED MILEAGE

	PROJECTED				
	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Kane Creek Mileage	0.40	0.80	1.20	1.60	2.00
UDOT Multiplier*	5	5	5	5	5
TOTAL WEIGHTED MILEAGE	2.00	4.00	6.00	8.00	10.00

*Based on Class B and C Roads Apportionment Formula (Utah Code 72-2-108)

Data on comparable towns were gathered to determine a typical operations and maintenance cost per weighted mile. The data included in the analysis comprises weighted mileage and FY 2024 budgeted roads expenditures. The average cost per weighted mile is estimated at \$1,552.

TABLE 4.6: COMPARABLE TOWN'S ROAD COSTS

	WEIGHTED MILEAGE (FY24)	ROADS EXPENSE FY24	EXPENSE PER WEIGHTED MILE
Bluff	58.60	\$10,020	\$171
Boulder	35.65	\$47,703	\$1,338
Castle Dale	71.14	\$152,961	\$2,150
Castle Valley	46.26	\$94,405	\$2,041
Clawson	14.53	\$1,000	\$69
Green River	48.01	\$33,070	\$689
Hanksville	14.70	\$1,700	\$116
Leeds	52.58	\$92,202	\$1,754
Monticello	84.50	\$476,502	\$5,639
Average Expense per Weighted Mile			\$1,552

Source: State Road GIS Shapefile, UDOT B&C Road Fund Information, Mileage and Annual Summary Reports, Utah State Auditor, Local and State Government Budget Reports

In comparison, LRB gathered 2024 budget information from Grand County's Class B Roads Fund⁷ to determine the average cost per weighted mile for the County. The County's cost per weighted mile is estimated at \$1,181, which is lower than the average cost per weighted mile of \$1,552 calculated in **Table 4.6**. The figure calculated in **Table 4.6** is utilized to project potential road costs in **Table 4.7** and is extended to 2030 at a three percent annual growth rate and applied to the projected Study Area weighted mileage.

⁷ Discussions with County staff indicate the Class B Roads Fund is used to service unincorporated County.



TABLE 4.7: KANE CREEK ROADS EXPENSE 5-YEAR PROJECTED COSTS

	PROJECTED				
	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Cost per Weighted Mile	\$1,552	\$1,598	\$1,646	\$1,696	\$1,747
Kane Creek Weighted Miles	2.00	4.00	6.00	8.00	10.00
TOTAL ESTIMATED ROADS COST	\$3,104	\$6,393	\$9,878	\$13,565	\$17,465

Table 4.8 summarizes the expenditures forecasted for the proposed Study Area. This scenario includes the applicable incorporation costs as outlined in Section §10-2a-510 and assumes the cost for a general government office and public works facility will be paid by the developer during Phase I of development.

TABLE 4.8: KANE CREEK 5-YEAR PROJECTED EXPENDITURES

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Incorporation Costs	\$29,651	\$0	\$0	\$0	\$0
General Government	\$100,106	\$296,469	\$507,744	\$632,942	\$692,715
Law Enforcement & Animal Control	\$12,567	\$37,217	\$63,740	\$79,457	\$86,960
Roads	\$3,104	\$6,393	\$9,878	\$13,565	\$17,465
TOTAL OPERATING EXPENSE	\$145,427	\$340,080	\$581,362	\$725,964	\$797,140



SECTION 5: INITIAL & FIVE-YEAR PROJECTED REVENUE

Utah Code §10-2a-504(3) requires the preliminary feasibility study to include:

an analysis of the following, determined as if, at the time of the analysis, the proposed preliminary municipality area is incorporated as a town with a population of 100 people; and, assuming the same tax categories and tax rates as imposed by the county and all other current service providers at the time during which the feasibility consultant prepares the feasibility study, the initial and five-year projected revenue for the proposed preliminary municipality area.

GENERAL METHODOLOGY

This section compares the revenues the County and Study Area are likely to generate. Similar to the expenditure projections, the revenues were calculated using CY financial reports detailing General Fund actuals from CY 2019 – 2023, updated based on proposed CY 2024 budget information and recommendations from the County Clerk/Auditor. Additional allocation methodologies were utilized based on population, assessed value, and standard State allocation practices.

COUNTY REVENUES

The General Fund revenues were grouped into major categories from a budgeting perspective. The projections below are based on an analysis of the historic AAGR for each budget line item, as well as insight from County staff. Between 2019 and 2024, the County's GF revenue grew at an AAGR of 9.6 percent.

TABLE 5.1: COUNTY GF HISTORIC AND CURRENT REVENUES

	2019	2020	2021	2022	2023	2024
Taxes	\$5,873,055	\$7,258,038	\$8,534,910	\$10,023,474	\$10,316,515	\$10,488,913
Licenses and Permits	\$374,760	\$353,773	\$446,013	\$420,245	\$383,200	\$327,500
Intergovernmental	\$1,959,301	\$3,637,593	\$3,229,419	\$1,947,044	\$7,331,708	\$1,060,658
Charges for Services	\$411,132	\$614,176	\$657,054	\$625,865	\$781,529	\$978,565
Fines and Forfeitures	\$505,274	\$314,887	\$391,616	\$353,182	\$348,490	\$351,000
Interest Income	\$168,386	\$63,449	\$69,389	\$413,383	\$986,227	\$87,533
Miscellaneous	\$647,246	\$540,708	\$756,903	\$862,278	\$1,038,739	\$792,342
Transfers In	\$3,454,052	\$2,664,874	\$6,578,469	\$6,794,693	\$6,250,780	\$7,054,646
TOTAL	\$13,393,206	\$15,447,498	\$20,663,773	\$21,440,164	\$27,437,188	\$21,141,157

Table 5.2 includes property tax projected tied to new growth at five percent. While County General Fund expenditures exceed revenues from 2025 through 2027, an additional levy is not modeled in this analysis due to revenues beginning to exceed expense beginning in 2028. This trend is consistent with historical General Fund budget data, demonstrating revenues exceeding expense by an average of 5.4 percent from 2019 – 2024.

TABLE 5.2: COUNTY SCENARIO INITIAL & 5-YEAR PROJECTED REVENUES

	2025	2026	2027	2028	2029	2030
Taxes	\$10,926,157	\$11,383,994	\$11,863,425	\$12,365,505	\$12,891,339	\$13,442,085
Licenses and Permits	\$335,875	\$344,504	\$353,394	\$362,554	\$371,991	\$381,715
Intergovernmental	\$1,091,968	\$1,125,617	\$1,161,816	\$1,200,795	\$1,242,806	\$1,288,128
Charges for Services	\$1,040,222	\$1,107,981	\$1,182,451	\$1,264,301	\$1,354,268	\$1,453,160
Fines and Forfeitures	\$351,000	\$351,000	\$351,000	\$351,000	\$351,000	\$351,000
Interest Income	\$96,286	\$105,915	\$116,506	\$128,157	\$140,973	\$155,070



	2025	2026	2027	2028	2029	2030
Miscellaneous	\$811,144	\$831,132	\$852,395	\$875,024	\$899,120	\$924,793
Transfers In	\$6,852,725	\$7,512,990	\$8,238,246	\$9,034,946	\$9,910,186	\$10,871,766
TOTAL	\$21,505,376	\$22,763,133	\$24,119,234	\$25,582,283	\$27,161,683	\$28,867,717

STUDY AREA REVENUES (ASSUMING TOWN INCORPORATES)

Revenues for the Study Area were calculated using the following methodologies:

- Property tax based on assessed value and new growth
- State Sales Tax allocation based on population and point of sale
- State Class C Road Fund allocation based on lane miles and population
- License and permit revenues based on estimated expenses
- Interest earnings based on cumulative fund balance

PROPERTY TAX

The property tax revenue calculation is based on the assessed value of the Study Area and applying the projected County levy for general operations. With that said, Grand County does not have a separate Municipal Service Fund accounting for the cost of services provided to unincorporated county. Based on discussions with the County, expenditures related to assessor, surveyor, and county maintenance are provided for all County residents. These county-wide services' expenditures account for approximately 25 percent of total general government expenditures. LRB applied a LOS adjustment for revenues generated from the County equivalent tax rate to be more reflective of the services currently provided to unincorporated county.

New growth calculations in the table above are based on the future construction provided in **Appendix C**. Assumptions regarding home values and price per square foot are provided in the **Table 3.16**.

TABLE 5.3: STUDY AREA TAXABLE VALUE 5-YEAR PROJECTED REVENUES

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Assessed Value	\$3,330,000	\$3,330,000	\$93,360,000	\$238,000,000	\$411,900,000
New Growth	\$0	\$90,030,000	\$144,640,000	\$173,900,000	\$90,000,000
TOTAL TAXABLE VALUE	\$3,330,000	\$93,360,000	\$238,000,000	\$411,900,000	\$501,900,000
County GF Levy	0.001416	0.001416	0.001416	0.001416	0.001416
Tax Revenue from GF Levy	\$4,717	\$132,244	\$337,126	\$583,454	\$710,939
LOS Adjustment	75%	75%	75%	75%	75%
ADJUSTED TAX REVENUE	\$3,538	\$99,183	\$252,844	\$437,591	\$533,204

SALES TAX

Sales tax revenues are distributed based on two methodologies: 1) the ratio of population; and 2) point of sale, or the location of the sale. Total sales tax collections are distributed equally between these allocation strategies, with 50 percent assigned to point of sale and 50 percent to population. Future sales tax growth projections are based on a general growth estimate of five percent.

Population revenues are distributed to local entities based on the ratio of their population to the State's population as a whole. The State population distribution pool in **Table 5.4** represents an average between the applicable current and prior fiscal year to estimate State's sale tax for the calendar year. The calculated average was then multiplied by 50 percent to distribute the total sales tax collections based on population.



TABLE 5.4: RATIO OF POPULATION DISTRIBUTION 5-YEAR PROJECTED REVENUES

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
State Population Distribution Pool	559,948,216	587,945,627	617,342,909	648,210,054	680,620,557
Growth Rate	5.00%	5.00%	5.00%	5.00%	5.00%
State Population	3,595,100	3,656,244	3,718,428	3,781,670	3,845,987
Distributed per Capita	\$155.75	\$160.81	\$166.02	\$171.41	\$176.97
Study Area Estimated Population	180	517	860	1,040	1,105
POPULATION DISTRIBUTION	\$28,003	\$83,128	\$142,705	\$178,314	\$195,616

Point of sale revenues were calculated using estimated retail and hotel square footage. Retail point of sale revenues assume a starting commercial sales per square footage figure of \$300 and is extended to 2030 at a five percent annual growth rate. Hotel point of sale revenues assume a daily rate of \$150 per room with an occupancy adjustment of 70 percent. Online point of sale revenues is calculated using taxable sales revenue from Grand County and are adjusted based on E-Commerce figures from the US Census Bureau. During the third quarter of 2024, E-Commerce sales accounted for 15.6 percent of total store and non-store sales.⁸

TABLE 5.5: POINT OF SALE DISTRIBUTION 5-YEAR PROJECTED REVENUES

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
RETAIL					
Sales Tax per SF ¹	\$315.00	\$330.75	\$347.29	\$364.65	\$382.88
Total Commercial SF	15,000	37,000	57,000	57,000	57,000
Subtotal Retail Sales	\$4,725,000	\$12,237,750	\$19,795,388	\$20,785,157	\$21,824,415
HOTEL					
Daily Rate	\$154.50	\$159.14	\$163.91	\$168.83	\$173.89
Hotel Rate Increase	3%	3%	3%	3%	3%
Hotel Rooms	102	102	102	102	102
Occupancy	70%	70%	70%	70%	70%
Subtotal Hotel Sales	\$4,026,425	\$4,147,217	\$4,271,634	\$4,399,783	\$4,531,776
ONLINE					
Grand County Taxable Sales	\$810,957,533	\$851,505,410	\$894,080,680	\$938,784,714	\$985,723,950
% E-Commerce	16%	16%	16%	16%	16%
Grand County E-Commerce Sales	\$126,432,067	\$132,753,670	\$139,391,354	\$146,360,921	\$153,678,967
Grand County Population	10,072	10,466	10,865	11,103	11,225
Grand County Per Capita E-Commerce	\$12,553	\$12,685	\$12,829	\$13,182	\$13,690
Kane Creek Population	180	517	860	1,040	1,105
Subtotal Online Sales	\$2,256,938	\$6,557,288	\$11,027,294	\$13,713,151	\$15,132,997
Point of Sale Allocation	0.50%	0.50%	0.50%	0.50%	0.50%
TOTAL POINT OF SALE REVENUE	\$55,042	\$114,711	\$175,472	\$194,490	\$207,446

Note 1: Assumes commercial sales per SF of \$300. Figure is extended to future years at a five percent growth rate.

TABLE 5.6: TOTAL SALES TAX 5-YEAR PROJECTED REVENUES

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Population Distribution (Table 5.4)	\$28,003	\$83,128	\$142,705	\$178,314	\$195,616
Retail Point of Sale (Table 5.5)	\$55,042	\$114,711	\$175,472	\$194,490	\$207,446
TOTAL ESTIMATED SALES TAX	\$83,044	\$197,839	\$318,177	\$372,805	\$403,062

⁸ US Census Bureau. (2024, November). Quarterly Retail E-Commerce Sales. Retrieved from <https://www.census.gov/retail/ecommerce.html>



CLASS C ROAD FUND

Of the eight total miles of Kane Creek Road 114, the County currently maintains the 1.34 miles that are in the Study Area. According to the County (see **Appendix D**), this road would remain a County Class B road, and the Town would not incur any cost nor gain any Class C revenue from Kane Creek Road 114. The remaining roads in Kane Creek are privately owned and maintained. This analysis assumes that the Town will construct a total of two miles of roads by the end of five-year horizon.

TABLE 5.7: KANE CREEK PROJECTED WEIGHTED MILEAGE

	PROJECTED				
	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Kane Creek Mileage	0.40	0.80	1.20	1.60	2.00
UDOT Multiplier*	5	5	5	5	5
TOTAL WEIGHTED MILEAGE	2.00	4.00	6.00	8.00	10.00

*Based on Class B and C Roads Apportionment Formula (Utah Code 72-2-108)

Table 5.8 depicts the growth rate calculated and subsequently applied to forecast key variables (statewide total distribution pool, lane miles, weighted miles).

TABLE 5.8: CLASS B&C ROADS HISTORIC AAGR

	2019	2020	2021	2022	2023	2024 ¹	2025 ¹	2019 – 2023 AAGR
Total Distribution Pool	179,188,729	177,562,815	194,764,526	203,134,579	216,853,217	227,446,713	238,557,711	4.89%
Lane Miles Pool	89,594,365	88,781,407	97,382,263	101,567,289	108,426,609	113,723,356	119,278,856	4.89%
Statewide Weighted Miles	121,813	122,842	124,521	125,318	126,997	128,328	129,672	1.05%

Note 1: Estimated using 2019 – 2023 AAGR.

Source: UDOT B&C Road Fund Information, Mileage and Annual Summary Reports

Utilizing **Table 5.8's** calculated weighted mileage for the Study Area and methodology delineated in Utah State Code, the Study Area's distribution can be calculated.

TABLE 5.9: CLASS B&C ROADS INITIAL AND 5-YEAR PROJECTED REVENUES

	PROJECTED				
	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Total Distribution Pool	250,211,493	262,434,574	275,254,764	288,701,234	302,804,577
Lane Miles Pool	125,105,747	131,217,287	137,627,382	144,350,617	151,402,288
Statewide Weighted Miles	131,030	132,403	133,790	135,191	136,607
Distribution Per Weighted Mile	955	991	1,029	1,068	1,108
Estimated Weighted Miles	2.00	4.00	6.00	8.00	10.00
Lane Mile Distribution	\$1,910	\$3,964	\$6,172	\$8,542	\$11,083
State Population	3,595,100	3,656,244	3,718,428	3,781,670	3,845,987
State Distribution per Capita	\$34.80	\$35.89	\$37.01	\$38.17	\$39.37
Study Area Population	180	517	860	1,040	1,105
Population Distribution	\$6,256	\$18,552	\$31,814	\$39,709	\$43,514
TOTAL STUDY AREA DISTRIBUTION	\$8,166	\$22,517	\$37,986	\$48,251	\$54,597



LICENSES & PERMITS

Reflecting that business licenses and building permit fees, likely expected for the Study Area upon consideration of planned development, are charged at a rate that is proportional to the costs to the incorporated Town to issue them, licenses & permits revenue in this study are tied directly to estimated costs for planning and zoning. For this study, half of the estimated costs for planning and zoning are considered attributable to managing licenses and permits, thus expected licenses & permits revenue is equal to that value. LRB isolated the planning and zoning costs from the total general government expense calculated in **Table 4.2** to determine the license and permit revenues.

TABLE 5.10: LICENSES & PERMITS 5-YEAR PROJECTED REVENUES

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
LICENSES & PERMITS REVENUE	\$8,236	\$24,392	\$41,774	\$52,074	\$56,992

INTEREST EARNINGS

Interest earnings are calculated based on a 1.50 percent interest rate on any fund balance carryover.

OTHER REVENUE CONSIDERATIONS

Additional types of revenue streams may be collected including transient room taxes, grants, and weed control fees. These alternate revenue mechanisms will be explored in greater detail in **Section 7**.

Table 5.11 summarizes the revenues forecasted for the proposed Study Area. This allows the proposed Town's fund balance to increase overtime and produce interest revenues.

TABLE 5.11: KANE CREEK 5-YEAR PROJECTED REVENUES

	PROJECTED				
	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Property Tax ¹	\$3,538	\$99,183	\$252,844	\$437,591	\$533,204
Sales & Use Tax	\$83,044	\$197,839	\$318,177	\$372,805	\$403,062
Class C Roads	\$8,166	\$22,517	\$37,986	\$48,251	\$54,597
Licenses & Permits	\$8,236	\$24,392	\$41,774	\$52,074	\$56,992
Interest Earnings	\$0	\$0	\$0	\$35,169	\$258,394
TOTAL OPERATING REVENUES	\$102,984	\$343,930	\$650,781	\$945,890	\$1,306,250

Note 1: Property tax revenue generated in Kane Creek assuming equivalent County rate. Property tax revenue is then adjusted by 75%.



SECTION 6: RISKS & OPPORTUNITIES

Utah Code §10-2a-504(3) requires the preliminary feasibility study to include:

an analysis of the following, determined as if, at the time of the analysis, the proposed preliminary municipality area is incorporated as a town with a population of 100 people; and, the risks and opportunities that might affect the actual costs described in Subsection (3)(a)(ii)(B) or the revenues described in Subsection (3)(a)(ii)(C) of the proposed preliminary municipality area.

RISKS

Discussions with the County pointed to concern towards the impacts on infrastructure regardless of incorporation. The County Clerk/Auditor and Roads Department noted that Kane Springs Road is commonly used for recreation purposes and noted that road width improvements are most likely necessary to continue providing adequate recreation access. This study does not contemplate costs related to future CIP, as capital improvements that are not currently being provided by the County through the GF are not included in the current LOS. Should the Town incorporate, the Town could complete a master plan that identifies future CIP. These additional costs can be mitigated by grants, tax or rate increases, or impact fees. The County also acknowledged the potential fiscal impacts on storm water mitigation and emergency management from developing on a floodplain.

Roads within the boundary would most likely be privately funded and maintained. Therefore, expenses associated with roads would be the responsibility of the applicable Homeowner Association (HOA). In **Appendix D**, stakeholders pointed to the possible cost burden to residents as a result of HOA fees. While the Study illustrates potential costs if the proposed Town decides to maintain the new roads, actual road expenses will vary and be determined based on the contracts established by the newly incorporated town.

Several variables influence the Study Area's taxable assessed value and taxable sales revenues including new growth calculations based on future residential and commercial construction and general assumptions regarding home values and price per square foot. This analysis does not include a market feasibility study to determine whether the proposed commercial square footage is supportable. The lack of a market feasibility analysis presents a certain risk in that the study assumes the planned development will occur upon incorporation. Additionally, the financial feasibility of this study may be jeopardized if cost assumptions for home values and price per square foot are reduced.

As Kane Creek does not presently generate retail point of sale revenue, the fiscal sustainability of the Study Area is contingent upon proposed commercial and industrial development. In the event that this development does not transpire or proceeds at slower rates than modeled in this study, it is likely that total revenues would not offset total expenditures. Additionally, inflationary pressure will affect the Study Area, as well as the GF. The impact of inflation may be more pronounced within the Study Area.

OPPORTUNITIES

Opportunities in the Study Area post-incorporation may include self-governance, ability to develop public facilities, zoning and land-use authority, more local representation, and more direct control over the future of the area. Incorporation may increase local authority to meet the requests and needs of residents.



Specific goals related to population growth, economic growth and development, business licensing, and zoning policies could be addressed by the newly incorporated area. However, it is important to note that these elements may result in an increase in costs beyond what has been presented in this study.



SECTION 7: ANALYSIS OF NEW REVENUE SOURCES

Utah Code §10-2a-504(3) requires the preliminary feasibility study to include:

an analysis of the following, determined as if, at the time of the analysis, the proposed preliminary municipality area is incorporated as a town with a population of 100 people; and, new revenue sources that may be available to the proposed preliminary municipality area that are not available before the area incorporates, including an analysis of the amount of revenues the proposed preliminary municipality area might obtain from those revenue sources.

TRANSIENT ROOM TAX

Temporary lodging (i.e., hotel, motel, inn, tourist home, trailer court, or campground) used for less than thirty days are subject to both sales and transient room tax.⁹ To receive revenue from a transient room tax levy, Kane Creek may impose up to one percent tax on temporary lodging upon incorporation. Depending on whether some of the proposed commercial development in the Study Area will be comprised by temporarily lodging, a transient room tax may be a new revenue source the Town could contemplate.

FRANCHISE TAX - MUNICIPAL ENERGY SALES AND USE TAX

Municipalities may adopt a tax on gas and electricity delivered within their jurisdiction. These taxes are collected by a seller and held in trust for the benefit of the locality imposing the tax.

DEBT FINANCING

Debt financing may be utilized to amortize larger capital costs over time, rather than addressing those costs in a shorter period. This does not introduce new revenues (interest and cost of issuance expenses add to the overall cost assumptions), but it does serve as a funding tool to allow for the construction of public facilities.

GRANTS

Most of the comparable cities included in the analysis receive grant monies, although it is uncertain which grants the Town would be eligible for.

IMPACT FEES

As mentioned in **Section 6**, the Town, if incorporation occurs, could begin to provide services (e.g., streets, parks) and would be able to charge impact fees to new development. It is important to note that the Town cannot assess impact fees if the eligible categories are not serviced by the Town.

FEES FOR SERVICES

The newly incorporated area will have the ability to adopt necessary fees related to services provided. This study has followed the statutory requirement to maintain the same level of service currently provided to residents based on the expenditures and revenue sources utilized within the GF. However, the Town may be able to increase revenues by assessing specific fees for services. These may include transportation fees, recreation fees, disproportionate fees, and/or utility fees. It is important to note that these fees would be an additional cost to residents, beyond what is shown in the following sections.

⁹ Utah State Tax Commission. (2023, Nov 3). Transient Room Taxes. Retrieved from <https://tax.utah.gov/sales/transientroom>



HOA FEES

Homeowner Association (HOA) fees or Property Owners Association (POA) fees may serve as a funding source for road maintenance and other services. To quantify the financial impacts to the taxpayers of the proposed town, this analysis includes potential roads costs, and all other government expenses, assuming the Town is responsible for covering these expenses. However, HOA or POA fees may be utilized for these services.



SECTION 8: FISCAL IMPACTS & PROJECTED TAX BURDEN

Utah Code §10-2a-504(3) requires the preliminary feasibility study to include:

an analysis of the following, determined as if, at the time of the analysis, the proposed preliminary municipality area is incorporated as a town with a population of 100 people: the projected tax burden per household of any new taxes that may be levied within the proposed preliminary municipality area within five years after incorporation as a town; and the fiscal impact of the proposed preliminary municipality area's incorporation as a town on unincorporated areas, other municipalities, special districts, special service districts, and other governmental entities in the county.

The purpose of this study is to project and compare the impact of incorporation of the Study Area to the fiscal impact of remaining within the County service area. The following section details the impact to residents in the Study Area, as well as to the County.

FISCAL IMPACTS & TAX BURDEN ON THE COUNTY

A comparison of projected revenues and expenditures produces a surplus beginning in year three based on the County's projected 2025 rate of .001416, as shown in **Table 8.1**. The baseline tax impact to a primary residence in Grand County valued at \$750,000¹⁰ is \$584.

TABLE 8.1: FISCAL IMPACTS ON GRAND COUNTY

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
REVENUES					
COUNTY RATE	0.001416	0.001416	0.001416	0.001416	0.001416
Taxes	\$11,383,994	\$11,863,425	\$12,365,505	\$12,891,339	\$13,442,085
Licenses and Permits	\$344,504	\$353,394	\$362,554	\$371,991	\$381,715
Intergovernmental Revenues	\$1,125,617	\$1,161,816	\$1,200,795	\$1,242,806	\$1,288,128
Charges for Services	\$1,107,981	\$1,182,451	\$1,264,301	\$1,354,268	\$1,453,160
Fines and Forfeitures	\$351,000	\$351,000	\$351,000	\$351,000	\$351,000
Interest Income	\$105,915	\$116,506	\$128,157	\$140,973	\$155,070
Miscellaneous	\$831,132	\$852,395	\$875,024	\$899,120	\$924,793
Transfers In	\$7,512,990	\$8,238,246	\$9,034,946	\$9,910,186	\$10,871,766
TOTAL REVENUES	\$22,763,133	\$24,119,234	\$25,582,283	\$27,161,683	\$28,867,717
EXPENDITURES					
General Government	\$7,403,026	\$7,777,097	\$8,177,918	\$8,607,712	\$9,068,907
Public Safety	\$11,563,122	\$12,104,921	\$12,678,697	\$13,286,600	\$13,930,940
Public Works	\$1,045,143	\$1,095,761	\$1,149,254	\$1,205,802	\$1,265,598
Public Health	\$198,229	\$200,357	\$202,527	\$204,741	\$206,999
Community	\$1,923,489	\$2,006,353	\$2,094,208	\$2,187,419	\$2,286,383
Intergovernmental	\$352,878	\$363,464	\$374,368	\$385,599	\$397,167
Transfers Out	\$638,937	\$660,553	\$684,331	\$710,486	\$739,257
TOTAL EXPENDITURES	\$23,124,822	\$24,208,506	\$25,361,303	\$26,588,358	\$27,895,250
NET REVENUES (EXPENSE)	(\$361,689)	(\$89,272)	\$220,979	\$573,324	\$972,468
County Taxable Value	\$3,764,381,263	\$3,952,600,327	\$4,150,230,343	\$4,357,741,860	\$4,575,628,953
TOTAL COUNTY RATE	0.001416	0.001416	0.001416	0.001416	0.001416
BASELINE IMPACT ON COUNTY MEDIAN HOME (\$750K)	\$584	\$584	\$584	\$584	\$584

¹⁰ Rocket Homes. (2024, Dec 6). Grand County Housing Market Report . Retrieved from <https://www.rockethomes.com/real-estate-trends/ur/grand-county>



The Study Area may continue to receive County Services at the level of service currently provided as a part of the GF with negligible additional costs as compared with the current County tax levies.

In the event of incorporation, the County would likely experience a loss of revenue, modeled here as equivalent to the projected revenue for the Study Area, resulting in the need for an additional property tax increase in year one over the baseline County levy. This increase represents lost revenue for municipal services, as well as revenues gained through the Sheriff's Department. The contract revenue is estimated at \$12,567 in year one. The net impact of the Town incorporation is a loss of \$95,860 in revenues in 2026, as illustrated in **Table 8.2**. This potential lost revenue is based upon the development scenario considered within this study for an incorporated town. However, this development scenario would likely not transpire if the Study Area were to remain unincorporated. As a result, it is unlikely that the GF levy would need to be raised to the extent modeled here to account for lost revenue from the Study Area in the event of incorporation.

It is possible that the newly incorporated town may contract for additional services with the County (e.g., engineering, planning, and building permitting), resulting in additional contract revenues flowing to the County. Furthermore, it is probable the County's GF would experience a decrease in expenses following the incorporation of the town.

TABLE 8.2: IMPACT TO COUNTY GF

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Potential Lost Revenue	(\$102,984)	(\$343,930)	(\$650,781)	(\$945,890)	(\$1,306,250)
Contract Revenue	\$12,567	\$37,217	\$63,740	\$79,457	\$86,960
NET IMPACT TO COUNTY GF	(\$90,417)	(\$306,713)	(\$587,041)	(\$866,433)	(\$1,219,289)
Tax Impact	0.000024	0.000078	0.000141	0.000199	0.000266
County Levy (If Kane Creek Incorporates)	0.001441	0.001494	0.001558	0.001615	0.001683
Estimated Impact on Median Home (\$750K)	\$594	\$616	\$643	\$666	\$694
Baseline Impact on Median Home (\$750K)	\$584	\$584	\$584	\$584	\$584
TAX INCREASE FROM BASELINE	\$10	\$32	\$58	\$82	\$110

FISCAL IMPACTS & TAX BURDEN ON STUDY AREA

The following section analyzes the fiscal impacts of a Town incorporation, which includes the incorporation costs outlined in §10-2a-510 and assumes the developers will construct a government office building during Phase I of development.

The results in **Table 8.3** assume the incorporated Town will assess a proportionate County tax rate necessary to maintain municipal services described in previous sections. A review of projected revenues under the proportionate County levy relative to proposed expenses illustrates a deficit in year one. Incorporation costs and delayed development contribute to the escalated costs in the first years of incorporation. Beginning in year two, revenues exceed expenditures within the Town and no additional Kane Creek rate is necessary to provide sufficient funding for the Study Area. The annual revenue margin is at an average of 22.7 percent over the five-year window of this study, meeting the requirement outlined in UCA §10-2a-504(4) to allow the process of incorporation to proceed.



TABLE 8.3: KANE CREEK FISCAL IMPACT

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5	AVERAGE
REVENUES						
PROPORTIONATE COUNTY RATE	0.001416	0.001416	0.001416	0.001416	0.001416	
Property Tax	\$3,538	\$99,183	\$252,844	\$437,591	\$533,204	\$265,272
Sales & Use Tax	\$83,044	\$197,839	\$318,177	\$372,805	\$403,062	\$274,985
Class C Roads	\$8,166	\$22,517	\$37,986	\$48,251	\$54,597	\$34,303
Licenses & Permits	\$8,236	\$24,392	\$41,774	\$52,074	\$56,992	\$36,694
Interest Earnings	\$0	\$0	\$0	\$35,169	\$258,394	\$58,713
Total Revenues	\$102,984	\$343,930	\$650,781	\$945,890	\$1,306,250	\$669,967
EXPENDITURES						
Incorporation Costs	\$29,651	\$0	\$0	\$0	\$0	\$5,930
General Government	\$100,106	\$296,469	\$507,744	\$632,942	\$692,715	\$445,995
Law Enforcement	\$12,567	\$37,217	\$63,740	\$79,457	\$86,960	\$55,988
Roads	\$3,104	\$6,393	\$9,878	\$13,565	\$17,465	\$10,081
Total Expenditures	\$145,427	\$340,080	\$581,362	\$725,964	\$797,140	\$517,995
NET (REVENUE MINUS EXPENSE)	(\$42,443)	\$3,850	\$69,419	\$219,926	\$509,109	\$151,972
REVENUE (EXPENSE) MARGIN*						22.7%

*Margin calculated by dividing net revenue by total revenues.

In year one, matching the County's proportionate tax rate is not sufficient to meet the expenditures within the Town and an additional Kane Creek rate is necessary to provide sufficient funding for the Study Area. The 2026 Town rate (.014162) is the sum of the County GF proportionate rate (.001416) and the Kane Creek rate (.012746). The tax impact within the Study Area is estimated at \$5,842 for a primary residence valued at \$750K in year one. This represents an increase of \$5,258 above the projected County levy of \$584, assuming the property tax levy remains unchanged following incorporation.

TABLE 8.4: KANE CREEK TAX BURDEN

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
EQUIVALENT COUNTY RATE	0.001416	0.001416	0.001416	0.001416	0.001416
Additional Levy to Balance Budget*	0.012746	0.000000	0.000000	0.000000	0.000000
TOTAL TOWN RATE (COUNTY & TOWN LEVY)**	0.014162	0.001416	0.001416	0.001416	0.001416
Estimated Certified Tax Value	\$3,330,000	\$93,360,000	\$238,000,000	\$411,900,000	\$501,900,000
Estimated Town Impact (Median Home \$750K)	\$5,842	\$584	\$584	\$584	\$584
County Baseline Impact (Median Home \$750K)	\$584	\$584	\$584	\$584	\$584
NET IMPACT	\$5,258	\$0	\$0	\$0	\$0

*Kane Creek levy calculated based on estimated assessed value and 75% adjustment.

** Based on the sum of the "Combined County Rate" plus the "Additional Levy to Balance Budget".



SECTION 9: WATER AVAILABILITY

Utah Code §10-2a-504(3) requires the preliminary feasibility study to include:

an analysis regarding whether sufficient water will be available to support the proposed preliminary municipality area when the development of the area is complete.

Kane Springs Water Company will serve as the municipal water supply upon incorporation. The company presently has approximately 422-acre feet of water rights. Water sources include five wells and the ability to pull directly from the Colorado River. The developer estimates that the proposed development will likely need 200-acre feet, resulting in sufficient water supply to support the proposed preliminary municipality area when the development of the area is complete.



APPENDIX B: UPC DETERMINATION



Memorandum

June 24, 2020

To: Jordan Schwanke, Office of the Lieutenant Governor
 From: Eric Albers, Public Policy Analyst, Kem C. Gardner Policy Institute
 CC: Mallory Bateman, Director of Demographic Research, Kem C. Gardner Policy Institute
 Subject: Kane Creek Preliminary Municipal Feasibility Review

Introduction

This review follows the feasibility request for the preliminary municipality of Kane Creek, in Grand County, Utah. This memo determines whether Kane Creek meets the population, density, and contiguity requirements for preliminary incorporation (defined in Utah Code 10-2a-503).

The Utah Population Committee (UPC) analysis indicates that Kane Creek meets the preliminary incorporation requirements.

Table 1: Initial Feasibility Requirements for West Hills Incorporation

Criteria	Meets Criteria?	Requirement by Statute	West Hills Details
Population	Yes	Population must be equal to or greater than 100 when all phases of the plan are completed.	Population estimate upon plan completion: 1,105
Population Density	Yes	Density must be seven people per square mile or higher	Population density estimate upon plan completion: 4,009 persons per square mile.
Contiguity	Yes	Area is contiguous, does not have a strip of land connecting geographically separate areas	The proposed boundary covers a contiguous area

Population data source: U.S. Census Bureau, 2020 Census

Note: Requirements are summarized; Full statutory requirements are delineated in Utah Code 10-2a-502.

Table 2: Kane Creek Population Estimate

Phase	Population Estimate
Phase 1	733
Phase 2	330
Phase 3	42
Total	1105



Methodology

Housing Unit Method

The UPC uses the housing unit method of estimation to determine the population of places seeking to incorporate. For preliminary municipal incorporations where the population of the defined area is zero, estimates of housing units are taken as given from the description of the preliminary municipality.

The method assumes that single family homes and other residential structures with less than 12 units are owner-occupied. Residential structures with 12 or more units are considered renter occupied. The method assumes 99% occupancy for owner-occupied units and 97% occupancy for renter-occupied units. Occupied units are then multiplied by county-level persons per household (2.37 for Grand County) from the 2020 census to determine household population.



APPENDIX C: BUILDOUT PROFORMA

Property Section	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Total
Phase 1 - Lower Riverside Land							
RM-U Mixed Use, Commercial/Amenity		15,000	22,000	20,000			57,000
OA Hotel - Commercial Space		10,000					10,000
Total Commercial Sq Ft	0	25,000	22,000	20,000	0	0	97,000
OA Overnight Accommodations		102					102
R-AFH Residential, Affordable Housing (Rental)		28	24				52
Total Units - OA & Long Term Rental	0	126	24	0	0	0	150
R-MU Condo/Mixed Use Locations		74		36			110
RM-F Central Amenity Area - Condos		24	24	3			51
R-SF Residential, Single-Family Detached		10	20	20			50
R-TW Residential, Town Homes		22	33	33	24		112
Total Phase 1 For Sale Units	2	94	98	94	24	0	279
Phase 2 - Main Upper Land							
R-SF Residential, Single-Family Detached			6	24	24	10	64
R-TH Residential, Townhomes Attached			12	24	32	12	70
Total Phase 2 For Sale Units	0	0	18	48	46	22	134
Phase 3 - North Upper Land							
R-SF Residential, Single-Family Detached			6	6	6		18
Total Phase 3 For Sale Units	0	0	6	6	6	0	18
All Phases - Total For Sale Units	0	94	122	148	78	28	430
All Phases - Total All Residential Unit Types	0	78	146	148	78	28	478

Assumptions

- Start date is based on existing and delivery for all build products. R-SF is based on economic build completion by buyers (18 month build cycle)
- Commercial / Mixed Use - Developed in three locations shown on plan, north, north east to south end of development.
- Hotel Completed by end of Year 2
- Residential Affordable Product built in 12/24 unit phases.
- Central Amenity Condos are first product out of the ground, max of 8 and 12 unit buildings
- Upper Land units - delivered on time just 18-24 months from Lower Land launch
- Assume incorporation four years from first Certificate of Occupancy, 6 months 10 after launch / Time to full incorporation from Preliminary Municipality at approx. 3-5 years
- Final unit sales prices for Property Taxes: Condos at \$500K-\$1.2M, Townhomes & Townhomes at \$1.8-4.7M, Residential Lots from \$1.8M-\$7.5M (Home Values at \$3-\$5M)

PHASE #	KEY	LAND USE	LAND AREA	COUNTY #	OVERNIGHT ACCOMMODATION UNITS	SINGLE FAMILY DETACHED UNITS	TOWN HOME UNITS	TOWNHOUSE UNITS	CONDO UNITS	TOTAL PER-MIA (RESIDENTIAL UNITS)	NET DENSABLE (RESIDENTIAL UNITS)	TOTAL ALL (RESIDENTIAL UNITS)	Density (Units per Acre)
1	RM-U	Mixed Use, Commercial/Amenity	15.000	17.000						15.000	22.000	37.000	2.47
	OA	Hotel - Commercial Space	10.000	10.000						10.000		10.000	1.00
	R-MU	Condo/Mixed Use Locations	74.000	74.000						74.000		74.000	1.00
	RM-F	Central Amenity Area - Condos	24.000	24.000						24.000		24.000	1.00
	R-SF	Residential, Single-Family Detached	10.000	10.000						10.000		10.000	1.00
	R-TW	Residential, Town Homes	22.000	22.000						22.000		22.000	1.00
Sub-Total			154.000	154.000	102 Units	126 Units	24 Units	36 Units	110 Units	279 Units	430 Units	2.87	
2	R-SF	Residential, Single-Family Detached	6.000	6.000						6.000		6.000	1.00
	R-TH	Residential, Townhomes Attached	12.000	12.000						12.000		12.000	1.00
	R-SF	Residential, Single-Family Detached	6.000	6.000						6.000		6.000	1.00
	Sub-Total			24.000	24.000	18 Units	48 Units	46 Units	22 Units	134 Units	134 Units	134 Units	5.58
3	R-SF	Residential, Single-Family Detached	6.000	6.000						6.000		6.000	1.00
	R-SF	Residential, Single-Family Detached	6.000	6.000						6.000		6.000	1.00
	Sub-Total			12.000	12.000	6 Units	6 Units	6 Units	0 Units	18 Units	18 Units	18 Units	1.50
Grand Total			190.000	190.000	126 Units	180 Units	96 Units	64 Units	214 Units	631 Units	672 Units	3.54	

APPLICABLE UNIT TYPE

KEY	LAND USE	LAND AREA	TOTAL OVERNIGHT UNITS
R-MU	Condo/Mixed Use Locations	74.000	0
RM-F	Central Amenity Area - Condos	24.000	0
R-SF	Residential, Single-Family Detached	10.000	0
R-TW	Residential, Town Homes	22.000	0
R-SF	Residential, Single-Family Detached	6.000	0
R-TH	Residential, Townhomes Attached	12.000	0

dtj DESIGN

FANE CREEK PRESERVATION & DEVELOPMENT
 PROJECT #241
 24100 S. 1000 E. SUITE 100
 SALT LAKE CITY, UT 84115

2



APPENDIX D: STAKEHOLDER FEEDBACK

Section §10-2a-504(3)(c) outlines the stakeholders that were consulted and received the draft of the preliminary feasibility study on December 11, 2024 to review and provide comment to the draft. The following appendix includes feedback from Grand County during the draft phase of the study. LRB's response to each item is in red.



Grand County stakeholders have reviewed the PRELIMINARY FEASIBILITY STUDY FOR THE PROPOSED INCORPORATION OF KANE CREEK, prepared by LRB Public Finance Advisors and dated December 2024 (hereinafter "the STUDY"). Below is the review.

1. The STUDY assumes the 1.34 miles of paved road, Route #114 - Kane Creek Boulevard (STUDY erroneously gives the name Canyon Road), would become a Class C road upon incorporation. This is not accurate, as an important collector road in the Grand County road system, this road would remain a County Class B road as permitted by Utah statute 17-50-305. Exclusion of this road substantially changes all the analysis and results presented in the STUDY, especially the predicted Class C road revenues.

LRB Response: The Study has removed the 1.34 miles of paved roads, assuming it would remain County maintained. Any revenue or cost related to Kane Creek Road 114 has been removed from the analysis.

2. The STUDY ignores all proposed new roads stating that these roads would be privately maintained. Presumably funding for this road maintenance will come from Property Owners Association (POA) fees. I think it important to consider that POA fees are essentially a property tax burden, and the POA and Town boundaries will be one and the same. The real cost to maintain all of the new circulation roads could be a significant cost burden to a limited population. If the purpose of the STUDY is to demonstrate the necessary property tax revenue, ignoring all the road maintenance costs as a private cost may not give an accurate picture.

LRB Response: The County property tax levy does not include the maintenance for private roads. For purposes of determining feasibility and in following Section 10-2a-504(3)(a)(ii)(B), expense related to private roads is not required. With that said, to illustrate potential costs to new roads, LRB has included a calculation (see Table 4.5 - 4.7) of road expense assuming new roads would be maintained by the new Town, although it is likely that new road costs would be incurred by residents via HOA fees. While adding these potential costs does not jeopardize the financial feasibility, the risk section will include this concern.

3. The STUDY develops a road operations maintenance unit cost by pulling from nine comparable towns. The unit costs from these nine towns varied widely (from \$69/mile to \$5,639/mile) and all the towns have 2 to 12 times the amount of mileage that the STUDY is based on. The actual road operation expenditures could vary widely from the STUDY estimate.

LRB Response: The average cost per mile from comparable towns (\$1,552) is higher than the average cost per mile from the County's Class B road expense (\$1,181). LRB will include the County's calculation for reference and language to clarify that we are using the higher cost estimate.

4. The STUDY does not account for the large up-front cost required to establish a road maintenance department. Initial equipment purchase could be \$500,000 to \$1,000,000 plus. The extremely small mileage amount does not offer any economy of scale.

LRB Response: A municipality at this size, especially during development and with all new roads, would be highly unlikely to have an in-house roads maintenance department. The Sponsor indicated the new Town would likely rely on a third party civil engineering contractor to assess and recommend needed repairs and the Town would then contract the work out for repairs.

5. Page 15 of the STUDY under the heading ROADS: paragraph under table 4.5 3rd sentence says " Canyon Road 114" and in table 4.6. This should be Kane Creek Road 114.

LRB Response: The Study has removed all references to Canyon Road 114 and has replaced it with Kane Creek Road 114.

6. Page 15 of the STUDY paragraph under Table 4.5 sentence 4 talks about maintenance expenses and types of maintenance. I suggest adding asphalt patching, rock fall removal, snow removal, flood cleanup and repair, culvert cleaning and repair, mowing roadside vegetation and signage repair/replacement.

LRB Response: The maintenance expense of Kane Creek Road 114 is no longer included in the Study, as item #1 stated that this road will remain a County Class B road.



**Corrected Feasibility Study for
March 5, 2025, Public Hearing**



PUBLIC
FINANCE
ADVISORS

LEWIS | ROBERTSON | BURNINGHAM



GRAND
COUNTY,
UTAH

JANUARY 2025

PRELIMINARY FEASIBILITY STUDY FOR
THE PROPOSED INCORPORATION
OF KANE CREEK

PREPARED BY:

LRB PUBLIC FINANCE ADVISORS

FORMERLY LEWIS YOUNG ROBERTSON & BURNINGHAM INC.

TABLE OF CONTENTS

SECTION 1: EXECUTIVE SUMMARY	3
SECTION 2: POPULATION & POPULATION DENSITY	3
SECTION 3: INITIAL & FIVE-YEAR PROJECTIONS OF DEMOGRAPHICS & TAX BASE	6
SECTION 4: INITIAL & FIVE-YEAR COST PROJECTIONS	12
SECTION 5: INITIAL & FIVE-YEAR PROJECTED REVENUE	17
SECTION 6: RISKS & OPPORTUNITIES	22
SECTION 7: ANALYSIS OF NEW REVENUE SOURCES	24
SECTION 8: FISCAL IMPACTS & PROJECTED TAX BURDEN	26
SECTION 9: WATER AVAILABILITY	29
APPENDIX A: PHASE DEVELOPMENT MAPS	30
APPENDIX B: UPC DETERMINATION	33
APPENDIX C: BUILDOUT PROFORMA	35
APPENDIX D: STAKEHOLDER FEEDBACK	36



SECTION 1: EXECUTIVE SUMMARY

LRB Public Finance Advisors was retained by the Office of the Lieutenant Governor (OLG) to complete a preliminary feasibility study related to incorporation of an unincorporated area within Grand County (County) as outlined in Section §10-2a-504. The purpose of the Executive Summary is to fulfill the requirements established in Section §10-2a-504(2)(c)(iii) which requires the feasibility consultant to submit a completed feasibility study, including a one-page summary of the results. This document corrects a previous error found on page 21 regarding the calculation of interest earnings.

The purpose of this study is to compare the fiscal impact to the residents of Kane Creek (Town or Study Area) if the County continues to provide services through the General Fund (GF) or if a newly incorporated Town provides services at a similar quality and level of service. Assuming the incorporated Town assesses a proportionate County tax rate necessary to maintain municipal services, the results shown below include the applicable incorporation costs as outlined in Section §10-2a-510 and assumes the cost for a general government office and public works facility will be paid by the developers during Phase I. **The five-year average revenue margin is at 15.4 percent, allowing the incorporation process to proceed.**

TABLE 1.1: FISCAL IMPACT TO STUDY AREA SUMMARY

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5	AVERAGE
Total Revenue	\$102,984	\$343,930	\$650,781	\$911,183	\$1,051,096	\$611,995
Total Expense	\$145,427	\$340,080	\$581,362	\$725,964	\$797,140	\$517,995
NET REVENUE (EXPENSE)	(\$45,846)	\$434	\$65,991	\$185,219	\$253,956	\$94,000
					Revenue Margin	15.4%

Matching the County's proportionate tax rate is sufficient to meet the expenditures within the Town in years two through five, and an additional Kane Creek rate is necessary to provide sufficient funding for the Study Area in year one.

TABLE 1.2: TAX IMPACT TO STUDY AREA SUMMARY

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
PROPORTIONATE COUNTY RATE	0.001416	0.001416	0.001416	0.001416	0.001416
Additional Levy to Balance Budget	0.012746	0.000000	0.000000	0.000000	0.000000
TOTAL TOWN RATE (COUNTY & TOWN LEVY)	0.014162	0.001416	0.001416	0.001416	0.001416
NET IMPACT ON MEDIAN HOME (\$750K)	\$5,258	\$0	\$0	\$0	\$0

Table 1.3 shows that in the event of incorporation, the tax impact for a median home (valued at \$750,000) in the remaining Grand County in year five is \$694, representing an increase of \$110 above the baseline tax impact of \$584. This assumes that the proposed development occurs but remains within the County. However, it is probable the County's GF would experience a decrease in expenses following the incorporation of the town.

TABLE 1.3: COUNTY PROVIDED SERVICES TAX IMPACT SUMMARY

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
COUNTY RATE	0.001416	0.001416	0.001416	0.001416	0.001416
Tax Impact	0.000024	0.000078	0.000141	0.000191	0.000211
TOTAL COUNTY LEVY (IF KANE CREEK INCORPORATES)	0.001441	0.001494	0.001558	0.001607	0.001627
TAX INCREASE FROM BASELINE ON MEDIAN HOME (\$750K)	\$10	\$32	\$58	\$79	\$87




SECTION 2: POPULATION & POPULATION DENSITY

Utah Code §10-2a-504(3) requires the preliminary feasibility study to include:

an analysis of the likely population and population density within the proposed preliminary municipality area when all phases of the map or plat for the proposed preliminary municipality area are completed; and the population and population density of the area surrounding the proposed preliminary municipality area on the day on which the feasibility request was submitted.

The preliminary incorporation boundary for the Study Area is illustrated in **Figure 2.1** and includes unincorporated areas of Grand County known as Kane Creek.

FIGURE 2.1: STUDY AREA BOUNDARY



POPULATION

Appendix A includes map illustrations detailing the three phases of development within the Study Area. Section §10-2a-504(3)(a)(i) requires the preliminary feasibility study to include an analysis of the likely population within

the preliminary municipality area when all phases of the map are completed. The total estimated population of Kane Creek upon phase completion is calculated at 1,105 persons. This calculation was determined by the Utah Population Committee (UPC) as detailed in **Appendix B**. Using the buildout proforma given by the Sponsors (see **Appendix C**), the UPC assumed that single family homes units are owner-occupied and other residential structures are considered renter occupied. The UPC’s methodology then assumes 99% occupancy for owner-occupied units and 97% occupancy for renter-occupied units. The projected occupied units are then multiplied by Grand County’s persons per occupied housing unit (HU) at 2.37. **Table 2.1** displays the calculated population and households in the Study Area using the UPC’s methodology and buildout proforma. The likely population within the Study Area is calculated at 1,105 people.

TABLE 2.1: KANE CREEK LIKELY POPULATION BY PHASE COMPLETION

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5	TOTAL
Phase 1						
Population¹	180	281	217	55	-	733
Owner Occupied Units ²	10	20	20	-	-	50
Renter Occupied Units ³	68	102	74	24	-	268
Total Residential Units	78	122	94	24	-	318
Phase 2						
Population	-	42	111	111	65	330
Owner Occupied Units	-	6	24	24	15	69
Renter Occupied Units	-	12	24	24	13	73
Total Residential Units	-	18	48	48	28	142
Phase 3						
Population	-	14	14	14	-	42
Owner Occupied Units	-	6	6	6	-	18
Renter Occupied Units	-	-	-	-	-	-
Total Residential Units	-	6	6	6	-	18
Total Projected Population						1,105
Total Projected Residential Units						478

Note 1: Assumes persons per occupied housing unit at 2.37

Note 2: Assumes 99 percent occupancy

Note 3: Assumes 97 percent occupancy

POPULATION DENSITY

The UPC determined Kane Creek’s population density upon plan competition is 4,009 persons per square mile, thus complying with Utah statute that requires the proposed area has an average population density of more than seven people per square mile.¹ The estimated 2024 populations and population density of surrounding communities within the County are shown below.

TABLE 2.2: POPULATION AND POPULATION DENSITY FOR SURROUNDING AREAS

	ESTIMATED POPULATION	LAND AREA (SQUARE MILES)	POPULATION PER SQUARE MILE
Castle Valley ¹	415	8.8	47.2
Moab ¹	5,395	4.8	1,123.7
Kane Creek²	1,105	0.3	4,009.0

Note 1: Estimated population on the day on which the feasibility request was submitted.

Note 2: Estimated population upon plan completion.

¹ Utah Code 10-2a-502(2)(e)(ii)



SECTION 3: INITIAL & FIVE-YEAR PROJECTIONS OF DEMOGRAPHICS & TAX BASE

Utah Code §10-2a-504(3) requires the preliminary feasibility study to include:

an analysis of the following, determined as if, at the time of the analysis, the proposed preliminary municipality area is incorporated as a town with a population of 100 people; and, the initial and projected five-year demographics and tax base within the boundaries of the proposed preliminary municipality area and the surrounding area, including household size and income, commercial and industrial development, and public facilities.

DEMOGRAPHICS

LRB assumed Kane Creek's year one population is 180 people. The projected demographics are calculated using the UPC's methodology and buildout proforma found in **Table 2.1**.

POPULATION PROJECTIONS

For purposes of calculating the surrounding area's initial and five-year projected population and HUs, the average annual growth rate (AAGR) of historic redistricting Census data from 2010 and 2020 was calculated for each community. The AAGR was then applied to the most recent Census data (2022) and onward. The initial and five-year demographic projections are illustrated in **Table 3.3**.

TABLE 3.1: GROWTH RATE DETERMINATION

	2010		2020		AAGR 2010-2020	
	POPULATION	HU	POPULATION	HU	POPULATION	HU
Grand County	9,225	4,816	9,669	5,192	0.5%	0.8%
Castle Valley	319	291	347	289	0.8%	-0.1%
Moab	5,046	2,366	5,366	2,622	0.6%	1.0%
Unincorporated Grand County	3,860	2,159	3,956	2,281	0.2%	0.6%

Source: U.S. Census Bureau, 2010 and 2020 Census Redistricting Data (PL 94-171)

TABLE 3.2: GRAND COUNTY HISTORIC POPULATION FIGURES

	2019	2020	2021	2022	2023	2024 ¹
Grand County	9,640	9,669	9,630	9,680	9,726	9,780
Castle Valley	365	347	398	409	412	415
Moab	5,268	5,366	5,329	5,329	5,362	5,395
Unincorporated Grand County	4,007	3,956	3,903	3,942	3,952	3,970

Note 1: Estimated 2024 population using growth rates calculated in Table 3.1.

Source: U.S. Census Bureau, American Community Survey 5-Year Estimates (DP05) (SUB-IP-EST2023-POP-49)

TABLE 3.3: GRAND COUNTY INITIAL AND 5-YEAR POPULATION FIGURES

	2025	2026	2027	2028	2029	2030
Grand County	9,936	10,172	10,566	10,965	11,203	11,225
Castle Valley	419	423	427	431	435	439
Moab	5,428	5,461	5,495	5,529	5,563	5,597
Unincorporated Grand County	3,989	4,008	4,027	4,046	4,065	4,084

The population projected in year one aligns with §10-2a-504(3)(a)(ii), which requires this analysis assumes the proposed preliminary municipality area is incorporated as a town with a population of 100 people. Five-year



population projections for the Study Area are based on the UPC's methodology and buildout proforma found in **Table 2.1**.

TABLE 3.4: KANE CREEK INITIAL AND 5-YEAR POPULATION FIGURES

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Kane Creek Population	180	517	860	1,040	1,105
Households	78	224	372	450	478
Projected New Homes (See Table 2.1)	78	146	148	78	28
Persons per Household	2.30	2.31	2.31	2.31	2.31

HOUSEHOLD SIZE

The number of households was estimated starting with 2022 occupied households as the base units. The AAGR calculated in **Table 3.1** was then applied to the base to estimate current units and the persons per household (PPH) for this analysis.

TABLE 3.5: INITIAL AND PROJECTED CALCULATED PERSONS PER HOUSEHOLD (PPH)

	2025		2026		2027		2028		2029		2030	
	HU	PPH	HU	PPH	HU	PPH	HU	PPH	HU	PPH	HU	PPH
Grand County	4,434	2.22	4,467	2.25	4,501	2.33	4,535	2.40	4,569	2.43	4,603	2.44
Castle Valley	209	2.00	209	2.02	209	2.04	209	2.06	209	2.08	209	2.10
Moab	2,356	2.30	2,380	2.29	2,405	2.28	2,430	2.28	2,455	2.27	2,480	2.26
Unincorporated Grand County	1,872	2.13	1,882	2.13	1,892	2.13	1,902	2.13	1,912	2.13	1,923	2.12
Kane Creek	NA	NA	78	2.30	224	2.31	372	2.31	450	2.31	478	2.31

Note: PPH figures are calculated based on total population and **occupied** housing units which differ from Census reported average household size based on household population.

Source: U.S. Census Bureau, American Community Survey 5-Year Estimates

INCOME

Utilizing Census tract-level data ², the Study Area's median household income is estimated at \$54,385 as of 2022.

TABLE 3.6: HISTORIC MEDIAN INCOME

	2019	2020	2021	2022	2023 ¹	2024 ¹	2010 - 2020 AAGR
Grand County	\$51,557	\$56,639	\$51,433	\$59,171	\$61,055	\$63,000	3.0%
Castle Valley	\$53,125	\$53,542	\$46,667	\$43,438	\$44,535	\$45,659	4.1%
Moab	\$51,168	\$46,875	\$42,083	\$52,385	\$53,265	\$54,160	3.5%
Kane Creek	NA	\$51,750	\$53,319	\$54,385	\$55,473	\$56,583	2.0% ²

Note 1: Applied growth 2010 - 2020 growth rate to determine estimates.

Note 2: 10-year AAGR not available. Two percent growth is applied instead.

Source: U.S. Census Bureau, American Community Survey 5-Year Estimates (B19019)

TABLE 3.7: INITIAL & PROJECTED MEDIAN INCOME

	2025	2026	2027	2028	2029	2030
Grand County	\$65,006	\$67,077	\$69,213	\$71,417	\$73,692	\$76,039
Castle Valley	\$46,812	\$47,994	\$49,206	\$50,448	\$51,722	\$53,027
Moab	\$55,070	\$55,995	\$56,936	\$57,892	\$58,865	\$59,854
Kane Creek	\$57,714	\$58,868	\$60,046	\$61,247	\$62,472	\$63,721

² Applicable Census tracts include: 3.02




TAX BASE

The tax base of the region is important to consider in this incorporation study as growth in property values, taxable sales, and employment are valuable components when determining feasibility. The following paragraphs discuss the County's regional economy.

REGIONAL ECONOMY

Grand County is located in southeast Utah. The unemployment rate for the County averaged 4.5 percent in October 2024. Unemployment peaked in 2010 at an average of 10.6 percent (see **Figure 3.1**) according to seasonally adjusted data provided by the Utah Department of Workforce Services. Notable shifts in employment occurred between April 2020 and April 2021 as Grand County experienced a 55.7 percent increase in non-farm jobs. More generally, from 2021 to 2022, the County experienced large increases in professional and business services, financial activities, and education and health services, with a total employment change of 7.9 percent. Over the same period, information jobs declined by 16.6 percent and construction jobs decreased by 6.1 percent.


FIGURE 3.1: HISTORIC GRAND COUNTY SEASONALLY ADJUSTED UNEMPLOYMENT RATES



A comparison of quarterly taxable sales trends for the County and State illustrates the percent change from 2018 to 2022 as shown in **Figure 3.2**. Between 2020 and 2021, Q2 experienced an increase of 123.2 percent in taxable sales in the County.



FIGURE 3.2: COMPARISON OF QUARTERLY TAXABLE SALES TRENDS FOR GRAND COUNTY



Historic taxable value figures for Grand County show an AAGR of 13.4 percent from 2019 through 2023. It is important to note that the values below include redevelopment agency values, which will be excluded in the projection of future taxable values.

TABLE 3.8: GRAND COUNTY HISTORIC TAXABLE VALUE

	2019	2020	2021	2022	2023	5 Yr. AAGR
Real: Land	\$540,307,662	\$549,418,430	\$582,216,743	\$597,424,760	\$918,455,520	14.2%
Real: Buildings	\$949,834,446	\$1,032,580,981	\$1,215,890,742	\$1,482,058,500	\$1,823,731,780	17.7%
Personal	\$59,068,599	\$60,530,248	\$63,068,182	\$79,797,432	\$100,706,311	14.3%
Centrally Assessed	\$446,623,367	\$443,408,536	\$488,032,700	\$537,994,602	\$460,142,417	0.7%
TOTAL	\$1,995,834,074	\$2,085,938,195	\$2,349,208,367	\$2,697,275,294	\$3,303,036,028	13.4%
Motor Vehicle	\$12,473,299	\$11,496,469	\$16,579,539	\$15,220,486	\$15,117,179	4.9%

Source: Utah State Tax Commission

STUDY AREA ECONOMY

Study Area is comprised of eight (8) parcels³ with a taxable value of \$3,330,000. The Study Area represents 0.1 percent of the total County taxable value. Based on a review of current property information within the Study Area, the property type of three of the eight parcels is commercial improved. The remaining parcels are vacant land.

TABLE 3.9: ESTIMATE OF STUDY AREA TAXABLE VALUE

CURRENT KANE CREEK TAXABLE VALUE	\$3,330,000
Study Area Taxable Value as % of County Taxable Value	0.10%

Appendix A includes map illustrations detailing the future development within the Study Area. Phase 1, located along the river, includes 67,000 square footage of commercial space, 48 affordable housing units, and 270 residential units. Phase 2, centrally located along the east side of the Study Area border, proposes 142 residential units. The final phase proposes the development of 18 residential units.

³ Parcels considered for this analysis are all those within the Study Area boundary except for roadways.



PROJECTIONS OF COUNTY TAX BASE

Grand County does not have a separate Municipal Service Fund accounting for the cost of services provided to unincorporated county. As a result, this study analyzes the County’s General Fund. Using Utah State Tax Commission data for Grand County, projected taxable value estimates are shown below. **Table 3.11** details the current and projected values based on a five percent growth rate.

TABLE 3.10: HISTORIC GRAND COUNTY TAXABLE VALUE

	2019	2020	2021	2022	2023	2024
Certified Tax Rate Value	\$1,845,296,400	\$1,933,334,163	\$2,179,315,399	\$2,461,104,261	\$3,093,282,013	\$3,414,404,774

Source: Utah State Tax Commission

TABLE 3.11: INITIAL AND 5-YEAR PROJECTED GRAND COUNTY TAXABLE VALUE

	2025	2026	2027	2028	2029	2030
Certified Tax Rate Value	\$3,585,125,013	\$3,764,381,263	\$3,952,600,327	\$4,150,230,343	\$4,357,741,860	\$4,575,628,953

Future sales tax growth projections are based on a general growth estimate of five percent. Historic data from financial reports showed an AAGR of 8.9 percent from 2019 – 2024.

TABLE 3.12: HISTORIC GRAND COUNTY SALES TAX REVENUE

	2019	2020	2021	2022	2023	2024
GF Sales Tax Revenue	\$1,070,752	\$1,085,126	\$1,525,926	\$1,573,919	\$1,678,984	\$1,678,984

TABLE 3.13: INITIAL AND PROJECTED GRAND COUNTY SALES TAX REVENUE

	2025	2026	2027	2028	2029	2030
GF Sales Tax Revenue	\$1,762,933	\$1,851,080	\$1,943,634	\$2,040,816	\$2,142,856	\$2,249,999

PROJECTIONS OF STUDY AREA TAX BASE

Significant factors that will influence revenues within the Study Area include taxable assessed value and taxable sales. Growth in taxable value will influence future property tax revenues and fund general government services. In addition, future sales tax revenues will supplement the General Fund to support the community’s needs. Taxable value growth projections are shown below for the Study Area.

TABLE 3.14: STUDY AREA TAXABLE VALUE

	PROJECTED				
	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Assessed Value	\$3,330,000	\$3,330,000	\$93,360,000	\$238,000,000	\$411,900,000
Prior Year New Growth	\$0	\$90,030,000	\$144,640,000	\$173,900,000	\$90,000,000
TOTAL TAXABLE VALUE	\$3,330,000	\$93,360,000	\$238,000,000	\$411,900,000	\$501,900,000

New growth calculations in the table above are based on the future construction provided in **Appendix C**. Assumptions regarding home values and price per square foot are provided in the **Table 3.15**.



TABLE 3.15: STUDY AREA TAXABLE VALUE NEW GROWTH

	PROJECTED				
	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
RESIDENTIAL DEVELOPMENT					
New Workforce Units ¹	24	24	-	-	-
New Condos/Twin Homes ²	44	90	98	48	13
New Single-Family Detached ³	10	32	50	30	15
Total Residential New Growth	\$61,800,000	\$139,140,000	\$168,900,000	\$90,000,000	\$33,450,000
COMMERCIAL DEVELOPMENT					
New Commercial SF ⁴	15,000	22,000	20,000	-	-
New Overnight Accommodation SF ⁵	10,000	-	-	-	-
Total Commercial New Growth	\$28,230,000	\$5,500,000	\$5,000,000	\$0	\$0
TOTAL NEW GROWTH	\$90,030,000	\$144,640,000	\$173,900,000	\$90,000,000	\$33,450,000

Note 1: Assumes \$100,000 per unit.

Note 2: Assumes \$1.5M per unit.

Note 3: Assumes \$2.4M per unit.

Note 4: Assumes \$250 per commercial SF.

Note 5: Assumes \$2,448 per room SF.

Sales tax revenues are distributed based on two methodologies: 1) the ratio of population; and 2) point of sale, or the location of the sale. Total sales tax collections are distributed equally between these allocation strategies, with 50 percent assigned to point of sale and 50 percent to population. LRB assumed an AAGR of five percent for the population and point of sales projections. Population revenues are distributed to local entities based on the ratio of their population to the State's population. Retail point of sale revenues was calculated using estimated commercial square footage, while online point of sale revenues was calculated using sales tax data from Grand County and E-Commerce figures from the US Census Bureau. The table below summarizes the total estimated sales tax revenue attributed to the Study Area. **Section 5** of this study discusses the population and point of sales methodologies further and **Section 7** outlines the challenges presented by the data utilized to calculate sales tax revenues.

TABLE 3.16: STUDY AREA ESTIMATED SALES TAX REVENUE

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Population Distribution	\$28,003	\$83,128	\$142,705	\$178,314	\$195,616
Point of Sale Distribution	\$55,042	\$114,711	\$175,472	\$194,490	\$207,446
TOTAL ESTIMATED SALES TAX	\$83,044	\$197,839	\$318,177	\$372,805	\$403,062

PUBLIC FACILITIES

There are presently no public facilities within the Study Area boundaries, except for utility-related infrastructure. There are various networks surrounding the proposed municipality including Moonflower Canyon and Moab Rim Trail.



SECTION 4: INITIAL & FIVE-YEAR COST PROJECTIONS

Utah Code §10-2a-504(3) requires the preliminary feasibility study to include:

an analysis of the following, determined as if, at the time of the analysis, the proposed preliminary municipality area is incorporated as a town with a population of 100 people; and, subject to Subsection (3)(b), the initial and five-year projected cost of providing municipal services to the proposed preliminary municipality area, including administrative costs.

GENERAL METHODOLOGY

This section compares the costs to the residents of the Study Area if the County continues to provide services or if a newly incorporated Town provides services. Utah Code requires that the level and quality of governmental services be fairly and reasonably approximate between the two options.⁴ This analysis assumes that several municipal services provided by the County, Special Districts, and private companies will continue to be provided regardless of the incorporation. However, actual service provision will be governed by the newly incorporated municipal governing body.

LRB assumes the following services will be provided by the various entities without any impact from incorporation or non-incorporation:

- Culinary and Secondary Water: Kane Springs Water Company, Grand County Water Conservancy District, Grand County Special Service Water District
- Sewer: Kane Springs Improvement District
- Fire: Moab Valley Fire Protection District
- Parks and Recreation: Grand County Cemetery Maintenance District, Grand County Recreation Service District, Grand County General Fund (there are currently no park facilities within the Study Area)
- Solid Waste: Solid Waste Special Service District #1

The following services were assumed to be provided by the County through the General Fund or through the Town if incorporated:

- General Government Services (including administrative overhead and planning and zoning)
- Law Enforcement and Animal Control
- Roads

COUNTY COST ESTIMATES

Expenditures related to County services were calculated using calendar year (CY) financial reports detailing General Fund actuals from CY 2019 – 2023, updated based on proposed CY 2024 budget information and recommendations from the County Clerk/Auditor. For the purposes of this analysis, the tables below combine the County's projected expenditures into the general categories specified in the financial report.

⁴Utah Code 10-2a-205(4)(b)(i)



TABLE 4.1: COUNTY SCENARIO: HISTORIC AND PRESENT EXPENDITURES

	2019	2020	2021	2022	2023	2024
General Government	\$3,963,843	\$3,755,185	\$3,616,673	\$4,783,217	\$5,839,944	\$5,851,384
Public Safety	\$6,101,488	\$6,052,999	\$7,360,218	\$8,768,057	\$10,899,656	\$11,443,361
Public Works	\$627,040	\$687,573	\$685,216	\$806,141	\$1,015,386	\$951,864
Public Health	\$186,392	\$185,281	\$184,508	\$190,261	\$191,414	\$194,098
Community	\$1,171,635	\$1,054,926	\$1,287,305	\$1,462,157	\$1,788,957	\$1,771,406
Intergovernmental	\$505,561	\$677,206	\$167,217	\$298,909	\$367,565	\$332,621
Transfers Out	\$786,712	\$637,315	\$5,676,874	\$3,323,558	\$7,333,223	\$601,421
TOTAL	\$13,342,671	\$13,050,485	\$18,978,011	\$19,632,300	\$27,436,145	\$21,146,155

Between 2019 and 2024, the County’s GF expenditures grew at an AAGR of 9.6 percent. The five-year projections are based on an analysis of the historic AAGR for each budget line item, which are then applied to account for inflation and anticipated growth.⁵ **Table 4.2** illustrates the County’s estimated expenditures if they are fixed, meaning the General Fund expenditures will not be reduced and the County tax rate will remain the same if there is an incorporation.

TABLE 4.2: COUNTY SCENARIO: INITIAL AND 5-YEAR PROJECTED EXPENDITURES

	2025	2026	2027	2028	2029	2030
General Government	\$7,053,662	\$7,403,026	\$7,777,097	\$8,177,918	\$8,607,712	\$9,068,907
Public Safety	\$11,051,304	\$11,563,122	\$12,104,921	\$12,678,697	\$13,286,600	\$13,930,940
Public Works	\$997,229	\$1,045,143	\$1,095,761	\$1,149,254	\$1,205,802	\$1,265,598
Public Health	\$196,143	\$198,229	\$200,357	\$202,527	\$204,741	\$206,999
Community	\$1,845,277	\$1,923,489	\$2,006,353	\$2,094,208	\$2,187,419	\$2,286,383
Intergovernmental	\$342,600	\$352,878	\$363,464	\$374,368	\$385,599	\$397,167
Transfers Out	\$619,286	\$638,937	\$660,553	\$684,331	\$710,486	\$739,257
TOTAL	\$22,105,500	\$23,124,822	\$24,208,506	\$25,361,303	\$26,588,358	\$27,895,250

STUDY AREA COST ESTIMATES (ASSUMING TOWN INCORPORATION)

Expenditures for the Study Area were calculated using the following methodologies in order to determine an acceptable level of service (LOS):

- Per capita expenditures within the General Fund applicable to unincorporated areas
- Per capita expenditures of comparable cities
- Expenditures per center lane mile of comparable cities
- Average total expenditures per mile based on County estimates

INCORPORATION COST

A one-time cost due to incorporation is included in the analysis for when the population of the Study Area is expected to reach over 99 people.⁶ **Table 2.1** shows the Town’s population exceeding 99 people in 2026. These expenses include the estimated election cost, assuming the incorporation goes to a vote, and the LRB contract cost. According to a discussion with the County Clerk/Auditor, the County administers Castle Valley’s elections in addition to unincorporated areas. To determine the estimated election cost for the Study Area, LRB calculated the per capita cost based on Castle Valley’s FY 2024 election expense. After applying an inflationary increase of

⁵ 510-2a-504(3)(b)(iii)

⁶ 510-2a-510(1)



three percent, the election cost per capita for Castle Valley is \$30. Applying this cost to the Kane Creek 2026 population of 180 results in an election cost of \$5,411.

GENERAL GOVERNMENT SERVICES

Grand County does not have a separate Municipal Service Fund accounting for the cost of services provided to unincorporated county. As a result, this study analyzes the County's General Fund. Based on discussions with the County, expenditures related to assessor, surveyor, and county maintenance are County-level provided services and will remain regardless of incorporation. Assessor, surveyor, and county maintenance expenditures account for approximately 25 percent of total general government expenditures in 2024. A per capita rate removing assessor, surveyor, and county maintenance was calculated to determine Kane Creek's estimated general government expenditures. This figure was extended to 2030 at a three percent annual growth rate and applied to the projected Study Area population.

TABLE 4.3: KANE CREEK GENERAL GOVERNMENT SERVICES 5-YEAR PROJECTED COSTS

	INITIAL	PROJECTED				
		YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
GF Government Services Cost per Capita ¹	\$541	\$557	\$574	\$591	\$608	\$627
Kane Creek Population	-	180	517	860	1,040	1,105
TOTAL GENERAL GOVERNMENT COSTS	\$0	\$100,106	\$296,469	\$507,744	\$632,942	\$692,715

Note 1: Does not include costs related to assessor, surveyor, and county maintenance.

As the Kane Creek population increases to 1,105 people at the end of the five-year period, general government costs also increase. LRB gathered FY 2024 budget information for Green River and Monticello cities to determine the average expense for general government services for municipalities with near or over 1,000 people. After removing budgetary line items determined to be one-time expenses or irrelevant to maintaining the present LOS, the FY 2024 general government expense for Green River was \$1.3M and \$562,700 for Monticello. The projected 2030 cost determined in **Table 4.3** of \$692,715 falls between the Green River and Monticello's average cost. LRB also gathered FY 2024 budget data for communities with under 1,000 people including Bluff, Boulder, Castle Valley, Clawson, Hanksville and Leeds. The average general government expense for municipalities under 1,000 people is roughly \$126,800 and the average per capita rate is \$433. Kane Creek's initial per capita rate exceeds the per capita rate of \$433.

LAW ENFORCEMENT AND ANIMAL CONTROL

LRB gathered budget data from nine comparable Cities in Utah based upon population and geography. Of these nine comparable cities, four communities (Green River, Hanksville, Leeds, and Monticello) provide services related to law enforcement. A per capita rate using these four communities was calculated to determine the proposed Town's law enforcement expense. This figure was extended to 2030 at a three percent annual growth rate and applied to the projected Study Area population.

TABLE 4.4: LAW ENFORCEMENT PER CAPITA COST ALLOCATION

	INITIAL	PROJECTED				
		YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Comp. Public Safety Cost per Capita	\$68	\$70	\$72	\$74	\$76	\$79
Kane Creek Population	-	180	517	860	1,040	1,105
TOTAL LAW ENFORCEMENT COSTS	\$0	\$12,567	\$37,217	\$63,740	\$79,457	\$86,960

Budgetary line items determined to be one-time expenses or irrelevant to maintaining the present level of service were removed from the estimation of this expense. Comparative communities include Green River, Hanksville, Leeds, and Monticello.



ROADS

Of the eight total miles of Kane Creek Road 114, the County currently maintains the 1.34 miles that are in the Study Area. According to the County (see **Appendix D**), this road would remain a County Class B road, and the Town would not incur any cost nor gain any Class C revenue from Kane Creek Road 114. The remaining roads, as well as future roads in Kane Creek are, or will be, privately owned and maintained. According to the Sponsor, an estimate of two miles of private roads will be constructed. To quantify the financial impacts to the taxpayers of the proposed town, this analysis includes potential roads costs, assuming the Town constructs 0.4 miles of roads per year, totaling 2 road miles at the end of the five-year horizon.

TABLE 4.5: KANE CREEK PROJECTED WEIGHTED MILEAGE

	PROJECTED				
	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Kane Creek Mileage	0.40	0.80	1.20	1.60	2.00
UDOT Multiplier*	5	5	5	5	5
TOTAL WEIGHTED MILEAGE	2.00	4.00	6.00	8.00	10.00

*Based on Class B and C Roads Apportionment Formula (Utah Code 72-2-108)

Data on comparable towns were gathered to determine a typical operations and maintenance cost per weighted mile. The data included in the analysis comprises weighted mileage and FY 2024 budgeted roads expenditures. The average cost per weighted mile is estimated at \$1,552.

TABLE 4.6: COMPARABLE TOWN'S ROAD COSTS

	WEIGHTED MILEAGE (FY24)	ROADS EXPENSE FY24	EXPENSE PER WEIGHTED MILE
Bluff	58.60	\$10,020	\$171
Boulder	35.65	\$47,703	\$1,338
Castle Dale	71.14	\$152,961	\$2,150
Castle Valley	46.26	\$94,405	\$2,041
Clawson	14.53	\$1,000	\$69
Green River	48.01	\$33,070	\$689
Hanksville	14.70	\$1,700	\$116
Leeds	52.58	\$92,202	\$1,754
Monticello	84.50	\$476,502	\$5,639
Average Expense per Weighted Mile			\$1,552

Source: State Road GIS Shapefile, UDOT B&C Road Fund Information, Mileage and Annual Summary Reports, Utah State Auditor, Local and State Government Budget Reports

In comparison, LRB gathered 2024 budget information from Grand County's Class B Roads Fund⁷ to determine the average cost per weighted mile for the County. The County's cost per weighted mile is estimated at \$1,181, which is lower than the average cost per weighted mile of \$1,552 calculated in **Table 4.6**. The figure calculated in **Table 4.6** is utilized to project potential road costs in **Table 4.7** and is extended to 2030 at a three percent annual growth rate and applied to the projected Study Area weighted mileage.

⁷ Discussions with County staff indicate the Class B Roads Fund is used to service unincorporated County.



TABLE 4.7: KANE CREEK ROADS EXPENSE 5-YEAR PROJECTED COSTS

	PROJECTED				
	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Cost per Weighted Mile	\$1,552	\$1,598	\$1,646	\$1,696	\$1,747
Kane Creek Weighted Miles	2.00	4.00	6.00	8.00	10.00
TOTAL ESTIMATED ROADS COST	\$3,104	\$6,393	\$9,878	\$13,565	\$17,465

Table 4.8 summarizes the expenditures forecasted for the proposed Study Area. This scenario includes the applicable incorporation costs as outlined in Section §10-2a-510 and assumes the cost for a general government office and public works facility will be paid by the developer during Phase I of development.

TABLE 4.8: KANE CREEK 5-YEAR PROJECTED EXPENDITURES

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Incorporation Costs	\$29,651	\$0	\$0	\$0	\$0
General Government	\$100,106	\$296,469	\$507,744	\$632,942	\$692,715
Law Enforcement & Animal Control	\$12,567	\$37,217	\$63,740	\$79,457	\$86,960
Roads	\$3,104	\$6,393	\$9,878	\$13,565	\$17,465
TOTAL OPERATING EXPENSE	\$145,427	\$340,080	\$581,362	\$725,964	\$797,140



SECTION 5: INITIAL & FIVE-YEAR PROJECTED REVENUE

Utah Code §10-2a-504(3) requires the preliminary feasibility study to include:

an analysis of the following, determined as if, at the time of the analysis, the proposed preliminary municipality area is incorporated as a town with a population of 100 people; and, assuming the same tax categories and tax rates as imposed by the county and all other current service providers at the time during which the feasibility consultant prepares the feasibility study, the initial and five-year projected revenue for the proposed preliminary municipality area.

GENERAL METHODOLOGY

This section compares the revenues the County and Study Area are likely to generate. Similar to the expenditure projections, the revenues were calculated using CY financial reports detailing General Fund actuals from CY 2019 – 2023, updated based on proposed CY 2024 budget information and recommendations from the County Clerk/Auditor. Additional allocation methodologies were utilized based on population, assessed value, and standard State allocation practices.

COUNTY REVENUES

The General Fund revenues were grouped into major categories from a budgeting perspective. The projections below are based on an analysis of the historic AAGR for each budget line item, as well as insight from County staff. Between 2019 and 2024, the County's GF revenue grew at an AAGR of 9.6 percent.

TABLE 5.1: COUNTY GF HISTORIC AND CURRENT REVENUES

	2019	2020	2021	2022	2023	2024
Taxes	\$5,873,055	\$7,258,038	\$8,534,910	\$10,023,474	\$10,316,515	\$10,488,913
Licenses and Permits	\$374,760	\$353,773	\$446,013	\$420,245	\$383,200	\$327,500
Intergovernmental	\$1,959,301	\$3,637,593	\$3,229,419	\$1,947,044	\$7,331,708	\$1,060,658
Charges for Services	\$411,132	\$614,176	\$657,054	\$625,865	\$781,529	\$978,565
Fines and Forfeitures	\$505,274	\$314,887	\$391,616	\$353,182	\$348,490	\$351,000
Interest Income	\$168,386	\$63,449	\$69,389	\$413,383	\$986,227	\$87,533
Miscellaneous	\$647,246	\$540,708	\$756,903	\$862,278	\$1,038,739	\$792,342
Transfers In	\$3,454,052	\$2,664,874	\$6,578,469	\$6,794,693	\$6,250,780	\$7,054,546
TOTAL	\$13,393,206	\$15,447,498	\$20,663,773	\$21,440,164	\$27,437,188	\$21,141,157

Table 5.2 includes property tax projected tied to new growth at five percent. While County General Fund expenditures exceed revenues from 2025 through 2027, an additional levy is not modeled in this analysis due to revenues beginning to exceed expense beginning in 2028. This trend is consistent with historical General Fund budget data, demonstrating revenues exceeding expense by an average of 5.4 percent from 2019 – 2024.

TABLE 5.2: COUNTY SCENARIO INITIAL & 5-YEAR PROJECTED REVENUES

	2025	2026	2027	2028	2029	2030
Taxes	\$10,926,157	\$11,383,994	\$11,863,425	\$12,365,505	\$12,891,339	\$13,442,085
Licenses and Permits	\$335,875	\$344,504	\$353,394	\$362,554	\$371,991	\$381,715
Intergovernmental	\$1,091,968	\$1,125,617	\$1,161,816	\$1,200,795	\$1,242,806	\$1,288,128
Charges for Services	\$1,040,222	\$1,107,981	\$1,182,451	\$1,264,301	\$1,354,268	\$1,453,160
Fines and Forfeitures	\$351,000	\$351,000	\$351,000	\$351,000	\$351,000	\$351,000
Interest Income	\$96,286	\$105,915	\$116,506	\$128,157	\$140,973	\$155,070



	2025	2026	2027	2028	2029	2030
Miscellaneous	\$811,144	\$831,132	\$852,395	\$875,024	\$899,120	\$924,793
Transfers In	\$6,852,725	\$7,512,990	\$8,238,246	\$9,034,946	\$9,910,186	\$10,871,766
TOTAL	\$21,505,376	\$22,763,133	\$24,119,234	\$25,582,283	\$27,161,683	\$28,867,717

STUDY AREA REVENUES (ASSUMING TOWN INCORPORATES)

Revenues for the Study Area were calculated using the following methodologies:

- Property tax based on assessed value and new growth
- State Sales Tax allocation based on population and point of sale
- State Class C Road Fund allocation based on lane miles and population
- License and permit revenues based on estimated expenses
- Interest earnings based on cumulative fund balance

PROPERTY TAX

The property tax revenue calculation is based on the assessed value of the Study Area and applying the projected County levy for general operations. With that said, Grand County does not have a separate Municipal Service Fund accounting for the cost of services provided to unincorporated county. Based on discussions with the County, expenditures related to assessor, surveyor, and county maintenance are provided for all County residents. These county-wide services' expenditures account for approximately 25 percent of total general government expenditures. LRB applied a LOS adjustment for revenues generated from the County equivalent tax rate to be more reflective of the services currently provided to unincorporated county.

New growth calculations in the table above are based on the future construction provided in **Appendix C**. Assumptions regarding home values and price per square foot are provided in the **Table 3.16**.

TABLE 5.3: STUDY AREA TAXABLE VALUE 5-YEAR PROJECTED REVENUES

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Assessed Value	\$3,330,000	\$3,330,000	\$93,360,000	\$238,000,000	\$411,900,000
New Growth	\$0	\$90,030,000	\$144,640,000	\$173,900,000	\$90,000,000
TOTAL TAXABLE VALUE	\$3,330,000	\$93,360,000	\$238,000,000	\$411,900,000	\$501,900,000
County GF Levy	0.001416	0.001416	0.001416	0.001416	0.001416
Tax Revenue from GF Levy	\$4,717	\$132,244	\$337,126	\$583,454	\$710,939
LOS Adjustment	75%	75%	75%	75%	75%
ADJUSTED TAX REVENUE	\$3,538	\$99,183	\$252,844	\$437,591	\$533,204

SALES TAX

Sales tax revenues are distributed based on two methodologies: 1) the ratio of population; and 2) point of sale, or the location of the sale. Total sales tax collections are distributed equally between these allocation strategies, with 50 percent assigned to point of sale and 50 percent to population. Future sales tax growth projections are based on a general growth estimate of five percent.

Population revenues are distributed to local entities based on the ratio of their population to the State's population as a whole. The State population distribution pool in **Table 5.4** represents an average between the applicable current and prior fiscal year to estimate State's sale tax for the calendar year. The calculated average was then multiplied by 50 percent to distribute the total sales tax collections based on population.



TABLE 5.4: RATIO OF POPULATION DISTRIBUTION 5-YEAR PROJECTED REVENUES

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
State Population Distribution Pool	559,948,216	587,945,627	617,342,909	648,210,054	680,620,557
Growth Rate	5.00%	5.00%	5.00%	5.00%	5.00%
State Population	3,595,100	3,656,244	3,718,428	3,781,670	3,845,987
Distributed per Capita	\$155.75	\$160.81	\$166.02	\$171.41	\$176.97
Study Area Estimated Population	180	517	860	1,040	1,105
POPULATION DISTRIBUTION	\$28,003	\$83,128	\$142,705	\$178,314	\$195,616

Point of sale revenues were calculated using estimated retail and hotel square footage. Retail point of sale revenues assume a starting commercial sales per square footage figure of \$300 and is extended to 2030 at a five percent annual growth rate. Hotel point of sale revenues assume a daily rate of \$150 per room with an occupancy adjustment of 70 percent. Online point of sale revenues is calculated using taxable sales revenue from Grand County and are adjusted based on E-Commerce figures from the US Census Bureau. During the third quarter of 2024, E-Commerce sales accounted for 15.6 percent of total store and non-store sales.⁸

TABLE 5.5: POINT OF SALE DISTRIBUTION 5-YEAR PROJECTED REVENUES

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
RETAIL					
Sales Tax per SF ¹	\$315.00	\$330.75	\$347.29	\$364.65	\$382.88
Total Commercial SF	15,000	37,000	57,000	57,000	57,000
Subtotal Retail Sales	\$4,725,000	\$12,237,750	\$19,795,388	\$20,785,157	\$21,824,415
HOTEL					
Daily Rate	\$154.50	\$159.14	\$163.91	\$168.83	\$173.89
Hotel Rate Increase	3%	3%	3%	3%	3%
Hotel Rooms	102	102	102	102	102
Occupancy	70%	70%	70%	70%	70%
Subtotal Hotel Sales	\$4,026,425	\$4,147,217	\$4,271,634	\$4,399,783	\$4,531,776
ONLINE					
Grand County Taxable Sales	\$810,957,533	\$851,505,410	\$894,080,680	\$938,784,714	\$985,723,950
% E-Commerce	16%	16%	16%	16%	16%
Grand County E-Commerce Sales	\$126,432,067	\$132,753,670	\$139,391,354	\$146,360,921	\$153,678,967
Grand County Population	10,072	10,466	10,865	11,103	11,225
Grand County Per Capita E-Commerce	\$12,553	\$12,685	\$12,829	\$13,182	\$13,690
Kane Creek Population	180	517	860	1,040	1,105
Subtotal Online Sales	\$2,256,938	\$6,557,288	\$11,027,294	\$13,713,151	\$15,132,997
Point of Sale Allocation	0.50%	0.50%	0.50%	0.50%	0.50%
TOTAL POINT OF SALE REVENUE	\$55,042	\$114,711	\$175,472	\$194,490	\$207,446

Note 1: Assumes commercial sales per SF of \$300. Figure is extended to future years at a five percent growth rate.

TABLE 5.6: TOTAL SALES TAX 5-YEAR PROJECTED REVENUES

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Population Distribution (Table 5.4)	\$28,003	\$83,128	\$142,705	\$178,314	\$195,616
Retail Point of Sale (Table 5.5)	\$55,042	\$114,711	\$175,472	\$194,490	\$207,446
TOTAL ESTIMATED SALES TAX	\$83,044	\$197,839	\$318,177	\$372,805	\$403,062

⁸ US Census Bureau. (2024, November). Quarterly Retail E-Commerce Sales. Retrieved from <https://www.census.gov/retail/ecommerce.html>



CLASS C ROAD FUND

Of the eight total miles of Kane Creek Road 114, the County currently maintains the 1.34 miles that are in the Study Area. According to the County (see **Appendix D**), this road would remain a County Class B road, and the Town would not incur any cost nor gain any Class C revenue from Kane Creek Road 114. The remaining roads in Kane Creek are privately owned and maintained. This analysis assumes that the Town will construct a total of two miles of roads by the end of five-year horizon.

TABLE 5.7: KANE CREEK PROJECTED WEIGHTED MILEAGE

	PROJECTED				
	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Kane Creek Mileage	0.40	0.80	1.20	1.60	2.00
UDOT Multiplier*	5	5	5	5	5
TOTAL WEIGHTED MILEAGE	2.00	4.00	6.00	8.00	10.00

*Based on Class B and C Roads Apportionment Formula (Utah Code 72-2-108)

Table 5.8 depicts the growth rate calculated and subsequently applied to forecast key variables (statewide total distribution pool, lane miles, weighted miles).

TABLE 5.8: CLASS B&C ROADS HISTORIC AAGR

	2019	2020	2021	2022	2023	2024 ¹	2025 ¹	2019 - 2023 AAGR
Total Distribution Pool	179,188,729	177,562,815	194,764,526	203,134,579	216,853,217	227,446,713	238,557,711	4.89%
Lane Miles Pool	89,594,365	88,781,407	97,382,263	101,567,289	108,426,609	113,723,356	119,278,856	4.89%
Statewide Weighted Miles	121,813	122,842	124,521	125,318	126,997	128,328	129,672	1.05%

Note 1: Estimated using 2019 - 2023 AAGR.

Source: UDOT B&C Road Fund Information, Mileage and Annual Summary Reports

Utilizing **Table 5.8's** calculated weighted mileage for the Study Area and methodology delineated in Utah State Code, the Study Area's distribution can be calculated.

TABLE 5.9: CLASS B&C ROADS INITIAL AND 5-YEAR PROJECTED REVENUES

	PROJECTED				
	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Total Distribution Pool	250,211,493	262,434,574	275,254,764	288,701,234	302,804,577
Lane Miles Pool	125,105,747	131,217,287	137,627,382	144,350,617	151,402,288
Statewide Weighted Miles	131,030	132,403	133,790	135,191	136,607
Distribution Per Weighted Mile	955	991	1,029	1,068	1,108
Estimated Weighted Miles	2.00	4.00	6.00	8.00	10.00
Lane Mile Distribution	\$1,910	\$3,964	\$6,172	\$8,542	\$11,083
State Population	3,595,100	3,656,244	3,718,428	3,781,670	3,845,987
State Distribution per Capita	\$34.80	\$35.89	\$37.01	\$38.17	\$39.37
Study Area Population	180	517	860	1,040	1,105
Population Distribution	\$6,256	\$18,552	\$31,814	\$39,709	\$43,514
TOTAL STUDY AREA DISTRIBUTION	\$8,166	\$22,517	\$37,986	\$48,251	\$54,597



LICENSES & PERMITS

Reflecting that business licenses and building permit fees, likely expected for the Study Area upon consideration of planned development, are charged at a rate that is proportional to the costs to the incorporated Town to issue them, licenses & permits revenue in this study are tied directly to estimated costs for planning and zoning. For this study, half of the estimated costs for planning and zoning are considered attributable to managing licenses and permits, thus expected licenses & permits revenue is equal to that value. LRB isolated the planning and zoning costs from the total general government expense calculated in **Table 4.2** to determine the license and permit revenues.

TABLE 5.10: LICENSES & PERMITS 5-YEAR PROJECTED REVENUES

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
LICENSES & PERMITS REVENUE	\$8,236	\$24,392	\$41,774	\$52,074	\$56,992

INTEREST EARNINGS

Interest earnings are calculated based on a 1.50 percent interest rate on any fund balance carryover.

OTHER REVENUE CONSIDERATIONS

Additional types of revenue streams may be collected including transient room taxes, grants, and weed control fees. These alternate revenue mechanisms will be explored in greater detail in **Section 7**.

Table 5.11 summarizes the revenues forecasted for the proposed Study Area. This allows the proposed Town's fund balance to increase overtime and produce interest revenues.

TABLE 5.11: KANE CREEK 5-YEAR PROJECTED REVENUES

	PROJECTED				
	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Property Tax ¹	\$3,538	\$99,183	\$252,844	\$437,591	\$533,204
Sales & Use Tax	\$83,044	\$197,839	\$318,177	\$372,805	\$403,062
Class C Roads	\$8,166	\$22,517	\$37,986	\$48,251	\$54,597
Licenses & Permits	\$8,236	\$24,392	\$41,774	\$52,074	\$56,992
Interest Earnings	\$0	\$0	\$0	\$462	\$3,241
TOTAL OPERATING REVENUES	\$102,984	\$343,930	\$650,781	\$911,183	\$1,051,096

Note 1: Property tax revenue generated in Kane Creek assuming equivalent County rate. Property tax revenue is then adjusted by 75%.



SECTION 6: RISKS & OPPORTUNITIES

Utah Code §10-2a-504(3) requires the preliminary feasibility study to include:

an analysis of the following, determined as if, at the time of the analysis, the proposed preliminary municipality area is incorporated as a town with a population of 100 people; and, the risks and opportunities that might affect the actual costs described in Subsection (3)(a)(ii)(B) or the revenues described in Subsection (3)(a)(ii)(C) of the proposed preliminary municipality area.

RISKS

Discussions with the County pointed to concern towards the impacts on infrastructure regardless of incorporation. The County Clerk/Auditor and Roads Department noted that Kane Springs Road is commonly used for recreation purposes and noted that road width improvements are most likely necessary to continue providing adequate recreation access. This study does not contemplate costs related to future CIP, as capital improvements that are not currently being provided by the County through the GF are not included in the current LOS. Should the Town incorporate, the Town could complete a master plan that identifies future CIP. These additional costs can be mitigated by grants, tax or rate increases, or impact fees. The County also acknowledged the potential fiscal impacts on storm water mitigation and emergency management from developing on a floodplain.

Roads within the boundary would most likely be privately funded and maintained. Therefore, expenses associated with roads would be the responsibility of the applicable Homeowner Association (HOA). In **Appendix D**, stakeholders pointed to the possible cost burden to residents as a result of HOA fees. While the Study illustrates potential costs if the proposed Town decides to maintain the new roads, actual road expenses will vary and be determined based on the contracts established by the newly incorporated town.

Several variables influence the Study Area's taxable assessed value and taxable sales revenues including new growth calculations based on future residential and commercial construction and general assumptions regarding home values and price per square foot. This analysis does not include a market feasibility study to determine whether the proposed commercial square footage is supportable. The lack of a market feasibility analysis presents a certain risk in that the study assumes the planned development will occur upon incorporation. Additionally, the financial feasibility of this study may be jeopardized if cost assumptions for home values and price per square foot are reduced.

As Kane Creek does not presently generate retail point of sale revenue, the fiscal sustainability of the Study Area is contingent upon proposed commercial and industrial development. In the event that this development does not transpire or proceeds at slower rates than modeled in this study, it is likely that total revenues would not offset total expenditures. Additionally, inflationary pressure will affect the Study Area, as well as the GF. The impact of inflation may be more pronounced within the Study Area.

OPPORTUNITIES

Opportunities in the Study Area post-incorporation may include self-governance, ability to develop public facilities, zoning and land-use authority, more local representation, and more direct control over the future of the area. Incorporation may increase local authority to meet the requests and needs of residents.



Specific goals related to population growth, economic growth and development, business licensing, and zoning policies could be addressed by the newly incorporated area. However, it is important to note that these elements may result in an increase in costs beyond what has been presented in this study.



SECTION 7: ANALYSIS OF NEW REVENUE SOURCES

Utah Code §10-2a-504(3) requires the preliminary feasibility study to include:

an analysis of the following, determined as if, at the time of the analysis, the proposed preliminary municipality area is incorporated as a town with a population of 100 people; and, new revenue sources that may be available to the proposed preliminary municipality area that are not available before the area incorporates, including an analysis of the amount of revenues the proposed preliminary municipality area might obtain from those revenue sources.

TRANSIENT ROOM TAX

Temporary lodging (i.e., hotel, motel, inn, tourist home, trailer court, or campground) used for less than thirty days are subject to both sales and transient room tax.⁹ To receive revenue from a transient room tax levy, Kane Creek may impose up to one percent tax on temporary lodging upon incorporation. Depending on whether some of the proposed commercial development in the Study Area will be comprised by temporarily lodging, a transient room tax may be a new revenue source the Town could contemplate.

FRANCHISE TAX - MUNICIPAL ENERGY SALES AND USE TAX

Municipalities may adopt a tax on gas and electricity delivered within their jurisdiction. These taxes are collected by a seller and held in trust for the benefit of the locality imposing the tax.

DEBT FINANCING

Debt financing may be utilized to amortize larger capital costs over time, rather than addressing those costs in a shorter period. This does not introduce new revenues (interest and cost of issuance expenses add to the overall cost assumptions), but it does serve as a funding tool to allow for the construction of public facilities.

GRANTS

Most of the comparable cities included in the analysis receive grant monies, although it is uncertain which grants the Town would be eligible for.

IMPACT FEES

As mentioned in **Section 6**, the Town, if incorporation occurs, could begin to provide services (e.g., streets, parks) and would be able to charge impact fees to new development. It is important to note that the Town cannot assess impact fees if the eligible categories are not serviced by the Town.

FEES FOR SERVICES

The newly incorporated area will have the ability to adopt necessary fees related to services provided. This study has followed the statutory requirement to maintain the same level of service currently provided to residents based on the expenditures and revenue sources utilized within the GF. However, the Town may be able to increase revenues by assessing specific fees for services. These may include transportation fees, recreation fees, disproportionate fees, and/or utility fees. It is important to note that these fees would be an additional cost to residents, beyond what is shown in the following sections.

⁹ Utah State Tax Commission. (2023, Nov 3). Transient Room Taxes. Retrieved from <https://tax.utah.gov/sales/transientroom>



HOA FEES

Homeowner Association (HOA) fees or Property Owners Association (POA) fees may serve as a funding source for road maintenance and other services. To quantify the financial impacts to the taxpayers of the proposed town, this analysis includes potential roads costs, and all other government expenses, assuming the Town is responsible for covering these expenses. However, HOA or POA fees may be utilized for these services.



SECTION 8: FISCAL IMPACTS & PROJECTED TAX BURDEN

Utah Code 510-2a-504(3) requires the preliminary feasibility study to include:

an analysis of the following, determined as if, at the time of the analysis, the proposed preliminary municipality area is incorporated as a town with a population of 100 people: the projected tax burden per household of any new taxes that may be levied within the proposed preliminary municipality area within five years after incorporation as a town; and the fiscal impact of the proposed preliminary municipality area's incorporation as a town on unincorporated areas, other municipalities, special districts, special service districts, and other governmental entities in the county.

The purpose of this study is to project and compare the impact of incorporation of the Study Area to the fiscal impact of remaining within the County service area. The following section details the impact to residents in the Study Area, as well as to the County.

FISCAL IMPACTS & TAX BURDEN ON THE COUNTY

A comparison of projected revenues and expenditures produces a surplus beginning in year three based on the County's projected 2025 rate of .001416, as shown in **Table 8.1**. The baseline tax impact to a primary residence in Grand County valued at \$750,000¹⁰ is \$584.

TABLE 8.1: FISCAL IMPACTS ON GRAND COUNTY

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
REVENUES					
COUNTY RATE	0.001416	0.001416	0.001416	0.001416	0.001416
Taxes	\$11,383,994	\$11,863,425	\$12,365,505	\$12,891,339	\$13,442,085
Licenses and Permits	\$344,504	\$353,394	\$362,554	\$371,991	\$381,715
Intergovernmental Revenues	\$1,125,617	\$1,161,816	\$1,200,795	\$1,242,806	\$1,288,128
Charges for Services	\$1,107,981	\$1,182,451	\$1,264,301	\$1,354,268	\$1,453,160
Fines and Forfeitures	\$351,000	\$351,000	\$351,000	\$351,000	\$351,000
Interest Income	\$105,915	\$116,506	\$128,157	\$140,973	\$155,070
Miscellaneous	\$831,132	\$852,395	\$875,024	\$899,120	\$924,793
Transfers In	\$7,512,990	\$8,238,246	\$9,034,946	\$9,910,186	\$10,871,766
TOTAL REVENUES	\$22,763,133	\$24,119,234	\$25,582,283	\$27,161,683	\$28,867,717
EXPENDITURES					
General Government	\$7,403,026	\$7,777,097	\$8,177,918	\$8,607,712	\$9,068,907
Public Safety	\$11,563,122	\$12,104,921	\$12,678,697	\$13,286,600	\$13,930,940
Public Works	\$1,045,143	\$1,095,761	\$1,149,254	\$1,205,802	\$1,265,598
Public Health	\$198,229	\$200,357	\$202,527	\$204,741	\$206,999
Community	\$1,923,489	\$2,006,353	\$2,094,208	\$2,187,419	\$2,286,383
Intergovernmental	\$352,878	\$363,464	\$374,368	\$385,599	\$397,167
Transfers Out	\$638,937	\$660,553	\$684,331	\$710,486	\$739,257
TOTAL EXPENDITURES	\$23,124,822	\$24,208,506	\$25,361,303	\$26,588,358	\$27,895,250
NET REVENUES (EXPENSE)	(\$361,689)	(\$89,272)	\$220,979	\$573,324	\$972,468
County Taxable Value	\$3,764,381,263	\$3,952,600,327	\$4,150,230,343	\$4,357,741,860	\$4,575,628,953
TOTAL COUNTY RATE	0.001416	0.001416	0.001416	0.001416	0.001416
BASELINE IMPACT ON COUNTY MEDIAN HOME (\$750K)	\$584	\$584	\$584	\$584	\$584

¹⁰ Rocket Homes. (2024, Dec 6). Grand County Housing Market Report . Retrieved from <https://www.rockethomes.com/real-estate-trends/ut/grand-county>



The Study Area may continue to receive County Services at the level of service currently provided as a part of the GF with negligible additional costs as compared with the current County tax levies.

In the event of incorporation, the County would likely experience a loss of revenue, modeled here as equivalent to the projected revenue for the Study Area, resulting in the need for an additional property tax increase in year one over the baseline County levy. This increase represents lost revenue for municipal services, as well as revenues gained through the Sheriff's Department. The contract revenue is estimated at \$12,567 in year one. The net impact of the Town incorporation is a loss of \$90,417 in revenues in 2026, as illustrated in **Table 8.2**. This potential lost revenue is based upon the development scenario considered within this study for an incorporated town. However, this development scenario would likely not transpire if the Study Area were to remain unincorporated. As a result, it is unlikely that the GF levy would need to be raised to the extent modeled here to account for lost revenue from the Study Area in the event of incorporation.

It is possible that the newly incorporated town may contract for additional services with the County (e.g., engineering, planning, and building permitting), resulting in additional contract revenues flowing to the County. Furthermore, it is probable the County's GF would experience a decrease in expenses following the incorporation of the town.

TABLE 8.2: IMPACT TO COUNTY GF

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
Potential Lost Revenue	(\$102,984)	(\$343,930)	(\$650,781)	(\$911,183)	(\$1,051,096)
Contract Revenue	\$12,567	\$37,217	\$63,740	\$79,457	\$86,960
NET IMPACT TO COUNTY GF	(\$90,417)	(\$306,713)	(\$587,041)	(\$831,726)	(\$964,136)
Tax Impact	0.000024	0.000078	0.000141	0.000191	0.000211
County Levy (If Kane Creek Incorporates)	0.001441	0.001494	0.001558	0.001607	0.001627
Estimated Impact on Median Home (\$750K)	\$594	\$616	\$643	\$663	\$671
Baseline Impact on Median Home (\$750K)	\$584	\$584	\$584	\$584	\$584
TAX INCREASE FROM BASELINE	\$10	\$32	\$58	\$79	\$87

FISCAL IMPACTS & TAX BURDEN ON STUDY AREA

The following section analyzes the fiscal impacts of a Town incorporation, which includes the incorporation costs outlined in §10-2a-510 and assumes the developers will construct a government office building during Phase I of development.

The results in **Table 8.3** assume the incorporated Town will assess a proportionate County tax rate necessary to maintain municipal services described in previous sections. A review of projected revenues under the proportionate County levy relative to proposed expenses illustrates a deficit in year one. Incorporation costs and delayed development contribute to the escalated costs in the first years of incorporation. Beginning in year two, revenues exceed expenditures within the Town and no additional Kane Creek rate is necessary to provide sufficient funding for the Study Area. The annual revenue margin is at an average of 15.4 percent over the five-year window of this study, meeting the requirement outlined in UCA §10-2a-504(4) to allow the process of incorporation to proceed.



TABLE 8.3: KANE CREEK FISCAL IMPACT

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5	AVERAGE
REVENUES						
PROPORTIONATE COUNTY RATE	0.001416	0.001416	0.001416	0.001416	0.001416	
Property Tax	\$3,538	\$99,183	\$252,844	\$437,591	\$533,204	\$265,272
Sales & Use Tax	\$83,044	\$197,839	\$318,177	\$372,805	\$403,062	\$274,985
Class C Roads	\$8,166	\$22,517	\$37,986	\$48,251	\$54,597	\$34,303
Licenses & Permits	\$8,236	\$24,392	\$41,774	\$52,074	\$56,992	\$36,694
Interest Earnings	\$0	\$0	\$0	\$462	\$3,241	\$741
Total Revenues	\$102,984	\$343,930	\$650,781	\$911,183	\$1,051,096	\$611,995
EXPENDITURES						
Incorporation Costs	\$29,651	\$0	\$0	\$0	\$0	\$5,930
General Government	\$100,106	\$296,469	\$507,744	\$632,942	\$692,715	\$445,995
Law Enforcement	\$12,567	\$37,217	\$63,740	\$79,457	\$86,960	\$55,988
Roads	\$3,104	\$6,393	\$9,878	\$13,565	\$17,465	\$10,081
Total Expenditures	\$145,427	\$340,080	\$581,362	\$725,964	\$797,140	\$517,995
NET (REVENUE MINUS EXPENSE)	(\$42,443)	\$3,850	\$69,419	\$185,219	\$253,956	\$94,000
REVENUE (EXPENSE) MARGIN*						15.4%

*Margin calculated by dividing net revenue by total revenues.

In year one, matching the County's proportionate tax rate is not sufficient to meet the expenditures within the Town and an additional Kane Creek rate is necessary to provide sufficient funding for the Study Area. The 2026 Town rate (.014162) is the sum of the County GF proportionate rate (.001416) and the Kane Creek rate (.012746). The tax impact within the Study Area is estimated at \$5,842 for a primary residence valued at \$750K in year one. This represents an increase of \$5,258 above the projected County levy of \$584, assuming the property tax levy remains unchanged following incorporation.

TABLE 8.4: KANE CREEK TAX BURDEN

	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5
EQUIVALENT COUNTY RATE	0.001416	0.001416	0.001416	0.001416	0.001416
Additional Levy to Balance Budget*	0.012746	0.000000	0.000000	0.000000	0.000000
TOTAL TOWN RATE (COUNTY & TOWN LEVY)**	0.014162	0.001416	0.001416	0.001416	0.001416
Estimated Certified Tax Value	\$3,330,000	\$93,360,000	\$238,000,000	\$411,900,000	\$501,900,000
Estimated Town Impact (Median Home \$750K)	\$5,842	\$584	\$584	\$584	\$584
County Baseline Impact (Median Home \$750K)	\$584	\$584	\$584	\$584	\$584
NET IMPACT	\$5,258	\$0	\$0	\$0	\$0

*Kane Creek levy calculated based on estimated assessed value and 75% adjustment.

** Based on the sum of the "Combined County Rate" plus the "Additional Levy to Balance Budget".



SECTION 9: WATER AVAILABILITY


Utah Code §10-2a-504(3) requires the preliminary feasibility study to include:

an analysis regarding whether sufficient water will be available to support the proposed preliminary municipality area when the development of the area is complete.


Kane Springs Water Company will serve as the municipal water supply upon incorporation. The company presently has approximately 422-acre feet of water rights. Water sources include five wells and the ability to pull directly from the Colorado River. The developer estimates that the proposed development will likely need 200-acre feet, resulting in sufficient water supply to support the proposed preliminary municipality area when the development of the area is complete.



APPENDIX A: PHASE DEVELOPMENT MAPS



PRELIMINARY FEASIBILITY STUDY FOR THE PROPOSED INCORPORATION OF KANE CREEK
 GRAND COUNTY, UTAH



APPENDIX B: UPC DETERMINATION



Memorandum

June 24, 2024

To: Jordan Schwanke, Office of the Lieutenant Governor
 From: Eric Aibers, Public Policy Analyst, Kem C. Gardner Policy Institute
 CC: Mallory Bateman, Director of Demographic Research, Kem C. Gardner Policy Institute
 Subject: Kane Creek Preliminary Municipal Feasibility Review

Introduction

This review follows the feasibility request for the preliminary municipality of Kane Creek, in Grand County, Utah. This memo determines whether Kane Creek meets the population, density, and contiguity requirements for preliminary incorporation (defined in Utah Code 10-2a-503).

The Utah Population Committee (UPC) analysis indicates that Kane Creek meets the preliminary incorporation requirements.

Table 1: Initial Feasibility Requirements for West Hills Incorporation

Criteria	Meets Criteria?	Requirement by Statute	West Hills Details
Population	Yes	Population must be equal to or greater than 100 when all phases of the plan are completed.	Population estimate upon plan completion: 1,105
Population Density	Yes	Density must be seven people per square mile or higher	Population density estimate upon plan completion: 4,009 persons per square mile.
Contiguity	Yes	Area is contiguous, does not have a strip of land connecting geographically separate areas	The proposed boundary covers a contiguous area

Population data source: U.S. Census Bureau, 2020 Census

Note: Requirements are summarized; Full statutory requirements are delineated in Utah Code 10-2a-502.

Table 2: Kane Creek Population Estimate

Phase	Population Estimate
Phase 1	733
Phase 2	330
Phase 3	42
Total	1105



Methodology
Housing Unit Method

The UPC uses the housing unit method of estimation to determine the population of places seeking to incorporate. For preliminary municipal incorporations where the population of the defined area is zero, estimates of housing units are taken as given from the description of the preliminary municipality.

The method assumes that single family homes and other residential structures with less than 12 units are owner-occupied. Residential structures with 12 or more units are considered renter occupied. The method assumes 99% occupancy for owner-occupied units and 97% occupancy for renter-occupied units. Occupied units are then multiplied by county-level persons per household (2.37 for Grand County) from the 2020 census to determine household population.



APPENDIX C: BUILDOUT PROFORMA

Property Section	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Total
Phase 1 - Lower Riverside Land							
BM-U Mixed Use, Commercial/Antiquity		16,000	22,000	20,000			57,000
OA Hotel, Commercial Space		10,000					10,000
Total Commercial Sq Ft	0	26,000	22,000	20,000	0	0	67,000
OA Overnight Accommodations		102					102
R-AF-R Residential, Affordable Housing (Rental)		24	24				48
Total Units - OA & Long Term Rental	0	126	24	0	0	0	150
R-MU One-story Mixed Use (retail)			24	36			60
BM-F Central Amenity Area, Condos		24	24	8			56
R-SF Residential, Single-Family Detached		19	29	29			77
R-TW Residential, Town Homes		22	33	32	24		114
Total Phase 1 For Sale Units	0	54	98	94	24	0	270
Phase 2 - Main Upper Land							
R-SF Residential, Single-Family Detached			6	24	24	15	60
R-TH Residential, Townhouse Attached			12	24	24	12	72
Total Phase 2 For Sale Units	0	0	18	48	48	27	142
Phase 3 - North Upper Land							
R-SF Residential, Single-Family Detached			6	6	6		18
Total Phase 3 For Sale Units	0	0	6	6	6	0	18
All Phases - Total For Sale Units	0	54	122	148	78	28	430
All Phases - Total All Residential Unit Types	0	78	146	148	78	28	478

Assumptions

- Schedule is based on closing and delivery for all built product; R-SF is based on expected build completion by buyers (18 month build cycle)
- Commercial Mixed Use developed in three locations shown on plan, starting from North to South end of development
- Hotel Completed by end of Year 2
- Residential Affordable Product built in 2/24 unit phases
- Central Amenity Condos are first product built on the ground, mix of 8 and 12 unit buildings
- Upper Land units deferred opening until 16-24 months from Lower Land Launch
- Assume incorporation four years from first Certificate of Occupancy at month 18 after launch / Time to full incorporation from Preliminary Municipality at approx. 5-6 years
- Gross initial sales prices for Property Taxes: Condos at \$800K-\$1.2M, Townhomes & Townhomes at \$1.8M-\$2.2M, Residential lots from \$1.8M-\$2.5M (Home Values of \$3-\$5M)

PHASE #	KEY	LAND USE	LAND AREA	DWELLING UNITS	OVERNIGHT ACCOMMODATION UNITS*	SINGLE FAMILY DETACHED UNITS	TOWN HOME UNITS	ROWHOUSE UNITS	CONDO UNITS	TOTAL FOR SALE UNITS (TOTAL UNITS)	AFFORDABLE HOUSING UNITS	STYLS (100% AFFORDABLE)	Capacity (Total All Unit Types)
1	BM-U	Mixed Use, Commercial/Antiquity	11.8 acres	17,000					16,000	33,000		0	33,000
	OA	Hotel/Accommodations	12.8 acres	10,000	102								102
	R-MU	One-story Mixed Use (retail)	7.8 acres			24				24			24
	R-TW	Residential, Town Homes	15.8 acres				29			29			29
	R-SF	Residential, Single-Family Detached	11.8 acres				19			19			19
	BM-F	Central Amenity Area, Condos	11.8 acres				24			24			24
	Sub-Total		70.8 acres	67,000 sq ft	102	102	94	29	0	67	200	0	200
2	R-SF	Residential, Single-Family Detached	12.8 acres			6				6			6
	R-TH	Residential, Townhouse Attached	12.8 acres			12				12			12
	R-SF	Residential, Single-Family Detached	12.8 acres			6				6			6
	Sub-Total		38.4 acres			18	12	0	0	18	0	0	30
3	R-SF	Residential, Single-Family Detached	12.8 acres			6				6			6
	R-SF	Residential, Single-Family Detached	12.8 acres			6				6			6
	Sub-Total		25.6 acres			12	0	0	0	12	0	0	12
Total		134.8 acres	137,000 sq ft	114	114	114	29	0	85	430	0	430	478

* Overnight Accommodations are based on 100% occupancy

† Total units include all units in all phases

‡ Total units include all units in all phases

dti
DESIGN

KANE CREEK PRESERVATION & DEVELOPMENT
PHASE 1-2A

KANE CREEK PRESERVATION & DEVELOPMENT, LLC
3000 SOUTH 2000 WEST, SUITE 100
SALT LAKE CITY, UT 84119

2



APPENDIX D: STAKEHOLDER FEEDBACK

Section §10-2a-504(3)(c) outlines the stakeholders that were consulted and received the draft of the preliminary feasibility study on December 11, 2024 to review and provide comment to the draft. The following appendix includes feedback from Grand County during the draft phase of the study. LRB's response to each item is in red.



Grand County stakeholders have reviewed the PRELIMINARY FEASIBILITY STUDY FOR THE PROPOSED INCORPORATION OF KANE CREEK, prepared by LRB Public Finance Advisors and dated December 2024 (hereinafter "the STUDY"). Below is the review.

1. The STUDY assumes the 1.34 miles of paved road, Route #114 - Kane Creek Boulevard (STUDY erroneously gives the name Canyon Road), would become a Class C road upon incorporation. This is not accurate, as an important collector road in the Grand County road system, this road would remain a County Class B road as permitted by Utah statute 17-50-305. Exclusion of this road substantially changes all the analysis and results presented in the STUDY, especially the predicted Class C road revenues.

LRB Response: The Study has removed the 1.34 miles of paved roads, assuming it would remain County maintained. Any revenue or cost related to Kane Creek Road 114 has been removed from the analysis.

2. The STUDY ignores all proposed new roads stating that these roads would be privately maintained. Presumably funding for this road maintenance will come from Property Owners Association (POA) fees. I think it important to consider that POA fees are essentially a property tax burden, and the POA and Town boundaries will be one and the same. The real cost to maintain all of the new circulation roads could be a significant cost burden to a limited population. If the purpose of the STUDY is to demonstrate the necessary property tax revenue, ignoring all the road maintenance costs as a private cost may not give an accurate picture.

LRB Response: The County property tax levy does not include the maintenance for private roads. For purposes of determining feasibility and in following Section 10-2a-504(3)(a)(ii)(B), expense related to private roads is not required. With that said, to illustrate potential costs to new roads, LRB has included a calculation (see Table 4.5 - 4.7) of road expense assuming new roads would be maintained by the new Town, although it is likely that new road costs would be incurred by residents via HOA fees. While adding these potential costs does not jeopardize the financial feasibility, the risk section will include this concern.

3. The STUDY develops a road operations maintenance unit cost by pulling from nine comparable towns. The unit costs from these nine towns varied widely (from \$69/mile to \$5,639/mile) and all the towns have 2 to 12 times the amount of mileage that the STUDY is based on. The actual road operation expenditures could vary widely from the STUDY estimate.

LRB Response: The average cost per mile from comparable towns (\$1,552) is higher than the average cost per mile from the County's Class B road expense (\$1,181). LRB will include the County's calculation for reference and language to clarify that we are using the higher cost estimate.

4. The STUDY does not account for the large up-front cost required to establish a road maintenance department. Initial equipment purchase could be \$500,000 to \$1,000,000 plus. The extremely small mileage amount does not offer any economy of scale.

LRB Response: A municipality at this size, especially during development and with all new roads, would be highly unlikely to have an in-house roads maintenance department. The Sponsor indicated the new Town would likely rely on a third party civil engineering contractor to assess and recommend needed repairs and the Town would then contract the work out for repairs.

5. Page 15 of the STUDY under the heading ROADS: paragraph under table 4.5 3rd sentence says " Canyon Road 114" and in table 4.6. This should be Kane Creek Road 114.

LRB Response: The Study has removed all references to Canyon Road 114 and has replaced it with Kane Creek Road 114.

6. Page 15 of the STUDY paragraph under Table 4.5 sentence 4 talks about maintenance expenses and types of maintenance. I suggest adding asphalt patching, rock fall removal, snow removal, flood cleanup and repair, culvert cleaning and repair, mowing roadside vegetation and signage repair/replacement.

LRB Response: The maintenance expense of Kane Creek Road 114 is no longer included in the Study, as item #1 stated that this road will remain a County Class B road.



Exhibit D
to Petition for Incorporation of Echo Canyon,
a Preliminary Municipality
Proposed Site Plan



88 E Center Street
Moab, UT 84532
435.259.8171

STANDARD LEGEND

- BOUNDARY CORNER
- ✦ SECTION MONUMENT

PROJECT TYPE:
PROPOSED SITE PLAN
SURVEY

PROJECT ADDRESS:
KANE CREEK BLVD, MOAB, UTAH


PROJECT LOCATION:
GRAND COUNTY, STATE OF UTAH

PREPARED FOR:
KANE CREEK
PRESERVATION AND
DEVELOPMENT, LLC



DATE
5/12/25

SHEET 1 OF 5

JOB NUMBER:
068-24




PROPOSED SITE PLAN
TOWN OF ECHO CANYON
GRAND COUNTY, UTAH
LOCATED IN SECTIONS 10, 15, & 16, T26S, R21E, SLB&M



SURVEYOR'S CERTIFICATION

I, Lucas Blake, certify that I am a Professional Land Surveyor as prescribed under the laws of the State of Utah and that I hold license no. 7540504. I further certify that a boundary survey was made of the property described below, and the findings of that survey are as shown hereon.

Lucas Blake
License No. 7540504



Lucas Blake
License No. 7540504

5/12/2025
DATE

PHASE I BOUNDARY LEGAL DESCRIPTION

Beginning at the Southeast corner of Section 16, Township 26 South, Range 21 East, Salt Lake Base and Meridian, and running thence South 89°55'57" West 900.24 Feet, more or less, along the South Section line to the easterly Meander Line of the Colorado River; thence, more or less, along the Meander Line of the Colorado the following seventeen courses: thence North 29°10'14" East 455.98 feet; thence North 18°13'02" East 507.07 feet; thence North 10°28'53" East 319.21 feet; thence North 08°22'50" East 639.1 feet; thence North 10°24'57" East 395.02 feet; thence North 11°11'15" East 497.69 feet; thence North 16°36'17" East 711.07 feet; thence North 16°36'17" East 105.60 feet; thence North 15°49'52" East 601.74 feet; thence North 28°26'24" East 793.82 feet; thence North 31°37'04" East 610.29 feet; thence North 31°37'04" East 147.57 feet; thence North 40°00'29" East 596.83 feet; thence North 40°36'00" East 718.96 feet; thence North 39°33'54" East 464.01 feet; thence North 43°59'37" East 392.77 feet; thence North 56°42'42" East 294.90 feet to a point on the center section line of Section 10, T26S, R21E, SLBM; thence with said line South 36°43'49" West 204.46 feet; thence South 50°04'31" West 154.43 feet; thence South 44°42'46" West 167.10 feet; thence South 24°22'54" West 118.55 feet; thence South 00°13'42" West 94.73 feet; thence South 31°08'04" West 139.93 feet; thence South 34°42'06" West 48.44 feet; thence South 21°34'01" West 123.10 feet; thence South 22°49'39" West 153.51 feet; thence South 30°59'10" West 204.04 feet; thence South 11°08'56" West 264.27 feet; thence North 89°50'30" West 517.07 feet; thence South 00°03'18" West 589.37 feet; thence South 17°24'21" West 191.62 feet; thence South 25°43'20" West 829.96 feet; thence South 31°46'10" West 717.70 feet; thence South 24°47'40" West 1633.11 feet; thence North 14°27'55" West 867.21 feet; thence South 86°33'20" East 300.91 feet; thence North 53°44'16" East 93.79 feet; thence South 00°03'18" West 864.74 feet to the point of beginning, having an area 92.85 acres, more or less.

PHASE II BOUNDARY LEGAL DESCRIPTION

Beginning at the Southwest corner of the NW1/4SW1/4 of Section 15, Township 26 South, Range 21 East, Salt Lake Base and Meridian, said point being North 00°03'18" East along the section line 1319.80 feet from the Southwest corner of Section 15, Township 26 South, Range 21 East, Salt Lake Base and Meridian, and proceeding thence South 00°03'18" West 455.06 feet; thence South 53°44'16" West 93.79 feet; thence North 86°33'20" West 300.55 feet; thence North 14°26'30" East 867.14 feet; thence North 24°47'40" East 1633.11 feet; thence North 31°46'10" East 717.70 feet; thence North 25°43'20" East 829.96 feet; thence North 17°24'21" East 191.62 feet; thence South 00°03'18" West 2054.07 feet to the Northeast corner of the NW1/4SW1/4 of said Section 15; thence South 00°04'22" West 1321.74 feet to the Southeast corner of the NW1/4SW1/4 of said Section 15; thence North 89°46'18" West 1316.83 feet to the point of beginning, having an area of 67.10 acres, more or less.

PHASE III BOUNDARY LEGAL DESCRIPTION

beginning at the North Quarter corner of Section 15, Township 26 South, Range 21 East, Salt Lake Base and Meridian, and proceeding thence North 89°50'30" West 800.71 feet; thence North 11°08'56" East 264.27 feet; thence North 30°59'10" East 204.04 feet; thence North 22°49'39" East 153.51 feet; thence North 21°34'01" East 123.10 feet; thence North 34°42'06" East 48.44 feet; thence North 31°08'04" East 139.93 feet; thence North 36°04'17" East 54.71 feet; thence North 00°13'42" West 94.73 feet; thence North 24°22'54" East 118.55 feet; thence North 44°42'46" East 167.10 feet; thence North 50°04'31" East 154.43 feet; thence North 36°43'49" East 204.46 feet; thence South 00°01'48" East 1480.64 feet to the point of beginning, having an area of 16.42 acres, more or less.

TOGETHER WITH a 25' Access easement filed as BLM serial N. UTU-57320

PROJECT BOUNDARY LEGAL DESCRIPTION

Beginning at the Southeast corner of Section 16, Township 26 South, Range 21 East, Salt Lake Base and Meridian, and running thence South 89°55'57" West 900.24 Feet, more or less, along the South Section line to the easterly Meander Line of the Colorado River; thence, more or less, along the Meander Line of the Colorado the following seventeen courses: thence North 29°10'14" East 455.98 feet; thence North 18°13'02" East 507.07 feet; thence North 10°28'53" East 319.21 feet; thence North 08°22'50" East 639.1 feet; thence North 10°24'57" East 395.02 feet; thence North 11°11'15" East 497.69 feet; thence North 16°36'17" East 711.07 feet; thence North 16°36'17" East 105.60 feet; thence North 15°49'52" East 601.74 feet; thence North 28°26'24" East 793.82 feet; thence North 31°37'04" East 610.29 feet; thence North 31°37'04" East 147.57 feet; thence North 40°00'29" East 596.83 feet; thence North 40°36'00" East 718.96 feet; thence North 39°33'54" East 464.01 feet; thence North 43°59'37" East 392.77 feet; thence North 56°42'42" East 294.90 feet to a point on the center section line of Section 10, T26S, R21E, SLBM; thence with said line South 00°01'48" East 1935.64 feet to the South Quarter corner of said Section 10; thence North 89°50'30" West 1317.78 feet to the Northwest corner of the NE1/4NW1/4 of section 15, T26S, R21E, SLBM; thence South 00°03'18" West 2643.43 feet to the Northeast corner of the NW1/4SW1/4 of said Section 15; thence South 00°04'22" West 1321.74 feet to the Southeast corner of the NW1/4SW1/4 of said Section 15; thence North 89°46'18" West 1316.83 feet to the Southwest corner of the NW1/4SW1/4 of said Section 15; thence South 00°03'18" West 1319.80 feet to the point of beginning, having an area of 176.37 acres, more or less.

TOGETHER WITH a 25' Access easement filed as BLM serial N. UTU-57320

LOCATED WITHIN
SECTIONS 10, 15, & 16, T26S, R21E, SLB&M

SURVEYOR NOTES

THE BASIS OF BEARING IS NORTH 00°03'18" EAST BETWEEN THE SOUTHWEST CORNER AND THE WEST QUARTER CORNER OF SECTION 15, TOWNSHIP 26 SOUTH, RANGE 21 EAST, SALT LAKE BASE AND MERIDIAN.

THE INTENT OF THE SURVEY IS CREATE A BOUNDARY OF THE PROJECTS PHASED BOUNDARIES.

REFERENCED AND LOCATED MONUMENTS OF BLM SURVEY PLAT DATED FEBRUARY 7, 2012.

LEGEND

R-MU: MIXED USE, COMMERCIAL / AMENITY / CONDO	R-MF: RESIDENTIAL, CONDO
OA: OVERNIGHT ACCOMMODATIONS	R-AFH: RESIDENTIAL, AFFORDABLE HOUSING
R-SF: RESIDENTIAL, SINGLE-FAMILY DETACHED HOMES	HOA: HOA PROPERTY
R-TW: RESIDENTIAL, TWIN HOMES	ROW: RIGHTS-OF-WAY
R-TH: RESIDENTIAL, TOWNHOUSE	

PROJECT TYPE:
PROPOSED SITE PLAN
SURVEY

PROJECT ADDRESS:
KANE CREEK BLVD., MOAB, UTAH


PROJECT LOCATION:
GRAND COUNTY, STATE OF UTAH

PREPARED FOR:
KANE CREEK
PRESERVATION AND
DEVELOPMENT, LLC


DATE
5/12/25

SHEET 2 OF 5

JOB NUMBER:
068-24




2 PHASING PLAN
NTS



LEGEND

R-MU: MIXED USE, COMMERCIAL / AMENITY / CONDO	R-MF: RESIDENTIAL, CONDO
OA: OVERNIGHT ACCOMMODATIONS	R-AFH: RESIDENTIAL, AFFORDABLE HOUSING
R-SF: RESIDENTIAL, SINGLE-FAMILY DETACHED HOMES	HOA: HOA PROPERTY
R-TW: RESIDENTIAL, TWIN HOMES	ROW: RIGHTS-OF-WAY
R-TH: RESIDENTIAL, TOWNHOUSE	

1 MASTER PLAN



LEGEND

 R-MU: MIXED USE, COMMERCIAL / AMENITY / CONDO	 R-MF: RESIDENTIAL CONDO
 OA: OVERNIGHT ACCOMMODATIONS	 R-AFH: RESIDENTIAL, AFFORDABLE HOUSING
 R-SF: RESIDENTIAL, SINGLE-FAMILY DETACHED HOMES	 HOA: HOA PROPERTY
 R-TW: RESIDENTIAL, TWIN HOMES	 ROW: RIGHTS-OF-WAY
 R-TH: RESIDENTIAL, TOWNHOUSE	

PROJECT TYPE:
PROPOSED SITE PLAN
SURVEY

PROJECT ADDRESS:
KANE CREEK BLVD, MOAB, UTAH



PROJECT LOCATION:
GRAND COUNTY, STATE OF UTAH

PREPARED FOR:
KANE CREEK
PRESERVATION AND
DEVELOPMENT, LLC

DATE
5/12/25

SHEET 4 OF 5

JOB NUMBER:
068-24



LEGEND

 R-MU: MIXED USE, COMMERCIAL / AMENITY / CONDO	 R-MF: RESIDENTIAL, CONDO
 OA: OVERNIGHT ACCOMMODATIONS	 R-AFH: RESIDENTIAL, AFFORDABLE HOUSING
 R-SF: RESIDENTIAL, SINGLE-FAMILY DETACHED HOMES	 HOA: HOA PROPERTY
 R-TW: RESIDENTIAL, TWIN HOMES	 ROW: RIGHTS-OF-WAY
 R-TH: RESIDENTIAL, TOWNHOUSE	

PROJECT TYPE:
PROPOSED SITE PLAN
SURVEY

PROJECT ADDRESS:
KANE CREEK BLVD, MOAB, UTAH


PROJECT LOCATION:
GRAND COUNTY, STATE OF UTAH

PREPARED FOR:
KANE CREEK
PRESERVATION AND
DEVELOPMENT, LLC

DATE
5/12/25

SHEET 5 OF 5

JOB NUMBER:
068-24



PHASE III




Exhibit E-1
to Petition for Incorporation of Echo Canyon,
a Preliminary Municipality
Cash Deposit Agreement

**CASH DEPOSIT AND RESTRICTED USE AGREEMENT
TO GUARANTEE COMPLETION OF SYSTEM INFRASTRUCTURE FOR
ECHO CANYON, A PROPOSED PRELIMINARY MUNICIPALITY**

This “Cash Deposit and Restricted Use Agreement to Guarantee Completion of System Infrastructure for Echo Canyon, a Proposed Preliminary Municipality” (the “Agreement”) is made and entered into on this 18th day of March 2025, by and among:

Initial Landowners:

- (1) Kane Creek Preservation and Development LLC, a Delaware limited liability company;
- (2) G&H Miller Family Holdings LLC, a Utah limited liability company; and

Holder:

Echo Canyon Bond Guarantee Co, a Utah limited liability Company,

For the benefit of Beneficiary:

Echo Canyon, a Proposed Preliminary Municipality and upon the issuance of the certificate of incorporation, by the Lieutenant Governor of Utah, a preliminary municipality and political subdivision of the State of Utah.

Recitals:

- A. The Initial Landowners are submitting a Petition for Incorporation of Echo Canyon, A Preliminary Municipality (“**Petition**”) to the Lieutenant Governor of Utah.
- B. This Agreement is intended to satisfy the requirement under Utah Code Ann. § 10-2a-507(1)(h) that the Petition be accompanied by a cash deposit that:
 - i. is posted by the Initial Landowners;
 - ii. is in favor of Echo Canyon;
 - iii. guarantees that the Initial Landowners will complete the System Infrastructure (defined below in accordance with Utah Code Ann. § 10-2a-501(13)) no later than six years after the day on which the initial landowners file the petition for incorporation described in this section; and
 - iv. will be refunded to the initial landowners in percentages that reflect the progress toward completing the system infrastructure.
- C. The Holder and the Initial Owners wish to establish procedures including engineering review and approval and documentation to guarantee the appropriate use of the deposited funds.

Now, therefore, for good and valuable consideration, Kane Creek Preservation and Development LLC, G&H Miller Family Holdings LLC, and Echo Canyon Bond Guarantee Co. (collectively the “**Parties**” and each individually a “**Party**”) agree as follows:

Echo Canyon Cash Deposit and Restricted Use Agreement
Page 2 of 8

1. Cash Deposit

The Initial Landowners shall deposit an amount equal to three million six hundred twenty two thousand six hundred fifty-two dollars (\$3,622,652.00)¹ (the “**Deposit Funds**”) with Holder to be used to complete the System Infrastructure in accordance with this Agreement.

2. Use of Deposit Funds

- a. The Initial Landowners shall construct the System Infrastructure within Echo Canyon.
- b. The “**System Infrastructure**” means the main thoroughfares within Echo Canyon, including any necessary connections to an existing road outside the Echo Canyon area, and the main utility lines and related stubs connecting to main lines to the development, as shown on the map or plat included in the Feasibility Request submitted to the Utah Lieutenant Governor’s Office dated May 1, 2024. A copy of the map or plat depicting the System Infrastructure is attached as **Exhibit B**.
- c. Any remaining balance of the Deposit Funds, after covering the costs associated with finding or installing the conduit, shall be returned to the Seller.

3. Reduction of Deposit Funds

The Deposit Funds shall be withdrawn from the Holder’s account, payable to an Initial Landowner or designated contractor which has performed work on the System Infrastructure, for reimbursement or payment of costs and expenses incurred in constructing and installing the System Infrastructure (“**Progress Payments**”). To obtain a Progress Payment, the Initial Landowners shall submit an itemized invoice (“**Invoice**”) to the Holder, identifying the work done including a percentage toward completion of the total System Infrastructure, purchases made, and other costs incurred by the Initial Landowners in the construction and installation of the System Infrastructure. Each Invoice shall also include a verification of costs signed by the Echo Canyon municipal engineer in substantially the form attached hereto as **Exhibit C**. The Invoices may be submitted no more frequently than every 30 days. The Progress Payment shall be made within 30 days of submission of each invoice. If the Holder or Initial Landowners object to the content of an invoice, the objecting Party shall provide notice to all Parties no later than five (5) days after the Initial Landowners submitted the invoice. The Parties will negotiate in good faith to resolve the objection. If no resolution has been reached within 30 days of the objection, the Progress Payment shall be made according to the accounting provided by the Initial Landowners in the invoice.

4. Release of Deposit Funds

Upon completion of the System Infrastructure, and the submission of invoices or receipts for any associated costs, the Holder shall release the remaining Deposit Funds, if any, to the Initial

¹ The Deposit Funds are comprised of the Engineer’s Opinion of Probably Costs attached as **Exhibit A** plus a ten percent (10%) administrative allowance consistent with Utah Code Ann. § 10-9a-604.5.

Echo Canyon Cash Deposit and Restricted Use Agreement
Page 3 of 8

Landowners within 30 days. If the Agreement is terminated, the Holder shall release the remaining Deposit Funds, if any, to the Initial Landowners within ten (10) days.

5. Holder's Responsibilities

The Holder shall hold and disburse the Deposit Funds in accordance with this Agreement. The Holder may not be liable for any action taken or omitted in good faith and in the exercise of reasonable judgment.

6. Substitution of Holder of Deposit Funds

Within ten (10) days of the issuance of the certificate of approval of the Petition by the Lieutenant Governor of Utah and the execution of a writing, in substantially the form of attached **Exhibit D**, by Echo Canyon Preliminary Municipality of its acceptance of this Agreement the Deposit Funds will be transferred by Holder into an account of Echo Canyon Preliminary Municipality and Echo Canyon Preliminary Municipality shall replace Echo Canyon Bond Guarantee Co. as the Holder of the Deposit Funds. Thereafter Echo Canyon Preliminary Municipality shall be the Holder of Deposit Funds and subject to this Agreement.

7. Termination

This Agreement shall terminate upon the release of all Deposit Funds in accordance with this Agreement. This Agreement shall also terminate in the event that the Lieutenant Governor of Utah fails to issue a certificate establishing Echo Canyon as a Preliminary Municipality within the time periods prescribed in Utah Code Ann. § 10-2a-501 et seq.

8. Governing Law

This Agreement shall be governed by and construed in accordance with the laws of the State of Utah.

9. Time is of the Essence

Time shall be of the essence in the performance of this Agreement.

[signature page follows]

Echo Canyon Cash Deposit and Restricted Use Agreement
Page 4 of 8

IN WITNESS WHEREOF, the Parties hereto have executed this Agreement as of the day and year first above written.

INITIAL LANDOWNERS

KANE CREEK PRESERVATION AND
DEVELOPMENT LLC,
a Delaware limited liability company


DocuSigned by:
By: 
Name: Craig Weston
Its: General Partner

G&H MILLER FAMILY HOLDINGS LLC,
a Utah limited liability company

DocuSigned by:
By: 
Name: Greg Miller
Its: Manager

HOLDER

ECHO CANYON BOND GUARANTEE CO.,
a Utah limited liability company

DocuSigned by:
By: 
Name: Trent Arnold
Its: Manager

Echo Canyon Cash Deposit and Restricted Use Agreement
Page 5 of 8

Exhibit A
Engineer's Opinion of Probable Cost

Town of Echo Canyon, Utah
Opinion of Probable Cost
System Infrastructure Improvements
 March 6, 2025



CIVIL ENGINEERING

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT
1	GENERAL REQUIREMENTS				
2	Mobilization/Demobilization	1	LS	\$ 50,000	\$ 50,000
3	Construction Surveying	1	LS	\$ 35,000	\$ 35,000
4	Potholing	1	LS	\$ 25,000	\$ 25,000
5	Traffic Control	1	LS	\$ 50,000	\$ 50,000
6	Quality Control & Material Testing (Soils, Concrete, Asphalt, etc.)	1	LS	\$ 50,000	\$ 50,000
7	Stormwater Management, Erosion Control, Vegetation Establishment	1	LS	\$ 25,000	\$ 25,000
8	DEMOLITION / REMOVALS				
9	Asphalt demo	19000	SY	\$ 4	\$ 76,000
10	EARTHWORK				
11	Clearing and Grubbing Vegetation and Removal	12	ACRES	\$ 2,000	\$ 24,000
12	Excavation (Cut)	7500	CY	\$ 10	\$ 75,000
13	Embankment (Fill)	7500	CY	\$ 15	\$ 112,500
14	ROAD IMPROVEMENTS				
15	<i>Kane Creek Blvd - ~7,800 LF, 26' Paved Width</i>				
16	Asphalt Paving (4" depth)	5000	Tons	\$ 160	\$ 800,000
17	Base Course (Roadway, Shoulders, & Multi-Use Path)	10150	CY	\$ 45	\$ 456,750
18	Compacted Sub-Base Course (Roadway & Shoulders)	3707	CY	\$ 10	\$ 37,070
19	10' Multi-Use Path (3" HMA)	1500	Tons	\$ 160	\$ 240,000
20	Signage and Striping	1	LS	\$ 35,000	\$ 35,000
21	SEWER SYSTEM				
22	<i>Kane Creek Blvd:</i>				
23	4" Forcemain	7500	LF	\$ 60	\$ 450,000
24	8" Sewer Service Stub	14	EA	\$ 2,500	\$ 35,000
25	WATER SYSTEM				
26	<i>Kane Creek Blvd:</i>				
27	12" PVC Water Main	7500	LF	\$ 90	\$ 675,000
28	Water Main Stub	14	EA	\$ 3,000	\$ 42,000
29	DRY UTILITIES				
30	Gas Main	1	LS	\$ -	See Notes
31	Electric	1	LS	\$ -	See Notes
32	TOTAL COST				\$ 3,293,320

Notes:

- Based upon attached Site Plan Drawings dated March 2025 prepared by SET Engineering with collaboration from DTJ Design.
- All Improvements to be built per Utah APWA and GWSSA Standards and Specifications.
- Earthwork quantities do not include expansion or shrinkage.
- Major water and sewer utility infrastructure shall be completed by the Kane Springs Improvement District and are not include din this estimate.
- Water system installation is complete in place including all trenching, bedding, fittings, valves, tees, thrust blocks, etc.
- Existing Gas Main under Kane Creek Boulevard to remain in place and service development.
- Existing power lines to service development.




Echo Canyon Cash Deposit and Restricted Use Agreement
Page 6 of 8

Exhibit B
Map of System Infrastructure

NOTES:

1. KANE CREEK BOULEVARD SHALL ACT AS THE SOLE MAIN THOROUGHFARE FOR THE PROPOSED MUNICIPAL AREA. KANE CREEK BOULEVARD SHALL BE CONSIDERED AS THE EXISTING GRAND COUNTY, UTAH AND MOGAI, UTAH ROAD NETWORK.
2. WATER MAIN TO BE SERVICED BY WATER TANK TO BE INSTALLED AND MAINTAINED BY KANE SPRINGS IMPROVEMENT DISTRICT. INFRASTRUCTURE DIRECTLY RELATED TO THE WATER TANK AND CONNECTION TO THE WATER MAIN ARE NOT INCLUDED IN DRAWINGS OR COST ESTIMATES.
3. SEWER FORCE MAIN TO BE SERVICED BY A WASTEWATER TREATMENT PLANT, INSTALLED AND MAINTAINED BY KANE SPRINGS IMPROVEMENT DISTRICT. INFRASTRUCTURE DIRECTLY RELATED TO THE WASTEWATER TREATMENT PLANT AND CONNECTION TO THE SEWER FORCE MAIN ARE NOT INCLUDED IN DRAWINGS OR COST ESTIMATES.
4. GAS AND POWER TO BE PROVIDED BY EXISTING INFRASTRUCTURE.



GRAPHIC SCALE
0 125 250 FEET

North Arrow

North

ECHO CANYON TOWN PLANS
SYSTEM INFRASTRUCTURE IMPROVEMENTS
ECHO CANYON, UTAH

SBT
CIVIL ENGINEERING
UTAH COUNTY
UTAH

EXH-01
SHEET 1 OF 1
PROJECT NUMBER
DATE OF ISSUE
DRAWN BY JAS

Echo Canyon Cash Deposit and Restricted Use Agreement
Page 7 of 8

Exhibit C

Form of Requisition with Certification

Requisition No. ____ To Echo Canyon Bond Guarantee Co.

The undersigned hereby makes a requisition from the Holder's Account under the Cash Deposit and Restricted Use Agreement to Guarantee Completion of System Infrastructure for Echo Canyon, a Preliminary Municipality (the "Agreement"), and in support thereof states:

1. The amount requisitioned is \$ _____, representing ____ percent (___%) of the projected costs for the System Infrastructure.
2. The name and address of the person, firm, or corporation to whom payment is due or has been made is as follows:

3. Payment is due for _____, as detailed in the supporting documentation.
4. The above obligation has been properly incurred, is a proper charge against the Deposit Funds, and has not been the basis of any previous withdrawal.
5. The costs for which the disbursement is requested herein are authorized by the Agreement and constitute System Infrastructure.
7. No event of default or other basis for termination has occurred and is continuing under the Agreement, and no event or condition has occurred which, with notice of passage of time or both, would constitute an event of default under the Agreement.

Engineer's Certification

As a professional engineer licensed in the State of Utah, I hereby certify that:

- (1) I have reviewed the foregoing Requisition and all documentation in support thereof;
- (2) I have conducted any field examinations as I have deemed necessary to evaluate the Requisition, the supporting documentation, and the System Infrastructure related thereto; and
- (3) The costs described in the Requisition and supporting documentation are reasonable and consistent with the fair market value for the System Infrastructure.

On the basis of the foregoing certification, I hereby recommend that Echo Canyon approve the foregoing Requisition and submit the same for payment from the Deposit Proceeds.

REQUESTER

ENGINEER

By: _____

By: _____

Name:

Name:

Its:

Its:

Dated:

Dated:

Echo Canyon Cash Deposit and Restricted Use Agreement
Page 8 of 8

Exhibit D
Form of Echo Canyon's Acceptance
BOARD OF ECHO CANYON PRELIMINARY MUNICIPALITY

RESOLUTION NO. _____

A RESOLUTION OF THE BOARD OF ECHO CANYON PRELIMINARY MUNICIPALITY TO CONSENT TO AND ACCEPT CASH DEPOSIT FROM ECHO CANYON BOND GUARANTEE CO.

WHEREAS, Echo Canyon is a preliminary municipality under Utah Code Title 10, Chapter 2a, Part 5 (the "Code"); and

WHEREAS, the initial landowners of the area comprising Echo Canyon ("**Initial Landowners**") entered into an agreement with Echo Canyon Bond Guarantee Co. LLC entitled the "Cash Deposit and Restricted Use Agreement to Guarantee Completion of System Infrastructure for Echo Canyon, a Proposed Preliminary Municipality" dated March 18, 2025, (the "**Cash Deposit Agreement**") and deposited the sum of \$3,622,652.00 for the benefit of Echo Canyon; and

WHEREAS, at the time the Echo Canyon could not contract directly with the Initial Landowners because it did not legally exist; and

WHEREAS, the District agrees to accept the Cash Deposit on the terms described in the Cash Deposit Agreement subject to any amendments deemed necessary between Echo Canyon and the Initial Landowners.

NOW, THEREFORE, BE IT RESOLVED BY THE LEGISLATIVE BODY OF THE ECHO CANYON PRELIMINARY MUNICIPALITY AS FOLLOWS:

1. Echo Canyon Preliminary Municipality hereby accepts the terms of the Cash Deposit Agreement attached hereto as **Exhibit A**.
2. The Chair, other board members, and staff are hereby authorized to take such actions in accordance with the Cash Deposit Agreement as are necessary and appropriate to carry out the intent and terms to the benefit of Echo Canyon.
3. The District agrees that the donated real property will be used for a public purpose.
4. This Resolution takes effect upon adoption.

DATED this _____ day of _____, 2025.

Clerk

Chair

Exhibit E-2

**to Petition for Incorporation of Echo Canyon,
a Preliminary Municipality**

Engineer's Opinion and Map of System Infrastructure

Town of Echo Canyon, Utah
Opinion of Probable Cost
System Infrastructure Improvements
 March 6, 2025



CIVIL ENGINEERING

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT
1	GENERAL REQUIREMENTS				
2	Mobilization/Demobilization	1	LS	\$ 50,000	\$ 50,000
3	Construction Surveying	1	LS	\$ 35,000	\$ 35,000
4	Potholing	1	LS	\$ 25,000	\$ 25,000
5	Traffic Control	1	LS	\$ 50,000	\$ 50,000
6	Quality Control & Material Testing (Soils, Concrete, Asphalt, etc.)	1	LS	\$ 50,000	\$ 50,000
7	Stormwater Management, Erosion Control, Vegetation Establishment	1	LS	\$ 25,000	\$ 25,000
8	DEMOLITION / REMOVALS				
9	Asphalt demo	19000	SY	\$ 4	\$ 76,000
10	EARTHWORK				
11	Clearing and Grubbing Vegetation and Removal	12	ACRES	\$ 2,000	\$ 24,000
12	Excavation (Cut)	7500	CY	\$ 10	\$ 75,000
13	Embankment (Fill)	7500	CY	\$ 15	\$ 112,500
14	ROAD IMPROVEMENTS				
15	<i>Kane Creek Blvd - ~7,800 LF, 26' Paved Width</i>				
16	Asphalt Paving (4" depth)	5000	Tons	\$ 160	\$ 800,000
17	Base Course (Roadway, Shoulders, & Multi-Use Path)	10150	CY	\$ 45	\$ 456,750
18	Compacted Sub-Base Course (Roadway & Shoulders)	3707	CY	\$ 10	\$ 37,070
19	10' Multi-Use Path (3" HMA)	1500	Tons	\$ 160	\$ 240,000
20	Signage and Striping	1	LS	\$ 35,000	\$ 35,000
21	SEWER SYSTEM				
22	<i>Kane Creek Blvd:</i>				
23	4" Forcemain	7500	LF	\$ 60	\$ 450,000
24	8" Sewer Service Stub	14	EA	\$ 2,500	\$ 35,000
25	WATER SYSTEM				
26	<i>Kane Creek Blvd:</i>				
27	12" PVC Water Main	7500	LF	\$ 90	\$ 675,000
28	Water Main Stub	14	EA	\$ 3,000	\$ 42,000
29	DRY UTILITIES				
30	Gas Main	1	LS	\$ -	See Notes
31	Electric	1	LS	\$ -	See Notes
32	TOTAL COST				\$ 3,293,320

Notes:

- Based upon attached Site Plan Drawings dated March 2025 prepared by SET Engineering with collaboration from DTJ Design.
- All Improvements to be built per Utah APWA and GWSSA Standards and Specifications.
- Earthwork quantities do not include expansion or shrinkage.
- Major water and sewer utility infrastructure shall be completed by the Kane Springs Improvement District and are not include din this estimate.
- Water system installation is complete in place including all trenching, bedding, fittings, valves, tees, thrust blocks, etc.
- Existing Gas Main under Kane Creek Boulevard to remain in place and service development.
- Existing power lines to service development.



Exhibit E-3
to Petition for Incorporation of Echo Canyon,
a Preliminary Municipality
Proof of Funding

[Overview](#) / Account: ECHO CANYON GUARANTEE [REDACTED]

ECHO CANYON GUARANTEE [REDACTED]
ECHO CANYON BOND GUARANTEE CO. LLC

\$3,622,652.00

Available balance

\$3,622,652.00
Present balance

\$0.00
Available credit

\$3,622,652.00
Available plus credit

Uncollected funds

Transactions

Showing

If you have other transactions that aren't shown in your account activity, review your [monthly statements](#).

You've reached the end of your account activity.

J.P.Morgan

March 19, 2025

To whom it may concern:

This letter is to confirm that JPMorgan Chase Bank, N.A. has maintained a relationship with Echo Canyon Bond Guarantee Co. LLC since March 2025. As of the date of this letter, Echo Canyon Bond Guarantee Co. LLC has a current balance of \$3,622,652.

It has been my pleasure to have Echo Canyon Bond Guarantee Co. LLC as my client.

Please do not hesitate to contact me at (801) 715-7356.

Sincerely,

Danielle Wright
J.P. Morgan Private Bank

This reference letter and the information it provides are furnished on the condition that they are strictly confidential, and that no liability or responsibility shall attach to JPMorgan Chase & Co., its subsidiaries or affiliates, or any of its officers, employees or agents, in connection with their content. This letter makes no representation regarding the general condition of its subject, its management or its future ability to meet any obligations. The information presented has been obtained from sources believed to be reliable, without express or implied warranties as to its completeness or accuracy. We expressly disclaim any liability for errors and omissions regarding the information contained in this letter, and any information provided is subject to change, without notice. Any account balances provided in this letter reflect the asset value of such account, net of monies owed to us, excluding mortgages, and reflect the market price of such assets as of the latest practicable date.

Bank products and services, which may include bank-managed investment accounts and custody as part of its trust and fiduciary services, are offered through JPMorgan Chase Bank, N.A. and its affiliates.

Brokerage investment products and services are offered through J.P. Morgan Securities LLC, member FINRA and SIPC.



JPMorgan Chase Bank, N.A. Member FDIC

INVESTMENT PRODUCTS: • NOT FDIC INSURED • NO BANK GUARANTEE • MAY LOSE VALUE

0521-053-CR-EB

Exhibit F
to Petition for Incorporation of Echo Canyon,
a Preliminary Municipality
12/31/24 Invoice and Cost Detail



LEWIS | ROBERTSON | BURNINGHAM

INVOICE

CLIENT:
State of Utah PO# 060 2500000001 State Capitol Complex Ste E220 PO Box 142220, Salt Lake City UT 8414-22

INVOICE NO:	2024-0227A
INVOICE DATE:	12/31/2024
PROJECT:	State of Utah PO# 060 2500000001 Kane Creek Incorporation Feasibility Study

DESCRIPTION OF SERVICES	FEE
For consulting services related to State of Utah, PO#: 060 2500000001, Kane Creek Incorporation, Feasibility Study. Please see attachment for details.	21,910.00

TOTAL AMOUNT DUE:	\$21,910.00
--------------------------	-------------

PLEASE REMIT PAYMENT TO:
LRB PUBLIC FINANCE ADVISORS, INC. 41 N. RIO GRANDE, SUITE 101 SALT LAKE CITY, UT 84101
WIRE TRANSFER INSTRUCTIONS:
ABA #: 324079555
CREDIT BANK: Mountain America Credit Union
CREDIT ACCOUNT #: #501010782570
CREDIT ACCOUNT NAME: LRB Public Finance Advisors, Inc.

AUTHORIZED BY: _____



PAYMENT HISTORY			
Invoice	Date	Invoiced	Paid
2024-0227A	12/31/2024	\$ 21,910.00	\$ -

GENERAL INFORMATION	
Client:	State of Utah, Lt. Governor's Office PO 060 2500000001 ST CAPITOL COMPLEX STE E220 P O Box 142220, Salt Lake City UT 84114-2220
Project Description:	Kane Creek Incorporation Feasibility Study
Invoice Date:	12/31/2024
Invoice Number:	2024-0227A
Primary LRB Contact:	Fred Philpot
Project Lead	Logan Loftis

CURRENT INVOICE 2024-0227A		
Percent	Amount	Remaining
100%	\$ 2,040.00	\$ -
100%	3,240.00	-
100%	6,700.00	-
100%	7,600.00	-
50%	2,330.00	2,330.00
Total	\$ 21,910.00	\$ 2,330.00

TOTAL INVOICED (including current)		
Percent	Amount	Remaining
100%	\$ 2,040.00	\$ -
100%	3,240.00	-
100%	6,700.00	-
100%	7,600.00	-
50%	2,330.00	2,330.00
Total	\$21,910.00	\$ 2,330.00
Total Paid	\$ -	
Total Due	\$21,910.00	

PROJECT TASKS		
Tasks	Fee per Task	
Task 1	Task 1: Initial Scoping Meeting	\$ 2,040.00
Task 2	Task 2: Demographic Analysis (Population and Density)	3,240.00
Task 3	Task 3: Review & Forecast Cost of Government Services	6,700.00
Task 4	Task 4: Fiscal/Tax Impacts	7,600.00
Task 5	Task 5: Written Report and Presentation (One Meeting)	4,660.00
TOTALS		\$ 24,240.00

Exhibit G

**to Petition for Incorporation of Echo Canyon,
a Preliminary Municipality
*Check for Payment of Lt. Governor Costs***

KANE CREEK PRESERVATION AND DEVELOPMENT

97-154/1240

DATE MARCH 25

PAY TO THE ORDER OF

LIEUTENANT GOVERNOR of UTAH \$ 24,240.⁰⁰

TWENTY FOUR THOUSAND TWO HUNDRED FORTY DOLLARS

CHASE
JPMorgan Chase Bank, N.A.
www.Chase.com

MEMO LRB REIMBURSEMENT

MP

